

**TABLE OF CONTENTS**

TITLE	INDEX OF PAGES
-------	----------------

---

**General Contract Provisions**

Section 10 – Definition of Terms.....	GP-1-8
Section 20 – Proposal Requirements and Conditions .....	GP-9-12
Section 30 – Award and Execution of Contract.....	GP-13-14
Section 40 – Scope of Work .....	GP-15-18
Section 50 – Control of Work.....	GP-19-24
Section 60 – Control of Materials.....	GP-25-28
Section 70 – Legal Regulations and Responsibility to Public .....	GP-29-34
Section 80 – Execution and Progress.....	GP-35-40
Section 90 – Measurement and Payment .....	GP-41-48

**Special Provisions**

Section 1 – Project Information .....	SP-1-12
Section 2 – Insurance Requirements.....	SP-13-14
Section 3 – Miscellaneous .....	SP-15-20
Section 4 – Listing of Duties, Responsibilities and Limitations of Authority of the Resident Project Representative.....	SP-21-24
Section 5 – Construction Safety and Phasing Plan (CSPP) .....	SP-25-26

**Technical Specifications**

C-100 Contractor Quality Control Program (CQCP).....	C-100-1-8
C-102 Temporary Air and Water Pollution, Soil Erosion, and Siltation Control .....	C-102-1-4
C-103 Safety and Security .....	C-103-1-8
C-104 Project Stakeout and As-Built Survey .....	C-104-1-6
C-105 Mobilization.....	C-105-1-2
C-106 Temporary Construction Items .....	C-106-1-4
C-110 Method of Estimating Percentage of Material Within Specification Limits (PWL).....	C-110-1-8
P-100 Airport Utilities General Provisions.....	P-100-1-2
P-101 Preparation/Removal of Existing Pavements .....	P-101-1-6
P-152 Excavation, Subgrade, and Embankment .....	P-152-1-8
P-209 Crushed Aggregate Base Course .....	P-209-1-6
P-401 Asphalt Mix Pavement .....	P-401-1-22
P-403 Asphalt Mix Pavement Base Course .....	P-403-1-20
P-501 Cement Concrete Pavement .....	P-501-1-34
P-603 Emulsified Asphalt Tack Coat.....	P-603-1-4
P-604 Compression Joint Seals for Concrete Pavement .....	P-604-1-6

TABLE OF CONTENTS

TITLE	INDEX OF PAGES
<b><u>Technical Specifications</u></b>	
P-605 Joint Sealants for Pavements .....	P-605-1-4
P-610 Concrete for Miscellaneous Structures .....	P-610-1-8
P-620 Runway and Taxiway Marking .....	P-620-1-6
 D-701 Pipe for Storm Drains and Culverts .....	 D-701-1-8
D-751 Manholes, Catch Basins, Inlets, and Inspection Holes .....	D-751-1-6

## CHANGES TO STANDARD FAA SPECIFICATIONS

**\*\*Note:** Specification sections have been modified from FAA standards as specified in Advisory Circular 150/5370-10H, *Standards for Specifying Construction of Airports*.

Text that has been deleted is shown using single line strikethrough. (e.g., ~~Sample Text~~)

Text that has been added is shown as blue and highlighted in grey. (e.g., **Sample Text**)

Text that has been deleted with strikethrough shall be treated as if it is not shown.

Text that has been added in blue and highlighted with grey shall be treated equivalently to any other information or requirements provided in the specifications.

Information selected from choices provided in the standard specification (“engineer notes”) is shown as normal text.

The following specification sections have been added to supplement the FAA standard technical specifications:

### SPECIAL PROVISIONS

ITEM C-103	SAFETY AND SECURITY
ITEM C-104	PROJECT STAKEOUT & AS-BUILT SURVEY
ITEM C-106	TEMPORARY CONSTRUCTION ITEMS
ITEM P-100	AIRPORT UTILITIES GENERAL PROVISIONS

## General Provisions



### Section 10 Definition of Terms

When the following terms are used in these specifications, in the contract, or in any documents or other instruments pertaining to construction where these specifications govern, the intent and meaning shall be defined as follows:

<b>Paragraph Number</b>	<b>Term</b>	<b>Definition</b>
<b>10-01</b>	<b>AASHTO</b>	The American Association of State Highway and Transportation Officials.
<b>10-02</b>	<b>Access Road</b>	The right-of-way, the roadway and all improvements constructed thereon connecting the airport to a public roadway.
<b>10-03</b>	<b>Advertisement</b>	A public announcement, as required by local law, inviting bids for work to be performed and materials to be furnished.
<b>10-04</b>	<b>Airport</b>	Airport means an area of land or water which is used or intended to be used for the landing and takeoff of aircraft; an appurtenant area used or intended to be used for airport buildings or other airport facilities or rights of way; airport buildings and facilities located in any of these areas, and a heliport.
<b>10-05</b>	<b>Airport Improvement Program (AIP)</b>	A grant-in-aid program, administered by the Federal Aviation Administration (FAA).
<b>10-06</b>	<b>Air Operations Area (AOA)</b>	The term air operations area (AOA) shall mean any area of the airport used or intended to be used for the landing, takeoff, or surface maneuvering of aircraft. An air operation area shall include such paved or unpaved areas that are used or intended to be used for the unobstructed movement of aircraft in addition to its associated runway, taxiway, or apron.
<b>10-07</b>	<b>Apron</b>	Area where aircraft are parked, unloaded or loaded, fueled and/or serviced.
<b>10-08</b>	<b>ASTM International (ASTM)</b>	Formerly known as the American Society for Testing and Materials (ASTM).
<b>10-09</b>	<b>Award</b>	The Owner's notice to the successful bidder of the acceptance of the submitted bid.

<b>Paragraph Number</b>	<b>Term</b>	<b>Definition</b>
<b>10-10</b>	<b>Bidder</b>	Any individual, partnership, firm, or corporation, acting directly or through a duly authorized representative, who submits a proposal for the work contemplated.
<b>10-11</b>	<b>Building Area</b>	An area on the airport to be used, considered, or intended to be used for airport buildings or other airport facilities or rights-of-way together with all airport buildings and facilities located thereon.
<b>10-12</b>	<b>Calendar Day</b>	Every day shown on the calendar.
<b>10-13</b>	<b>Certificate of Analysis (COA)</b>	The COA is the manufacturer's Certificate of Compliance (COC) including all applicable test results required by the specifications.
<b>10-14</b>	<b>Certificate of Compliance (COC)</b>	The manufacturer's certification stating that materials or assemblies furnished fully comply with the requirements of the contract. The certificate shall be signed by the manufacturer's authorized representative.
<b>10-15</b>	<b>Change Order</b>	A written order to the Contractor covering changes in the plans, specifications, or proposal quantities and establishing the basis of payment and contract time adjustment, if any, for work within the scope of the contract and necessary to complete the project.
<b>10-16</b>	<b>Contract</b>	<p>A written agreement between the Owner and the Contractor that establishes the obligations of the parties including but not limited to performance of work, furnishing of labor, equipment and materials and the basis of payment.</p> <p>The awarded contract includes but may not be limited to: Advertisement, Contract form, Proposal, Performance bond, payment bond, General provisions, certifications and representations, Technical Specifications, Plans, Supplemental Provisions, standards incorporated by reference and issued addenda.</p>
<b>10-17</b>	<b>Contract Item (Pay Item)</b>	A specific unit of work for which a price is provided in the contract.

<b>10-18</b>	<b>Contract Time</b>	The number of calendar days or working days, stated in the proposal, allowed for completion of the contract, including authorized time extensions. If a calendar date of completion is stated in the proposal, in lieu of a number of calendar or working days, the contract shall be completed by that date.
<b>10-19</b>	<b>Contractor</b>	The individual, partnership, firm, or corporation primarily liable for the acceptable performance of the work contracted and for the payment of all legal debts pertaining to the work who acts directly or through lawful agents or employees to complete the contract work.
<b>10-20</b>	<b>Contractors Quality Control (QC) Facilities</b>	The Contractor's QC facilities in accordance with the Contractor Quality Control Program (CQCP).
<b>10-21</b>	<b>Contractor Quality Control Program (CQCP)</b>	Details the methods and procedures that will be taken to assure that all materials and completed construction required by the contract conform to contract plans, technical specifications and other requirements, whether manufactured by the Contractor, or procured from subcontractors or vendors.
<b>10-22</b>	<b>Control Strip</b>	A demonstration by the Contractor that the materials, equipment, and construction processes results in a product meeting the requirements of the specification.
<b>10-23</b>	<b>Construction Safety and Phasing Plan (CSPP)</b>	The overall plan for safety and phasing of a construction project developed by the airport operator, or developed by the airport operator's consultant and approved by the airport operator. It is included in the invitation for bids and becomes part of the project specifications.
<b>10-24</b>	<b>Drainage System</b>	The system of pipes, ditches, and structures by which surface or subsurface waters are collected and conducted from the airport area.
<b>10-25</b>	<b>Engineer</b>	The individual, partnership, firm, or corporation duly authorized by the Owner to be responsible for engineering, inspection, and/or observation of the contract work and acting directly or through an authorized representative.
<b>10-26</b>	<b>Equipment</b>	All machinery, together with the necessary supplies for upkeep and maintenance; and all tools and apparatus necessary for the proper construction and acceptable completion of the work.

<b>10-27</b>	<b>Extra Work</b>	An item of work not provided for in the awarded contract as previously modified by change order or supplemental agreement, but which is found by the Owner's Engineer or Resident Project Representative (RPR) to be necessary to complete the work within the intended scope of the contract as previously modified.
<b>10-28</b>	<b>FAA</b>	The Federal Aviation Administration. When used to designate a person, FAA shall mean the Administrator or their duly authorized representative.
<b>10-29</b>	<b>Federal Specifications</b>	The federal specifications and standards, commercial item descriptions, and supplements, amendments, and indices prepared and issued by the General Services Administration.
<b>10-30</b>	<b>Force Account</b>	<p><b>a.</b> Contract Force Account - A method of payment that addresses extra work performed by the Contractor on a time and material basis.</p> <p><b>b.</b> Owner Force Account - Work performed for the project by the Owner's employees.</p>
<b>10-31</b>	<b>Intention of Terms</b>	<p>Whenever, in these specifications or on the plans, the words "directed," "required," "permitted," "ordered," "designated," "prescribed," or words of like import are used, it shall be understood that the direction, requirement, permission, order, designation, or prescription of the Engineer and/or Resident Project Representative (RPR) is intended; and similarly, the words "approved," "acceptable," "satisfactory," or words of like import, shall mean approved by, or acceptable to, or satisfactory to the Engineer and/or RPR, subject in each case to the final determination of the Owner.</p> <p>Any reference to a specific requirement of a numbered paragraph of the contract specifications or a cited standard shall be interpreted to include all general requirements of the entire section, specification item, or cited standard that may be pertinent to such specific reference.</p>
<b>10-32</b>	<b>Lighting</b>	A system of fixtures providing or controlling the light sources used on or near the airport or within the airport buildings. The field lighting includes all luminous signals, markers, floodlights, and illuminating devices used on or near the airport or to aid in the operation of aircraft landing at, taking off from, or taxiing on the airport surface.

<b>10-32a</b>	<b>Liquidated Damages</b>	Monetary damages paid by the Contractor to the Owner for each calendar day after the applicable contract time has elapsed until the work is completed and accepted by the Owner and RPR.
<b>10-33</b>	<b>Major and Minor Contract Items</b>	A major contract item shall be any item that is listed in the proposal, the total cost of which is equal to or greater than 20% of the total amount of the award contract. All other items shall be considered minor contract items.
<b>10-34</b>	<b>Materials</b>	Any substance specified for use in the construction of the contract work.
<b>10-35</b>	<b>Modification of Standards (MOS)</b>	Any deviation from standard specifications applicable to material and construction methods in accordance with FAA Order 5300.1.
<b>10-36</b>	<b>Notice to Proceed (NTP)</b>	A written notice to the Contractor to begin the actual contract work on a previously agreed to date. If applicable, the Notice to Proceed shall state the date on which the contract time begins.
<b>10-37</b>	<b>Owner</b>	The term “Owner” shall mean the party of the first part or the contracting agency signatory to the contract. Where the term “Owner” is capitalized in this document, it shall mean airport Sponsor only. The Owner for this project is The Charlottesville-Albemarle Authority Board.
<b>10-38</b>	<b>Passenger Facility Charge (PFC)</b>	Per 14 Code of Federal Regulations (CFR) Part 158 and 49 United States Code (USC) § 40117, a PFC is a charge imposed by a public agency on passengers enplaned at a commercial service airport it controls.
<b>10-39</b>	<b>Pavement Structure</b>	The combined surface course, base course(s), and subbase course(s), if any, considered as a single unit.
<b>10-40</b>	<b>Payment bond</b>	The approved form of security furnished by the Contractor and their own surety as a guaranty that the Contractor will pay in full all bills and accounts for materials and labor used in the construction of the work.
<b>10-41</b>	<b>Performance bond</b>	The approved form of security furnished by the Contractor and their own surety as a guaranty that the Contractor will complete the work in accordance with the terms of the contract.

<b>10-42</b>	<b>Plans</b>	The official drawings or exact reproductions which show the location, character, dimensions and details of the airport and the work to be done and which are to be considered as a part of the contract, supplementary to the specifications. Plans may also be referred to as 'contract drawings.'
<b>10-43</b>	<b>Project</b>	The agreed scope of work for accomplishing specific airport development with respect to a particular airport.
<b>10-44</b>	<b>Proposal</b>	The written offer of the bidder (when submitted on the approved proposal form) to perform the contemplated work and furnish the necessary materials in accordance with the provisions of the plans and specifications.
<b>10-45</b>	<b>Proposal guaranty</b>	The security furnished with a proposal to guarantee that the bidder will enter into a contract if their own proposal is accepted by the Owner.
<b>10-46</b>	<b>Quality Assurance (QA)</b>	Owner's responsibility to assure that construction work completed complies with specifications for payment.
<b>10-47</b>	<b>Quality Control (QC)</b>	Contractor's responsibility to control material(s) and construction processes to complete construction in accordance with project specifications.
<b>10-48</b>	<b>Quality Assurance (QA) Inspector</b>	An authorized representative of the Engineer and/or Resident Project Representative (RPR) assigned to make all necessary inspections, observations, tests, and/or observation of tests of the work performed or being performed, or of the materials furnished or being furnished by the Contractor.
<b>10-49</b>	<b>Quality Assurance (QA) Laboratory</b>	The official quality assurance testing laboratories of the Owner or such other laboratories as may be designated by the Engineer or RPR. May also be referred to as Engineer's, Owner's, or QA Laboratory.
<b>10-50</b>	<b>Resident Project Representative (RPR)</b>	The individual, partnership, firm, or corporation duly authorized by the Owner to be responsible for all necessary inspections, observations, tests, and/or observations of tests of the contract work performed or being performed, or of the materials furnished or being furnished by the Contractor, and acting directly or through an authorized representative.
<b>10-51</b>	<b>Runway</b>	The area on the airport prepared for the landing and takeoff of aircraft.

<b>10-52</b>	<b>Runway Safety Area (RSA)</b>	A defined surface surrounding the runway prepared or suitable for reducing the risk of damage to aircraft. See the construction safety and phasing plan (CSPP) for limits of the RSA.
<b>10-53</b>	<b>Safety Plan Compliance Document (SPCD)</b>	Details how the Contractor will comply with the CSPP.
<b>10-54</b>	<b>Specifications</b>	A part of the contract containing the written directions and requirements for completing the contract work. Standards for specifying materials or testing which are cited in the contract specifications by reference shall have the same force and effect as if included in the contract physically.
<b>10-55</b>	<b>Sponsor</b>	A Sponsor is defined in 49 USC § 47102(24) as a public agency that submits to the FAA for an AIP grant; or a private Owner of a public-use airport that submits to the FAA an application for an AIP grant for the airport.
<b>10-56</b>	<b>Structures</b>	Airport facilities such as bridges; culverts; catch basins, inlets, retaining walls, cribbing; storm and sanitary sewer lines; water lines; underdrains; electrical ducts, manholes, handholes, lighting fixtures and bases; transformers; navigational aids; buildings; vaults; and, other manmade features of the airport that may be encountered in the work and not otherwise classified herein.
<b>10-57</b>	<b>Subgrade</b>	The soil that forms the pavement foundation.
<b>10-58</b>	<b>Superintendent</b>	The Contractor's executive representative who is present on the work during progress, authorized to receive and fulfill instructions from the RPR, and who shall supervise and direct the construction.
<b>10-59</b>	<b>Supplemental Agreement</b>	A written agreement between the Contractor and the Owner that establishes the basis of payment and contract time adjustment, if any, for the work affected by the supplemental agreement. A supplemental agreement is required if: (1) in scope work would increase or decrease the total amount of the awarded contract by more than 25%; (2) in scope work would increase or decrease the total of any major contract item by more than 25%; (3) work that is not within the scope of the originally awarded contract; or (4) adding or deleting of a major contract item.
<b>10-60</b>	<b>Surety</b>	The corporation, partnership, or individual, other than the Contractor, executing payment or performance bonds that are furnished to the Owner by the Contractor.

<b>10-61</b>	<b>Taxilane</b>	A taxiway designed for low speed movement of aircraft between aircraft parking areas and terminal areas.
<b>10-62</b>	<b>Taxiway</b>	The portion of the air operations area of an airport that has been designated by competent airport authority for movement of aircraft to and from the airport's runways, aircraft parking areas, and terminal areas.
<b>10-63</b>	<b>Taxiway/Taxilane Safety Area (TSA)</b>	A defined surface alongside the taxiway prepared or suitable for reducing the risk of damage to an aircraft. See the construction safety and phasing plan (CSPP) for limits of the TSA.
<b>10-64</b>	<b>Work</b>	The furnishing of all labor, materials, tools, equipment, and incidentals necessary or convenient to the Contractor's performance of all duties and obligations imposed by the contract, plans, and specifications.
<b>10-65</b>	<b>Working day</b>	A working day shall be any day other than a legal holiday, Saturday, or Sunday on which the normal working forces of the Contractor may proceed with regular work for at least six (6) hours toward completion of the contract. When work is suspended for causes beyond the Contractor's control, it will not be counted as a working day. Saturdays, Sundays and holidays on which the Contractor's forces engage in regular work will be considered as working days.
<b>10-66</b>	<b>Owner Defined terms</b>	None

**END OF SECTION 10**



## Section 20 Proposal Requirements and Conditions

**20-01 Advertisement (Notice to Bidders).** Refer to the Invitation to Bid.

**20-02 Qualification of bidders.** Each bidder shall submit evidence of competency and evidence of financial responsibility to perform the work to the Owner at the time of bid opening.

Evidence of competency, unless otherwise specified, shall consist of statements covering the bidder's past experience on similar work, and a list of equipment and a list of key personnel that would be available for the work.

Each bidder shall furnish the Owner satisfactory evidence of their financial responsibility. Evidence of financial responsibility, unless otherwise specified, shall consist of a confidential statement or report of the bidder's financial resources and liabilities as of the last calendar year or the bidder's last fiscal year. Such statements or reports shall be certified by a public accountant. At the time of submitting such financial statements or reports, the bidder shall further certify whether their financial responsibility is approximately the same as stated or reported by the public accountant. If the bidder's financial responsibility has changed, the bidder shall qualify the public accountant's statement or report to reflect the bidder's true financial condition at the time such qualified statement or report is submitted to the Owner.

Unless otherwise specified, a bidder may submit evidence that they are prequalified with the State Highway Division and are on the current "bidder's list" of the state in which the proposed work is located. Evidence of State Highway Division prequalification may be submitted as evidence of financial responsibility in lieu of the certified statements or reports specified above.

**20-03 Contents of proposal forms.** The Owner's proposal forms state the location and description of the proposed construction; the place, date, and time of opening of the proposals; and the estimated quantities of the various items of work to be performed and materials to be furnished for which unit bid prices are asked. The proposal form states the time in which the work must be completed, and the amount of the proposal guaranty that must accompany the proposal. The Owner will accept only those Proposals properly executed on physical forms or electronic forms provided by the Owner. Bidder actions that may cause the Owner to deem a proposal irregular are given in paragraph 20-09 *Irregular proposals*.

Mobilization is limited to 10 percent of the total project cost.

A prebid conference is **optional** on this project to discuss as a minimum, the following items: material requirements; submittals; Quality Control/Quality Assurance requirements; the construction safety and phasing plan including airport access and staging areas; and unique airfield paving construction requirements. **There will be two (2) required prebid conferences, each to be held at CHO at an agreed upon date and time between involved parties.**

**20-04 Issuance of proposal forms.** The Owner reserves the right to refuse to issue a proposal form to a prospective bidder if the bidder is in default for any of the following reasons:

- a. Failure to comply with any prequalification regulations of the Owner, if such regulations are cited, or otherwise included, in the proposal as a requirement for bidding.
- b. Failure to pay, or satisfactorily settle, all bills due for labor and materials on former contracts in force with the Owner at the time the Owner issues the proposal to a prospective bidder.
- c. Documented record of Contractor default under previous contracts with the Owner.

d. Documented record of unsatisfactory work on previous contracts with the Owner.

**20-05 Interpretation of estimated proposal quantities.** An estimate of quantities of work to be done and materials to be furnished under these specifications is given in the proposal. It is the result of careful calculations and is believed to be correct. It is given only as a basis for comparison of proposals and the award of the contract. The Owner does not expressly, or by implication, agree that the actual quantities involved will correspond exactly therewith; nor shall the bidder plead misunderstanding or deception because of such estimates of quantities, or of the character, location, or other conditions pertaining to the work. Payment to the Contractor will be made only for the actual quantities of work performed or materials furnished in accordance with the plans and specifications. It is understood that the quantities may be increased or decreased as provided in the Section 40, paragraph 40-02, Alteration of Work and Quantities, without in any way invalidating the unit bid prices.

**20-06 Examination of plans, specifications, and site.** The bidder is expected to carefully examine the site of the proposed work, the proposal, plans, specifications, and contract forms. Bidders shall satisfy themselves to the character, quality, and quantities of work to be performed, materials to be furnished, and to the requirements of the proposed contract. The submission of a proposal shall be prima facie evidence that the bidder has made such examination and is satisfied to the conditions to be encountered in performing the work and the requirements of the proposed contract, plans, and specifications.

Boring logs and other records of subsurface investigations and tests are available [in the appendix of the project manual](#) for inspection of bidders. It is understood and agreed that such subsurface information, whether included in the plans, specifications, or otherwise made available to the bidder, was obtained and is intended for the Owner's design and estimating purposes only. Such information has been made available for the convenience of all bidders. It is further understood and agreed that each bidder is solely responsible for all assumptions, deductions, or conclusions which the bidder may make or obtain from their own examination of the boring logs and other records of subsurface investigations and tests that are furnished by the Owner.

**20-07 Preparation of proposal.** The bidder shall submit their proposal on the forms furnished by the Owner. All blank spaces in the proposal forms, unless explicitly stated otherwise, must be correctly filled in where indicated for each and every item for which a quantity is given. The bidder shall state the price (written in ink or typed) both in words and numerals which they propose for each pay item furnished in the proposal. In case of conflict between words and numerals, the words, unless obviously incorrect, shall govern.

The bidder shall correctly sign the proposal in ink. If the proposal is made by an individual, their name and post office address must be shown. If made by a partnership, the name and post office address of each member of the partnership must be shown. If made by a corporation, the person signing the proposal shall give the name of the state where the corporation was chartered and the name, titles, and business address of the president, secretary, and the treasurer. Anyone signing a proposal as an agent shall file evidence of their authority to do so and that the signature is binding upon the firm or corporation.

**20-08 Responsive and responsible bidder.** A responsive bid conforms to all significant terms and conditions contained in the Owner's invitation for bid. It is the Owner's responsibility to decide if the exceptions taken by a bidder to the solicitation are material or not and the extent of deviation it is willing to accept.

A responsible bidder has the ability to perform successfully under the terms and conditions of a proposed procurement, as defined in 2 CFR § 200.318(h). This includes such matters as Contractor integrity, compliance with public policy, record of past performance, and financial and technical resources.

**20-09 Irregular proposals.** Proposals shall be considered irregular for the following, [but not limited to](#), reasons:

a. If the proposal is on a form other than that furnished by the Owner, or if the Owner's form is altered, or if any part of the proposal form is detached.

b. If there are unauthorized additions, conditional or alternate pay items, or irregularities of any kind that make the proposal incomplete, indefinite, or otherwise ambiguous.

c. If the proposal does not contain a unit price for each pay item listed in the proposal, except in the case of authorized alternate pay items, for which the bidder is not required to furnish a unit price.

d. If the proposal contains unit prices that are obviously unbalanced, *as interpreted by the Owner and Engineer*.

e. If the proposal is not accompanied by the proposal guaranty specified by the Owner.

f. If the applicable Disadvantaged Business Enterprise information is incomplete.

The Owner reserves the right to reject any irregular proposal and the right to waive technicalities if such waiver is in the best interest of the Owner and conforms to local laws and ordinances pertaining to the letting of construction contracts.

**20-10 Bid guarantee.** Each separate proposal shall be accompanied by a bid bond, certified check, or other specified acceptable collateral, in the amount specified in the proposal form. Such bond, check, or collateral, shall be made payable to the Owner.

**20-11 Delivery of proposal.** Each proposal submitted shall be placed in a sealed envelope plainly marked with the project number, location of airport, and name and business address of the bidder on the outside. When sent by mail, preferably registered, the sealed proposal, marked as indicated above, should be enclosed in an additional envelope. No proposal will be considered unless received at the place specified in the advertisement or as modified by Addendum before the time specified for opening all bids. Proposals received after the bid opening time shall be returned to the bidder unopened.

**20-12 Withdrawal or revision of proposals.** A bidder may withdraw or revise (by withdrawal of one proposal and submission of another) a proposal provided that the bidder's request for withdrawal is received by the Owner in writing by email before the time specified for opening bids. Revised proposals must be received at the place specified in the advertisement before the time specified for opening all bids.

**20-13 Public opening of proposals.** Proposals shall be opened, and read, publicly at the time and place specified in the advertisement. Bidders, their authorized agents, and other interested persons are invited to attend. Proposals that have been withdrawn (by written or telegraphic request) or received after the time specified for opening bids shall be returned to the bidder unopened.

**20-14 Disqualification of bidders.** A bidder shall be considered disqualified for any of the following, *but not limited to*, reasons:

a. Submitting more than one proposal from the same partnership, firm, or corporation under the same or different name.

b. Evidence of collusion among bidders. Bidders participating in such collusion shall be disqualified as bidders for any future work of the Owner until any such participating bidder has been reinstated by the Owner as a qualified bidder.

c. If the bidder is considered to be in "default" for any reason specified in paragraph 20-04, *Issuance of Proposal Forms*, of this section.

**20-15 Discrepancies and Omissions.** A Bidder who discovers discrepancies or omissions with the project bid documents shall immediately notify the Owner's Engineer of the matter. A bidder that has doubt as to the true meaning of a project requirement may submit to the Owner's Engineer a written request for interpretation no later than seven (7) days prior to bid opening.

Any interpretation of the project bid documents by the Owner's Engineer will be by written addendum issued by the Owner. The Owner will not consider any instructions, clarifications or interpretations of the bidding documents in any manner other than written addendum.

**END OF SECTION 20**

## Section 30 Award and Execution of Contract

**30-01 Consideration of proposals.** After the proposals are publicly opened and read, they will be compared on the basis of the summation of the products obtained by multiplying the estimated quantities shown in the proposal by the unit bid prices. If a bidder's proposal contains a discrepancy between unit bid prices written in words and unit bid prices written in numbers, the unit bid price written in words shall govern.

Until the award of a contract is made, the Owner reserves the right to reject a bidder's proposal for any of the following reasons:

a. If the proposal is irregular as specified in Section 20, paragraph 20-09, *Irregular Proposals*.

b. If the bidder is disqualified for any of the reasons specified Section 20, paragraph 20-14, *Disqualification of Bidders*.

In addition, until the award of a contract is made, the Owner reserves the right to reject any or all proposals, waive technicalities, if such waiver is in the best interest of the Owner and is in conformance with applicable state and local laws or regulations pertaining to the letting of construction contracts; advertise for new proposals; or proceed with the work otherwise. All such actions shall promote the Owner's best interests.

**30-02 Award of contract.** The award of a contract, if it is to be awarded, shall be made within 90 calendar days of the date specified for publicly opening proposals, unless otherwise specified herein.

If the Owner elects to proceed with an award of contract, the Owner will make award to the responsible bidder whose bid, conforming with all the material terms and conditions of the bid documents, is the lowest in price.

**30-03 Cancellation of award.** The Owner reserves the right to cancel the award without liability to the bidder, except return of proposal guaranty, at any time before a contract has been fully executed by all parties and is approved by the Owner in accordance with paragraph 30-07 *Approval of Contract*.

**30-04 Return of proposal guaranty.** All proposal guaranties, except those of the two lowest bidders, will be returned immediately after the Owner has made a comparison of bids as specified in the paragraph 30-01, *Consideration of Proposals*. Proposal guaranties of the two lowest bidders will be retained by the Owner until such time as an award is made, at which time, the unsuccessful bidder's proposal guaranty will be returned. The successful bidder's proposal guaranty will be returned as soon as the Owner receives the contract bonds as specified in paragraph 30-05, *Requirements of Contract Bonds*.

**30-05 Requirements of contract bonds.** At the time of the execution of the contract, the successful bidder shall furnish the Owner a surety bond or bonds that have been fully executed by the bidder and the surety guaranteeing the performance of the work and the payment of all legal debts that may be incurred by reason of the Contractor's performance of the work. The surety and the form of the bond or bonds shall be acceptable to the Owner. Unless otherwise specified in this subsection, the surety bond or bonds shall be in a sum equal to the full amount of the contract.

**30-06 Execution of contract.** The successful bidder shall sign (execute) the necessary agreements for entering into the contract and return the signed contract to the Owner, along with the fully executed surety bond or bonds specified in paragraph 30-05, *Requirements of Contract Bonds*, of this section, within **20 calendar days** from the date mailed or otherwise delivered to the successful bidder.

**30-07 Approval of contract.** Upon receipt of the contract and contract bond or bonds that have been executed by the successful bidder, the Owner shall complete the execution of the contract in accordance with local laws or ordinances, and return the fully executed contract to the Contractor. Delivery of the fully executed contract to the Contractor shall constitute the Owner's approval to be bound by the successful bidder's proposal and the terms of the contract.

**30-08 Failure to execute contract.** Failure of the successful bidder to execute the contract and furnish an acceptable surety bond or bonds within the period specified in paragraph 30-06, *Execution of Contract*, of this section shall be just cause for cancellation of the award and forfeiture of the proposal guaranty, not as a penalty, but as liquidated damages to the Owner.

**END OF SECTION 30**

## Section 40 Scope of Work

**40-01 Intent of contract.** The intent of the contract is to provide for construction and completion, in every detail, of the work described. It is further intended that the Contractor shall furnish all labor, materials, equipment, tools, transportation, and supplies required to complete the work in accordance with the plans, specifications, and terms of the contract.

**40-02 Alteration of work and quantities.** The Owner reserves the right to make such changes in quantities and work as may be necessary or desirable to complete, in a satisfactory manner, the original intended work. Unless otherwise specified in the Contract, the Owner's Engineer or RPR shall be and is hereby authorized to make, in writing, such in-scope alterations in the work and variation of quantities as may be necessary to complete the work, provided such action does not represent a significant change in the character of the work.

For purpose of this section, a significant change in character of work means: any change that is outside the current contract scope of work; any change (increase or decrease) in the total contract cost by more than 25%; or any change in the total cost of a major contract item by more than 25%.

Work alterations and quantity variances that do not meet the definition of significant change in character of work shall not invalidate the contract nor release the surety. Contractor agrees to accept payment for such work alterations and quantity variances in accordance with Section 90, paragraph 90-03, *Compensation for Altered Quantities*.

Should the value of altered work or quantity variance meet the criteria for significant change in character of work, such altered work and quantity variance shall be covered by a supplemental agreement. Supplemental agreements shall also require consent of the Contractor's surety and separate performance and payment bonds. If the Owner and the Contractor are unable to agree on a unit adjustment for any contract item that requires a supplemental agreement, the Owner reserves the right to terminate the contract with respect to the item and make other arrangements for its completion.

**40-03 Omitted items.** The Owner, the Owner's Engineer or the RPR may provide written notice to the Contractor to omit from the work any contract item that does not meet the definition of major contract item. Major contract items may be omitted by a supplemental agreement. Such omission of contract items shall not invalidate any other contract provision or requirement.

Should a contract item be omitted or otherwise ordered to be non-performed, the Contractor shall be paid for all work performed toward completion of such item prior to the date of the order to omit such item. Payment for work performed shall be in accordance with Section 90, paragraph 90-04, *Payment for Omitted Items*.

**40-04 Extra work.** Should acceptable completion of the contract require the Contractor to perform an item of work not provided for in the awarded contract as previously modified by change order or supplemental agreement, Owner may issue a Change Order to cover the necessary extra work. Change orders for extra work shall contain agreed unit prices for performing the change order work in accordance with the requirements specified in the order, and shall contain any adjustment to the contract time that, in the RPR's opinion, is necessary for completion of the extra work.

When determined by the RPR to be in the Owner's best interest, the RPR may order the Contractor to proceed with extra work, with prior approval by the Owner and the FAA, as provided in Section 90, paragraph 90-05, *Payment for Extra Work*. Extra work that is necessary for acceptable completion of the

project, but is not within the general scope of the work covered by the original contract shall be covered by a supplemental agreement as defined in Section 10, paragraph 10-59, *Supplemental Agreement*.

If extra work is essential to maintaining the project critical path, RPR may order the Contractor to commence the extra work under a Time and Material contract method. Once sufficient detail is available to establish the level of effort necessary for the extra work, the Owner shall initiate a change order or supplemental agreement to cover the extra work.

Any claim for payment of extra work that is not covered by written agreement (change order or supplemental agreement) shall be rejected by the Owner.

**40-05 Maintenance of traffic.** It is the explicit intention of the contract that the safety of aircraft, as well as the Contractor's equipment and personnel, is the most important consideration. The Contractor shall maintain traffic in the manner detailed in the Construction Safety and Phasing Plan (CSPP).

**a.** It is understood and agreed that the Contractor shall provide for the free and unobstructed movement of aircraft in the air operations areas (AOAs) of the airport with respect to their own operations and the operations of all subcontractors as specified in Section 80, paragraph 80-04, *Limitation of Operations*. It is further understood and agreed that the Contractor shall provide for the uninterrupted operation of visual and electronic signals (including power supplies thereto) used in the guidance of aircraft while operating to, from, and upon the airport as specified in Section 70, paragraph 70-15, *Contractor's Responsibility for Utility Service and Facilities of Others*.

**b.** With respect to their own operations and the operations of all subcontractors, the Contractor shall provide marking, lighting, and other acceptable means of identifying personnel, equipment, vehicles, storage areas, and any work area or condition that may be hazardous to the operation of aircraft, fire-rescue equipment, or maintenance vehicles at the airport in accordance with the construction safety and phasing plan (CSPP) and the safety plan compliance document (SPCD).

**c.** When the contract requires the maintenance of an existing road, street, or highway during the Contractor's performance of work that is otherwise provided for in the contract, plans, and specifications, the Contractor shall keep the road, street, or highway open to all traffic and shall provide maintenance as may be required to accommodate traffic. The Contractor, at their expense, shall be responsible for the repair to equal or better than preconstruction conditions of any damage caused by the Contractor's equipment and personnel. The Contractor shall furnish, erect, and maintain barricades, warning signs, flag person, and other traffic control devices in reasonable conformity with the Manual on Uniform Traffic Control Devices (MUTCD) (<http://mutcd.fhwa.dot.gov/>), unless otherwise specified. The Contractor shall also construct and maintain in a safe condition any temporary connections necessary for ingress to and egress from abutting property or intersecting roads, streets or highways. Unless otherwise specified herein, the Contractor will not be required to furnish snow removal for such existing road, street, or highway.

**40-06 Removal of existing structures.** All existing structures encountered within the established lines, grades, or grading sections shall be removed by the Contractor, unless such existing structures are otherwise specified to be relocated, adjusted up or down, salvaged, abandoned in place, reused in the work or to remain in place. The cost of removing such existing structures shall not be measured or paid for directly, but shall be included in the various contract items.

Should the Contractor encounter an existing structure (above or below ground) in the work for which the disposition is not indicated on the plans, the Resident Project Representative (RPR) shall be notified prior to disturbing such structure. The disposition of existing structures so encountered shall be immediately determined by the RPR in accordance with the provisions of the contract.

Except as provided in Section 40, paragraph 40-07, *Rights in and Use of Materials Found in the Work*, it is intended that all existing materials or structures that may be encountered (within the lines, grades, or



grading sections established for completion of the work) shall be used in the work as otherwise provided for in the contract and shall remain the property of the Owner when so used in the work.

**40-07 Rights in and use of materials found in the work.** Should the Contractor encounter any material such as (but not restricted to) sand, stone, gravel, slag, or concrete slabs within the established lines, grades, or grading sections, the use of which is intended by the terms of the contract to be embankment, the Contractor may at their own option either:

- a. Use such material in another contract item, providing such use is approved by the RPR and is in conformance with the contract specifications applicable to such use; or,
- b. Remove such material from the site, upon written approval of the RPR; or
- c. Use such material for the Contractor's own temporary construction on site; or,
- d. Use such material as intended by the terms of the contract.

Should the Contractor wish to exercise option a., b., or c., the Contractor shall request the RPR's approval in advance of such use.

Should the RPR approve the Contractor's request to exercise option a., b., or c., the Contractor shall be paid for the excavation or removal of such material at the applicable contract price. The Contractor shall replace, at their expense, such removed or excavated material with an agreed equal volume of material that is acceptable for use in constructing embankment, backfills, or otherwise to the extent that such replacement material is needed to complete the contract work. The Contractor shall not be charged for use of such material used in the work or removed from the site.

Should the RPR approve the Contractor's exercise of option a., the Contractor shall be paid, at the applicable contract price, for furnishing and installing such material in accordance with requirements of the contract item in which the material is used.

It is understood and agreed that the Contractor shall make no claim for delays by reason of their own exercise of option a., b., or c.

The Contractor shall not excavate, remove, or otherwise disturb any material, structure, or part of a structure which is located outside the lines, grades, or grading sections established for the work, except where such excavation or removal is provided for in the contract, plans, or specifications.

**40-08 Final cleanup.** Upon completion of the work and before acceptance and final payment will be made, the Contractor shall remove from the site all machinery, equipment, surplus and discarded materials, rubbish, temporary structures, and stumps or portions of trees. The Contractor shall cut all brush and woods within the limits indicated and shall leave the site in a neat and presentable condition. Material cleared from the site and deposited on adjacent property will not be considered as having been disposed of satisfactorily, unless the Contractor has obtained the written permission of the property Owner.

## END OF SECTION 40

Page Intentionally Blank

## Section 50 Control of Work

**50-01 Authority of the Resident Project Representative (RPR).** The RPR, with concurrence from the Engineer of Record (EOR), has final authority regarding the interpretation of project specification requirements. The RPR shall determine acceptability of the quality of materials furnished, method of performance of work performed, and the manner and rate of performance of the work. The RPR does not have the authority to accept work that does not conform to specification requirements.

**50-02 Conformity with plans and specifications.** All work and all materials furnished shall be in reasonably close conformity with the lines, grades, grading sections, cross-sections, dimensions, material requirements, and testing requirements that are specified (including specified tolerances) in the contract, plans, or specifications.

If the RPR finds the materials furnished, work performed, or the finished product not within reasonably close conformity with the plans and specifications, but that the portion of the work affected will, in their opinion, result in a finished product having a level of safety, economy, durability, and workmanship acceptable to the Owner, the RPR will advise the Owner of their determination that the affected work be accepted and remain in place. The RPR will document the determination and recommend to the Owner a basis of acceptance that will provide for an adjustment in the contract price for the affected portion of the work. Changes in the contract price must be covered by contract change order or supplemental agreement as applicable.

If the RPR finds the materials furnished, work performed, or the finished product are not in reasonably close conformity with the plans and specifications and have resulted in an unacceptable finished product, the affected work or materials shall be removed and replaced or otherwise corrected by and at the expense of the Contractor in accordance with the RPR's written orders.

The term "reasonably close conformity" shall not be construed as waiving the Contractor's responsibility to complete the work in accordance with the contract, plans, and specifications. The term shall not be construed as waiving the RPR's responsibility to insist on strict compliance with the requirements of the contract, plans, and specifications during the Contractor's execution of the work, when, in the RPR's opinion, such compliance is essential to provide an acceptable finished portion of the work.

The term "reasonably close conformity" is also intended to provide the RPR with the authority, after consultation with the Sponsor and FAA, to use sound engineering judgment in their determinations to accept work that is not in strict conformity, but will provide a finished product equal to or better than that required by the requirements of the contract, plans and specifications.

The RPR will not be responsible for the Contractor's means, methods, techniques, sequences, or procedures of construction or the safety precautions incident thereto.

**50-03 Coordination of contract, plans, and specifications.** The contract, plans, specifications, and all referenced standards cited are essential parts of the contract requirements. If electronic files are provided and used on the project and there is a conflict between the electronic files and hard copy plans, the hard copy plans shall govern. A requirement occurring in one is as binding as though occurring in all. They are intended to be complementary and to describe and provide for a complete work. In case of discrepancy, calculated dimensions will govern over scaled dimensions; contract technical specifications shall govern over contract general provisions, plans, cited standards for materials or testing, and cited advisory circulars (ACs); contract general provisions shall govern over plans, cited standards for materials or testing, and cited ACs; plans shall govern over cited standards for materials or testing and cited ACs. If

any paragraphs contained in the Special Provisions conflict with General Provisions or Technical Specifications, the Special Provisions shall govern.

From time to time, discrepancies within cited testing standards occur due to the timing of the change, edits, and/or replacement of the standards. If the Contractor discovers any apparent discrepancy within standard test methods, the Contractor shall immediately ask the RPR for an interpretation and decision, and such decision shall be final.

The Contractor shall not take advantage of any apparent error or omission on the plans or specifications. In the event the Contractor discovers any apparent error or discrepancy, Contractor shall immediately notify the Owner or the designated representative in writing requesting their written interpretation and decision.

**50-04 List of Special Provisions.** Refer to Special Provisions, Sections 1-5.

**50-05 Cooperation of Contractor.** The Contractor shall be supplied with five hard copies or an electronic PDF of the plans and specifications. The Contractor shall have available on the construction site at all times one hardcopy each of the plans and specifications. Additional hard copies of plans and specifications may be obtained by the Contractor for the cost of reproduction.

The Contractor shall give constant attention to the work to facilitate the progress thereof, and shall cooperate with the RPR and their inspectors and with other Contractors in every way possible. The Contractor shall have a competent superintendent on the work at all times who is fully authorized as their agent on the work. The superintendent shall be capable of reading and thoroughly understanding the plans and specifications and shall receive and fulfill instructions from the RPR or their authorized representative.

**50-06 Cooperation between Contractors.** The Owner reserves the right to contract for and perform other or additional work on or near the work covered by this contract.

When separate contracts are let within the limits of any one project, each Contractor shall conduct the work not to interfere with or hinder the progress of completion of the work being performed by other Contractors. Contractors working on the same project shall cooperate with each other as directed.

Each Contractor involved shall assume all liability, financial or otherwise, in connection with their own contract and shall protect and hold harmless the Owner from any and all damages or claims that may arise because of inconvenience, delays, or loss experienced because of the presence and operations of other Contractors working within the limits of the same project.

The Contractor shall arrange their work and shall place and dispose of the materials being used to not interfere with the operations of the other Contractors within the limits of the same project. The Contractor shall join their work with that of the others in an acceptable manner and shall perform it in proper sequence to that of the others.

**50-07 Construction layout and stakes.** The Engineer/RPR shall establish necessary horizontal and vertical control. The establishment of Survey Control and/or reestablishment of survey control shall be by a State Licensed Land Surveyor. Contractor is responsible for preserving integrity of horizontal and vertical controls established by Engineer/RPR. In case of negligence on the part of the Contractor or their employees, resulting in the destruction of any horizontal and vertical control, the resulting **reestablishment** costs will be deducted as a liquidated damage against the Contractor.

Prior to the start of construction, the Contractor will check all control points for horizontal and vertical accuracy and certify in writing to the RPR that the Contractor concurs with survey control established for the project. All lines, grades and measurements from control points necessary for the proper execution and control of the work on this project will be provided to the RPR. The Contractor is responsible to establish all layout required for the construction of the project.

Copies of survey notes will be provided to the RPR for each area of construction and for each placement of material as specified to allow the RPR to make periodic checks for conformance with plan grades, alignments and grade tolerances required by the applicable material specifications. Surveys will be provided to the RPR prior to commencing work items that cover or disturb the survey staking. Survey(s) and notes shall be provided in the following format(s): AutoCAD 2018 or newer, and PDF.

Laser, GPS, String line, or other automatic control shall be checked with temporary control as necessary. In the case of error, on the part of the Contractor, their surveyor, employees or subcontractors, resulting in established grades, alignment or grade tolerances that do not concur with those specified or shown on the plans, the Contractor is solely responsible for correction, removal, replacement and all associated costs at no additional cost to the Owner.

No direct payment will be made, unless otherwise specified in contract documents, for this labor, materials, or other expenses. The cost shall be included in the price of the bid for the various items of the Contract.

**50-08 Authority and duties of Quality Assurance (QA) inspectors.** QA inspectors shall be authorized to inspect all work done and all material furnished. Such QA inspection may extend to all or any part of the work and to the preparation, fabrication, or manufacture of the materials to be used. QA inspectors are not authorized to revoke, alter, or waive any provision of the contract. QA inspectors are not authorized to issue instructions contrary to the plans and specifications or to act as foreman for the Contractor.

QA Inspectors are authorized to notify the Contractor or their representatives of any failure of the work or materials to conform to the requirements of the contract, plans, or specifications and to reject such nonconforming materials in question until such issues can be referred to the RPR for a decision.

**50-09 Inspection of the work.** All materials and each part or detail of the work shall be subject to inspection. The RPR shall be allowed access to all parts of the work and shall be furnished with such information and assistance by the Contractor as is required to make a complete and detailed inspection.

If the RPR requests it, the Contractor, at any time before acceptance of the work, shall remove or uncover such portions of the finished work as may be directed. After examination, the Contractor shall restore said portions of the work to the standard required by the specifications. Should the work thus exposed or examined prove acceptable, the uncovering, or removing, and the replacing of the covering or making good of the parts removed will be paid for as extra work; but should the work so exposed or examined prove unacceptable, the uncovering, or removing, and the replacing of the covering or making good of the parts removed will be at the Contractor's expense.

Provide advance written notice to the RPR of work the Contractor plans to perform each week and each day. Any work done or materials used without written notice and allowing opportunity for inspection by the RPR may be ordered removed and replaced at the Contractor's expense.

Should the contract work include relocation, adjustment, or any other modification to existing facilities, not the property of the (contract) Owner, authorized representatives of the Owners of such facilities shall have the right to inspect such work. Such inspection shall in no sense make any facility owner a party to the contract, and shall in no way interfere with the rights of the parties to this contract.

**50-10 Removal of unacceptable and unauthorized work.** All work that does not conform to the requirements of the contract, plans, and specifications will be considered unacceptable, unless otherwise determined acceptable by the RPR as provided in paragraph 50-02, *Conformity with Plans and Specifications*.

Unacceptable work, whether the result of poor workmanship, use of defective materials, damage through carelessness, or any other cause found to exist prior to the final acceptance of the work, shall be removed immediately and replaced in an acceptable manner in accordance with the provisions of Section 70, paragraph 70-14, *Contractor's Responsibility for Work*.

No removal work made under provision of this paragraph shall be done without lines and grades having been established by the RPR. Work done contrary to the instructions of the RPR, work done beyond the lines shown on the plans or as established by the RPR, except as herein specified, or any extra work done without authority, will be considered as unauthorized and will not be paid for under the provisions of the contract. Work so done may be ordered removed or replaced at the Contractor's expense.

Upon failure on the part of the Contractor to comply with any order of the RPR made under the provisions of this subsection, the RPR will have authority to cause unacceptable work to be remedied or removed and replaced; and unauthorized work to be removed and recover the resulting costs as a liquidated damage against the Contractor.

**50-11 Load restrictions.** The Contractor shall comply with all legal load restrictions in the hauling of materials on public roads beyond the limits of the work. A special permit will not relieve the Contractor of liability for damage that may result from the moving of material or equipment.

The operation of equipment of such weight or so loaded as to cause damage to structures or to any other type of construction will not be permitted. Hauling of materials over the base course or surface course under construction shall be limited as directed. No loads will be permitted on a concrete pavement, base, or structure before the expiration of the curing period. The Contractor, at their own expense, shall be responsible for the repair to equal or better than preconstruction conditions of any damage caused by the Contractor's equipment and personnel.

**50-12 Maintenance during construction.** The Contractor shall maintain the work during construction and until the work is accepted. Maintenance shall constitute continuous and effective work prosecuted day by day, with adequate equipment and forces so that the work is maintained in satisfactory condition at all times.

In the case of a contract for the placing of a course upon a course or subgrade previously constructed, the Contractor shall maintain the previous course or subgrade during all construction operations.

All costs of maintenance work during construction and before the project is accepted shall be included in the unit prices bid on the various contract items, and the Contractor will not be paid an additional amount for such work.

**50-13 Failure to maintain the work.** Should the Contractor at any time fail to maintain the work as provided in paragraph 50-12, *Maintenance during Construction*, the RPR shall immediately notify the Contractor of such noncompliance. Such notification shall specify a reasonable time within which the Contractor shall be required to remedy such unsatisfactory maintenance condition. The time specified will give due consideration to the exigency that exists.

Should the Contractor fail to respond to the RPR's notification, the Owner may suspend any work necessary for the Owner to correct such unsatisfactory maintenance condition, depending on the exigency that exists. Any maintenance cost incurred by the Owner, shall be recovered as a liquidated damage against the Contractor.

**50-14 Partial acceptance.** If at any time during the execution of the project the Contractor substantially completes a usable unit or portion of the work, the occupancy of which will benefit the Owner, the Contractor may request the RPR to make final inspection of that unit. If the RPR finds upon inspection that the unit has been satisfactorily completed in compliance with the contract, the RPR may accept it as being complete, and the Contractor may be relieved of further responsibility for that unit. Such partial acceptance and beneficial occupancy by the Owner shall not void or alter any provision of the contract.

**50-15 Final acceptance.** Upon due notice from the Contractor of presumptive completion of the entire project, the RPR and Owner will make an inspection. If all construction provided for and contemplated by the contract is found to be complete in accordance with the contract, plans, and specifications, such

inspection shall constitute the final inspection. The RPR shall notify the Contractor in writing of final acceptance as of the date of the final inspection.

If, however, the inspection discloses any work, in whole or in part, as being unsatisfactory, the RPR will notify the Contractor and the Contractor shall correct the unsatisfactory work. Upon correction of the work, another inspection will be made which shall constitute the final inspection, provided the work has been satisfactorily completed. In such event, the RPR will make the final acceptance and notify the Contractor in writing of this acceptance as of the date of final inspection.

**50-16 Claims for adjustment and disputes.** If for any reason the Contractor deems that additional compensation is due for work or materials not clearly provided for in the contract, plans, or specifications or previously authorized as extra work, the Contractor shall notify the RPR in writing of their intention to claim such additional compensation before the Contractor begins the work on which the Contractor bases the claim. If such notification is not given or the RPR is not afforded proper opportunity by the Contractor for keeping strict account of actual cost as required, then the Contractor hereby agrees to waive any claim for such additional compensation. Such notice by the Contractor and the fact that the RPR has kept account of the cost of the work shall not in any way be construed as proving or substantiating the validity of the claim. When the work on which the claim for additional compensation is based has been completed, the Contractor shall, within 10 calendar days, submit a written claim to the RPR who will present it to the Owner for consideration in accordance with local laws or ordinances.

Nothing in this subsection shall be construed as a waiver of the Contractor's right to dispute final payment based on differences in measurements or computations.

## **END OF SECTION 50**

Page Intentionally Blank



## Section 60 Control of Materials

**60-01 Source of supply and quality requirements.** The materials used in the work shall conform to the requirements of the contract, plans, and specifications. Unless otherwise specified, such materials that are manufactured or processed shall be new (as compared to used or reprocessed).

In order to expedite the inspection and testing of materials, the Contractor shall furnish documentation to the RPR as to the origin, composition, and manufacture of all materials to be used in the work.

Documentation shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials.

At the RPR's option, materials may be approved at the source of supply before delivery. If it is found after trial that sources of supply for previously approved materials do not produce specified products, the Contractor shall furnish materials from other sources.

The Contractor shall furnish airport lighting equipment that meets the requirements of the specifications; and is listed in AC 150/5345-53, *Airport Lighting Equipment Certification Program* and *Addendum*, that is in effect on the date of advertisement.

**60-02 Samples, tests, and cited specifications.** All materials used in the work shall be inspected, tested, and approved by the RPR before incorporation in the work unless otherwise designated. Any work in which untested materials are used without approval or written permission of the RPR shall be performed at the Contractor's risk. Materials found to be unacceptable and unauthorized will not be paid for and, if directed by the RPR, shall be removed at the Contractor's expense.

Unless otherwise designated, quality assurance tests will be made by and at the expense of the Owner in accordance with the cited standard methods of ASTM, American Association of State Highway and Transportation Officials (AASHTO), federal specifications, Commercial Item Descriptions, and all other cited methods, which are current on the date of advertisement for bids.

The testing organizations performing on-site quality assurance field tests shall have copies of all referenced standards on the construction site for use by all technicians and other personnel. Unless otherwise designated, samples for quality assurance will be taken by a qualified representative of the RPR. All materials being used are subject to inspection, test, or rejection at any time prior to or during incorporation into the work. Copies of all tests will be furnished to the Contractor's representative at their request after review and approval of the RPR.

A copy of all Contractor QC test data shall be provided to the RPR daily, along with printed reports, in an approved format, on a weekly basis. After completion of the project, and prior to final payment, the Contractor shall submit a final report to the RPR showing all test data reports, plus an analysis of all results showing ranges, averages, and corrective action taken on all failing tests.

The Contractor shall employ a Quality Control (QC) testing organization to perform all Contractor required QC tests in accordance with Item C-100 Contractor Quality Control Program (CQCP).

**60-03 Certification of compliance/analysis (COC/COA).** The RPR may permit the use, prior to sampling and testing, of certain materials or assemblies when accompanied by manufacturer's COC stating that such materials or assemblies fully comply with the requirements of the contract. The certificate shall be signed by the manufacturer. Each lot of such materials or assemblies delivered to the work must be accompanied by a certificate of compliance in which the lot is clearly identified. The COA is the manufacturer's COC and includes all applicable test results.

Materials or assemblies used on the basis of certificates of compliance may be sampled and tested at any time and if found not to be in conformity with contract requirements will be subject to rejection whether in place or not.

The form and distribution of certificates of compliance shall be as approved by the RPR.

When a material or assembly is specified by “brand name or equal” and the Contractor elects to furnish the specified “or equal,” the Contractor shall be required to furnish the manufacturer’s certificate of compliance for each lot of such material or assembly delivered to the work. Such certificate of compliance shall clearly identify each lot delivered and shall certify as to:

- a. Conformance to the specified performance, testing, quality or dimensional requirements; and,
- b. Suitability of the material or assembly for the use intended in the contract work.

The RPR shall be the sole judge as to whether the proposed “or equal” is suitable for use in the work.

The RPR reserves the right to refuse permission for use of materials or assemblies on the basis of certificates of compliance.

**60-04 Plant inspection.** The RPR or their authorized representative may inspect, at its source, any specified material or assembly to be used in the work. Manufacturing plants may be inspected from time to time for the purpose of determining compliance with specified manufacturing methods or materials to be used in the work and to obtain samples required for acceptance of the material or assembly.

Should the RPR conduct plant inspections, the following conditions shall exist:

- a. The RPR shall have the cooperation and assistance of the Contractor and the producer with whom the Contractor has contracted for materials.
- b. The RPR shall have full entry at all reasonable times to such parts of the plant that concern the manufacture or production of the materials being furnished.
- c. If required by the RPR, the Contractor shall arrange for adequate office or working space that may be reasonably needed for conducting plant inspections. Place office or working space in a convenient location with respect to the plant.

It is understood and agreed that the Owner shall have the right to retest any material that has been tested and approved at the source of supply after it has been delivered to the site. The RPR shall have the right to reject only material which, when retested, does not meet the requirements of the contract, plans, or specifications.

**60-05 Engineer/ Resident Project Representative (RPR) field office.** The Contractor shall provide dedicated space for the use of the engineer, RPR, and inspectors, as a field office for the duration of the project. This space shall be located conveniently near the construction and shall be separate from any space used by the Contractor. The Contractor shall furnish water, sanitary facilities, heat, air conditioning, and electricity.

**60-06 Storage of materials.** Materials shall be stored to assure the preservation of their quality and fitness for the work. Stored materials, even though approved before storage, may again be inspected prior to their use in the work. Stored materials shall be located to facilitate their prompt inspection. The Contractor shall coordinate the storage of all materials with the RPR. Materials to be stored on airport property shall not create an obstruction to air navigation nor shall they interfere with the free and unobstructed movement of aircraft. Unless otherwise shown on the plans and/or CSPP, the storage of materials and the location of the Contractor’s plant and parked equipment or vehicles shall be as directed by the RPR. Private property shall not be used for storage purposes without written permission of the Owner or lessee of such property. The Contractor shall make all arrangements and bear all expenses for

the storage of materials on private property. Upon request, the Contractor shall furnish the RPR a copy of the property Owner's permission.

All storage sites on private or airport property shall be restored to their original condition by the Contractor at their expense, except as otherwise agreed to (in writing) by the Owner or lessee of the property.

**60-07 Unacceptable materials.** Any material or assembly that does not conform to the requirements of the contract, plans, or specifications shall be considered unacceptable and shall be rejected. The Contractor shall remove any rejected material or assembly from the site of the work, unless otherwise instructed by the RPR.

Rejected material or assembly, the defects of which have been corrected by the Contractor, shall not be returned to the site of the work until such time as the RPR has approved its use in the work.

**60-08 Owner furnished materials.** The Contractor shall furnish all materials required to complete the work, except those specified, if any, to be furnished by the Owner. Owner-furnished materials shall be made available to the Contractor at the location specified.

All costs of handling, transportation from the specified location to the site of work, storage, and installing Owner-furnished materials shall be included in the unit price bid for the contract item in which such Owner-furnished material is used.

After any Owner-furnished material has been delivered to the location specified, the Contractor shall be responsible for any demurrage, damage, loss, or other deficiencies that may occur during the Contractor's handling, storage, or use of such Owner-furnished material. The Owner will deduct from any monies due or to become due the Contractor any cost incurred by the Owner in making good such loss due to the Contractor's handling, storage, or use of Owner-furnished materials.

## **END OF SECTION 60**

Page Intentionally Blank

## Section 70 Legal Regulations and Responsibility to Public

**70-01 Laws to be observed.** The Contractor shall keep fully informed of all federal and state laws, all local laws, ordinances, and regulations and all orders and decrees of bodies or tribunals having any jurisdiction or authority, which in any manner affect those engaged or employed on the work, or which in any way affect the conduct of the work. The Contractor shall at all times observe and comply with all such laws, ordinances, regulations, orders, and decrees; and shall protect and indemnify the Owner and all their officers, agents, or servants against any claim or liability arising from or based on the violation of any such law, ordinance, regulation, order, or decree, whether by the Contractor or the Contractor's employees.

**70-02 Permits, licenses, and taxes.** The Contractor shall procure all permits and licenses, pay all charges, fees, and taxes, and give all notices necessary and incidental to the due and lawful execution of the work.

**70-03 Patented devices, materials, and processes.** If the Contractor is required or desires to use any design, device, material, or process covered by letters of patent or copyright, the Contractor shall provide for such use by suitable legal agreement with the Patentee or Owner. The Contractor and the surety shall indemnify and hold harmless the Owner, any third party, or political subdivision from any and all claims for infringement by reason of the use of any such patented design, device, material or process, or any trademark or copyright, and shall indemnify the Owner for any costs, expenses, and damages which it may be obliged to pay by reason of an infringement, at any time during the execution or after the completion of the work.

**70-04 Restoration of surfaces disturbed by others.** The Owner reserves the right to authorize the construction, reconstruction, or maintenance of any public or private utility service, FAA or National Oceanic and Atmospheric Administration (NOAA) facility, or a utility service of another government agency at any time during the progress of the work. To the extent that such construction, reconstruction, or maintenance has been coordinated with the Owner, such authorized work (by others), if applicable, is indicated on the plans, ~~must be shown on the plans and is indicated as follows: [ ]~~.

Except as listed above, as authorized by the owner, the Contractor shall not permit any individual, firm, or corporation to excavate or otherwise disturb such utility services or facilities located within the limits of the work without the written permission of the RPR.

Should the Owner of public or private utility service, FAA, or NOAA facility, or a utility service of another government agency be authorized to construct, reconstruct, or maintain such utility service or facility during the progress of the work, the Contractor shall cooperate with such Owners by arranging and performing the work in this contract to facilitate such construction, reconstruction or maintenance by others whether or not such work by others is listed above. When ordered as extra work by the RPR, the Contractor shall make all necessary repairs to the work which are due to such authorized work by others, unless otherwise provided for in the contract, plans, or specifications. It is understood and agreed that the Contractor shall not be entitled to make any claim for damages due to such authorized work by others or for any delay to the work resulting from such authorized work.

**70-05 Federal Participation.** The United States Government has agreed to reimburse the Owner for some portion of the contract costs. The contract work is subject to the inspection and approval of duly authorized representatives of the FAA Administrator. No requirement of this contract shall be construed as making the United States a party to the contract nor will any such requirement interfere, in any way, with the rights of either party to the contract.

**70-06 Sanitary, health, and safety provisions.** The Contractor's worksite and facilities shall comply with applicable federal, state, and local requirements for health, safety and sanitary provisions.

**70-07 Public convenience and safety.** The Contractor shall control their operations and those of their subcontractors and all suppliers, to assure the least inconvenience to the traveling public. Under all circumstances, safety shall be the most important consideration.

The Contractor shall maintain the free and unobstructed movement of aircraft and vehicular traffic with respect to their own operations and those of their own subcontractors and all suppliers in accordance with Section 40, paragraph 40-05, *Maintenance of Traffic*, and shall limit such operations for the convenience and safety of the traveling public as specified in Section 80, paragraph 80-04, *Limitation of Operations*.

The Contractor shall remove or control debris and rubbish resulting from its work operations at frequent intervals, and upon the order of the RPR. If the RPR determines the existence of Contractor debris in the work site represents a hazard to airport operations and the Contractor is unable to respond in a prompt and reasonable manner, the RPR reserves the right to assign the task of debris removal to a third party and recover the resulting costs as a liquidated damage against the Contractor.

**70-08 Construction Safety and Phasing Plan (CSPP).** The Contractor shall complete the work in accordance with the approved Construction Safety and Phasing Plan (CSPP) developed in accordance with AC 150/5370-2, Operational Safety on Airports During Construction. The CSPP is on sheet(s) G-120 – G-127 and G-151 – G-153 of the project plans.

**70-09 Use of explosives.** The use of explosives is not permitted on this project.

**70-10 Protection and restoration of property and landscape.** The Contractor shall be responsible for the preservation of all public and private property, and shall protect carefully from disturbance or damage all land monuments and property markers until the Engineer/RPR has witnessed or otherwise referenced their location and shall not move them until directed.

The Contractor shall be responsible for all damage or injury to property of any character, during the execution of the work, resulting from any act, omission, neglect, or misconduct in manner or method of executing the work, or at any time due to defective work or materials, and said responsibility shall not be released until the project has been completed and accepted.

When or where any direct or indirect damage or injury is done to public or private property by or on account of any act, omission, neglect, or misconduct in the execution of the work, or in consequence of the non-execution thereof by the Contractor, the Contractor shall restore, at their expense, such property to a condition similar or equal to that existing before such damage or injury was done, by repairing, or otherwise restoring as may be directed, or the Contractor shall make good such damage or injury in an acceptable manner.

**70-11 Responsibility for damage claims.** The Contractor shall indemnify and hold harmless the Engineer/RPR and the Owner and their officers, agents, and employees from all suits, actions, or claims, of any character, brought because of any injuries or damage received or sustained by any person, persons, or property on account of the operations of the Contractor; or on account of or in consequence of any neglect in safeguarding the work; or through use of unacceptable materials in constructing the work; or because of any act or omission, neglect, or misconduct of said Contractor; or because of any claims or amounts recovered from any infringements of patent, trademark, or copyright; or from any claims or amounts arising or recovered under the "Workmen's Compensation Act," or any other law, ordinance, order, or decree. Money due the Contractor under and by virtue of their own contract considered necessary by the Owner for such purpose may be retained for the use of the Owner or, in case no money is due, their own surety may be held until such suits, actions, or claims for injuries or damages shall have been settled and suitable evidence to that effect furnished to the Owner, except that money due the

Contractor will not be withheld when the Contractor produces satisfactory evidence that he or she is adequately protected by public liability and property damage insurance.

**70-12 Third party beneficiary clause.** It is specifically agreed between the parties executing the contract that it is not intended by any of the provisions of any part of the contract to create for the public or any member thereof, a third-party beneficiary or to authorize anyone not a party to the contract to maintain a suit for personal injuries or property damage pursuant to the terms or provisions of the contract.

**70-13 Opening sections of the work to traffic.** If it is necessary for the Contractor to complete portions of the contract work for the beneficial occupancy of the Owner prior to completion of the entire contract, such “phasing” of the work must be specified below and indicated on the approved Construction Safety and Phasing Plan (CSPP) and the project plans. When so specified, the Contractor shall complete such portions of the work on or before the date specified or as otherwise specified.

Upon completion of any portion of **phased work as shown on the CSPP (Sheets G-120 through G-127)** ~~work listed above~~, such portion shall be accepted by the Owner in accordance with Section 50, paragraph 50-14, *Partial Acceptance*.

No portion of the work may be opened by the Contractor until directed by the Owner in writing. Should it become necessary to open a portion of the work to traffic on a temporary or intermittent basis, such openings shall be made when, in the opinion of the RPR, such portion of the work is in an acceptable condition to support the intended traffic. Temporary or intermittent openings are considered to be inherent in the work and shall not constitute either acceptance of the portion of the work so opened or a waiver of any provision of the contract. Any damage to the portion of the work so opened that is not attributable to traffic which is permitted by the Owner shall be repaired by the Contractor at their expense.

The Contractor shall make their own estimate of the inherent difficulties involved in completing the work under the conditions herein described and shall not claim any added compensation by reason of delay or increased cost due to opening a portion of the contract work.

The Contractor must conform to safety standards contained AC 150/5370-2 and the approved CSPP.

Contractor shall refer to the plans, specifications, and the approved CSPP to identify barricade requirements, temporary and/or permanent markings, airfield lighting, guidance signs and other safety requirements prior to opening up sections of work to traffic.

**70-14 Contractor’s responsibility for work.** Until the RPR’s final written acceptance of the entire completed work, excepting only those portions of the work accepted in accordance with Section 50, paragraph 50-14, *Partial Acceptance*, the Contractor shall have the charge and care thereof and shall take every precaution against injury or damage to any part due to the action of the elements or from any other cause, whether arising from the execution or from the non-execution of the work. The Contractor shall rebuild, repair, restore, and make good all injuries or damages to any portion of the work occasioned by any of the above causes before final acceptance and shall bear the expense thereof except damage to the work due to unforeseeable causes beyond the control of and without the fault or negligence of the Contractor, including but not restricted to acts of God such as earthquake, tidal wave, tornado, hurricane or other cataclysmic phenomenon of nature, or acts of the public enemy or of government authorities.

If the work is suspended for any cause whatever, the Contractor shall be responsible for the work and shall take such precautions necessary to prevent damage to the work. The Contractor shall provide for normal drainage and shall erect necessary temporary structures, signs, or other facilities at their own expense. During such period of suspension of work, the Contractor shall properly and continuously maintain in an acceptable growing condition all living material in newly established planting, seeding, and sodding furnished under the contract, and shall take adequate precautions to protect new tree growth and other important vegetative growth against injury.

**70-15 Contractor's responsibility for utility service and facilities of others.** As provided in paragraph 70-04, *Restoration of Surfaces Disturbed by Others*, the Contractor shall cooperate with the owner of any public or private utility service, FAA or NOAA, or a utility service of another government agency that may be authorized by the Owner to construct, reconstruct or maintain such utility services or facilities during the progress of the work. In addition, the Contractor shall control their operations to prevent the unscheduled interruption of such utility services and facilities.

To the extent that such public or private utility services, FAA, or NOAA facilities, or utility services of another governmental agency are known to exist within the limits of the contract work, the approximate locations have been indicated on the plans and/or in the contract documents.

#### Facilities and Utilities

Facility or Utility	Point of Contact	Telephone
Airport Facilities	Jason Burch	434-973-8342
Fauquier County Utility Dept.	Albemarle County Service Authority	434-977-4511
FAA Equipment	FAA Air Traffic Control System Command Center	866-709-4993
Virginia 811		811 or (800) 552-7001

It is understood and agreed that the Owner does not guarantee the accuracy or the completeness of the location information relating to existing utility services, facilities, or structures that may be shown on the plans or encountered in the work. Any inaccuracy or omission in such information shall not relieve the Contractor of the responsibility to protect such existing features from damage or unscheduled interruption of service.

It is further understood and agreed that the Contractor shall, upon execution of the contract, notify the Owners of all utility services or other facilities of their plan of operations. Such notification shall be in writing addressed to "The Person to Contact" as provided in this paragraph and paragraph 70-04, *Restoration of Surfaces Disturbed By Others*. A copy of each notification shall be given to the RPR.

In addition to the general written notification provided, it shall be the responsibility of the Contractor to keep such individual Owners advised of changes in their plan of operations that would affect such Owners.

Prior to beginning the work in the general vicinity of an existing utility service or facility, the Contractor shall again notify each such Owner of their plan of operation. If, in the Contractor's opinion, the Owner's assistance is needed to locate the utility service or facility or the presence of a representative of the Owner is desirable to observe the work, such advice should be included in the notification. Such notification shall be given by the most expeditious means to reach the utility owner's "Person to Contact" no later than two normal business days prior to the Contractor's commencement of operations in such general vicinity. The Contractor shall furnish a written summary of the notification to the RPR.

The Contractor's failure to give the two days' notice shall be cause for the Owner to suspend the Contractor's operations in the general vicinity of a utility service or facility.



Where the outside limits of an underground utility service have been located and staked on the ground, the Contractor shall be required to use hand excavation methods within 3 feet (1 m) of such outside limits at such points as may be required to ensure protection from damage due to the Contractor's operations.

Should the Contractor damage or interrupt the operation of a utility service or facility by accident or otherwise, the Contractor shall immediately notify the proper authority and the RPR and shall take all reasonable measures to prevent further damage or interruption of service. The Contractor, in such events, shall cooperate with the utility service or facility owner and the RPR continuously until such damage has been repaired and service restored to the satisfaction of the utility or facility owner.

The Contractor shall bear all costs of damage and restoration of service to any utility service or facility due to their operations whether due to negligence or accident. The Owner reserves the right to deduct such costs from any monies due or which may become due the Contractor, or their own surety.

**70-15.1 FAA facilities and cable runs.** The Contractor is hereby advised that the construction limits of the project include **may** existing facilities and buried cable runs that are owned, operated and maintained by the FAA. The Contractor, during the execution of the project work, shall comply with the following:

**a.** The Contractor shall permit FAA maintenance personnel the right of access to the project work site for purposes of inspecting and maintaining all existing FAA owned facilities.

**b.** The Contractor shall provide notice to the FAA Air Traffic Organization (ATO)/Technical Operations/System Support Center (SSC) Point-of-Contact through the airport Owner a minimum of seven (7) calendar days prior to commencement of construction activities in order to permit sufficient time to locate and mark existing buried cables and to schedule any required facility outages.

**c.** If execution of the project work requires a facility outage, the Contractor shall contact the FAA Point-of-Contact a minimum of 72 hours prior to the time of the required outage.

**d.** Any damage to FAA cables, access roads, or FAA facilities during construction caused by the Contractor's equipment or personnel whether by negligence or accident will require the Contractor to repair or replace the damaged cables, access road, or FAA facilities to FAA requirements. The Contractor shall not bear the cost to repair damage to underground facilities or utilities improperly located by the FAA.

**e.** If the project work requires the cutting or splicing of FAA owned cables, the FAA Point-of-Contact shall be contacted a minimum of 72 hours prior to the time the cable work commences. The FAA reserves the right to have a FAA representative on site to observe the splicing of the cables as a condition of acceptance. All cable splices are to be accomplished in accordance with FAA specifications and require approval by the FAA Point-of-Contact as a condition of acceptance by the Owner. The Contractor is hereby advised that FAA restricts the location of where splices may be installed. If a cable splice is required in a location that is not permitted by FAA, the Contractor shall furnish and install a sufficient length of new cable that eliminates the need for any splice.

**70-16 Furnishing rights-of-way.** The Owner will be responsible for furnishing all rights-of-way upon which the work is to be constructed in advance of the Contractor's operations.

**70-17 Personal liability of public officials.** In carrying out any of the contract provisions or in exercising any power or authority granted by this contract, there shall be no liability upon the Engineer, RPR, their authorized representatives, or any officials of the Owner either personally or as an official of the Owner. It is understood that in such matters they act solely as agents and representatives of the Owner.

**70-18 No waiver of legal rights.** Upon completion of the work, the Owner will expeditiously make final inspection and notify the Contractor of final acceptance. Such final acceptance, however, shall not preclude or stop the Owner from correcting any measurement, estimate, or certificate made before or after completion of the work, nor shall the Owner be precluded or stopped from recovering from the Contractor

or their surety, or both, such overpayment as may be sustained, or by failure on the part of the Contractor to fulfill their obligations under the contract. A waiver on the part of the Owner of any breach of any part of the contract shall not be held to be a waiver of any other or subsequent breach.

The Contractor, without prejudice to the terms of the contract, shall be liable to the Owner for latent defects, fraud, or such gross mistakes as may amount to fraud, or as regards the Owner's rights under any warranty or guaranty.

**70-19 Environmental protection.** The Contractor shall comply with all federal, state, and local laws and regulations controlling pollution of the environment. The Contractor shall take necessary precautions to prevent pollution of streams, lakes, ponds, and reservoirs with fuels, oils, asphalts, chemicals, or other harmful materials and to prevent pollution of the atmosphere from particulate and gaseous matter.

**70-20 Archaeological and historical findings.** Unless otherwise specified in this subsection, the Contractor is advised that the site of the work is not within any property, district, or site, and does not contain any building, structure, or object listed in the current National Register of Historic Places published by the United States Department of Interior.

Should the Contractor encounter, during their operations, any building, part of a building, structure, or object that is incongruous with its surroundings, the Contractor shall immediately cease operations in that location and notify the RPR. The RPR will immediately investigate the Contractor's finding and the Owner will direct the Contractor to either resume operations or to suspend operations as directed.

Should the Owner order suspension of the Contractor's operations in order to protect an archaeological or historical finding, or order the Contractor to perform extra work, such shall be covered by an appropriate contract change order or supplemental agreement as provided in Section 40, paragraph 40-04, *Extra Work*, and Section 90, paragraph 90-05, *Payment for Extra Work*. If appropriate, the contract change order or supplemental agreement shall include an extension of contract time in accordance with Section 80, paragraph 80-07, *Determination and Extension of Contract Time*.

**70-21 Insurance Requirements.** Refer to Section 2 of the Special Provisions.

## END OF SECTION 70

## Section 80 Execution and Progress

**80-01 Subletting of contract.** The Owner **and Engineer** will not recognize any subcontractor on the work. The Contractor shall at all times when work is in progress be represented either in person, by a qualified superintendent, or by other designated, qualified representative who is duly authorized to receive and execute orders of the Resident Project Representative (RPR).

The Contractor shall perform, with his organization, an amount of work equal to at least 25 percent of the total contract cost.

Should the Contractor elect to assign their contract, said assignment shall be concurred in by the surety, shall be presented for the consideration and approval of the Owner, and shall be consummated only on the written approval of the Owner.

**The Contractor shall provide copies of all subcontracts to the RPR 14 days prior to being utilized on the project. As a minimum, the information shall include the following:**

- Subcontractor's legal company name.
- Subcontractor's legal company address, including County name.
- Principal contact person's name, telephone and fax number.
- Complete narrative description, and dollar value of the work to be performed by the subcontractor.
- Copies of required insurance certificates in accordance with the specifications.
- Minority/ non-minority status.

**80-02 Notice to proceed (NTP).** The Owners notice to proceed will state the date on which contract time commences. The Contractor is expected to commence project operations within ten (10) days of the **Administrative** NTP date. The Contractor shall notify the RPR at least 24 hours in advance of the time contract operations begins. The Contractor shall not commence any actual operations prior to the date on which the notice to proceed is issued by the Owner.

**80-03 Execution and progress.** Unless otherwise specified, the Contractor shall submit their coordinated construction schedule showing all work activities for the RPR's review and acceptance at least 10 days prior to the **Preconstruction Meeting** ~~start of work~~. The Contractor's progress schedule, once accepted by the RPR, will represent the Contractor's baseline plan to accomplish the project in accordance with the terms and conditions of the Contract. The RPR will compare actual Contractor progress against the baseline schedule to determine that status of the Contractor's performance. The Contractor shall provide sufficient materials, equipment, and labor to guarantee the completion of the project in accordance with the plans and specifications within the time set forth in the proposal.

If the Contractor falls significantly behind the submitted schedule, the Contractor shall, upon the RPR's request, submit a revised schedule for completion of the work within the contract time and modify their operations to provide such additional materials, equipment, and labor necessary to meet the revised schedule. Should the execution of the work be discontinued for any reason, the Contractor shall notify the RPR at least 24 hours in advance of resuming operations.

The Contractor shall not commence any actual construction prior to the date on which the NTP is issued by the Owner.

The project schedule shall be prepared as a network diagram in Critical Path Method (CPM), Program Evaluation and Review Technique (PERT), or other format, or as otherwise specified. It shall include information on the sequence of work activities, milestone dates, and activity duration. The schedule shall show all work items identified in the project proposal for each work area and shall include the project start date and end date.

The Contractor shall maintain the work schedule and provide an update and analysis of the progress schedule on a twice monthly basis, or as otherwise specified in the contract. Submission of the work schedule shall not relieve the Contractor of overall responsibility for scheduling, sequencing, and coordinating all work to comply with the requirements of the contract.

**80-04 Limitation of operations.** The Contractor shall control their operations and the operations of their subcontractors and all suppliers to provide for the free and unobstructed movement of aircraft in the air operations areas (AOA) of the airport.

When the work requires the Contractor to conduct their operations within an AOA of the airport, the work shall be coordinated with airport operations (through the RPR) at least 48 hours prior to commencement of such work. The Contractor shall not close an AOA until so authorized by the RPR and until the necessary temporary marking, signage and associated lighting is in place as provided in Section 70, paragraph 70-08, *Construction Safety and Phasing Plan (CSPP)*.

When the contract work requires the Contractor to work within an AOA of the airport on an intermittent basis (intermittent opening and closing of the AOA), the Contractor shall maintain constant communications as specified; immediately obey all instructions to vacate the AOA; and immediately obey all instructions to resume work in such AOA. Failure to maintain the specified communications or to obey instructions shall be cause for suspension of the Contractor's operations in the AOA until satisfactory conditions are provided. ~~The areas of the AOA identified in the Construction Safety Phasing Plan (CSPP) and as listed below, cannot be closed to operating aircraft to permit the Contractor's operations on a continuous basis and will therefore be closed to aircraft operations intermittently as follows:~~

[Details of the project phasing, and Contractor's responsibilities are shown in the CSPP, included in Section 5 of the Special Provisions of these specifications.](#)

The Contractor shall be required to conform to safety standards contained in AC 150/5370-2, Operational Safety on Airports During Construction and the approved CSPP.

**80-04.1 Operational safety on airport during construction.** All Contractors' operations shall be conducted in accordance with the approved project Construction Safety and Phasing Plan (CSPP) and the Safety Plan Compliance Document (SPCD) and the provisions set forth within the current version of AC 150/5370-2, Operational Safety on Airports During Construction. The CSPP included within the contract documents conveys minimum requirements for operational safety on the airport during construction activities. The Contractor shall prepare and submit a SPCD that details how it proposes to comply with the requirements presented within the CSPP.

The Contractor shall implement all necessary safety plan measures prior to commencement of any work activity. The Contractor shall conduct routine checks to assure compliance with the safety plan measures.

The Contractor is responsible to the Owner for the conduct of all subcontractors it employs on the project. The Contractor shall assure that all subcontractors are made aware of the requirements of the CSPP and SPCD and that they implement and maintain all necessary measures.

No deviation or modifications may be made to the approved CSPP and SPCD unless approved in writing by the Owner. The necessary coordination actions to review Contractor proposed modifications to an approved CSPP or approved SPCD can require a significant amount of time.

**80-05 Character of workers, methods, and equipment.** The Contractor shall, at all times, employ sufficient labor and equipment for prosecuting the work to full completion in the manner and time required by the contract, plans, and specifications.

All workers shall have sufficient skill and experience to perform properly the work assigned to them. Workers engaged in special work or skilled work shall have sufficient experience in such work and in the operation of the equipment required to perform the work satisfactorily.

Any person employed by the Contractor or by any subcontractor who violates any operational regulations or operational safety requirements and, in the opinion of the RPR, does not perform his work in a proper and skillful manner or is intemperate or disorderly shall, at the written request of the RPR, be removed immediately by the Contractor or subcontractor employing such person, and shall not be employed again in any portion of the work without approval of the RPR.

Should the Contractor fail to remove such person or persons, or fail to furnish suitable and sufficient personnel for the proper execution of the work, the RPR may suspend the work by written notice until compliance with such orders.

All equipment that is proposed to be used on the work shall be of sufficient size and in such mechanical condition as to meet requirements of the work and to produce a satisfactory quality of work. Equipment used on any portion of the work shall not cause injury to previously completed work, adjacent property, or existing airport facilities due to its use.

When the methods and equipment to be used by the Contractor in accomplishing the work are not prescribed in the contract, the Contractor is free to use any methods or equipment that will accomplish the work in conformity with the requirements of the contract, plans, and specifications.

When the contract specifies the use of certain methods and equipment, such methods and equipment shall be used unless otherwise authorized by the RPR. If the Contractor desires to use a method or type of equipment other than specified in the contract, the Contractor may request authority from the RPR to do so. The request shall be in writing and shall include a full description of the methods and equipment proposed and of the reasons for desiring to make the change. If approval is given, it will be on the condition that the Contractor will be fully responsible for producing work in conformity with contract requirements. If, after trial use of the substituted methods or equipment, the RPR determines that the work produced does not meet contract requirements, the Contractor shall discontinue the use of the substitute method or equipment and shall complete the remaining work with the specified methods and equipment. The Contractor shall remove any deficient work and replace it with work of specified quality, or take such other corrective action as the RPR may direct. No change will be made in basis of payment for the contract items involved nor in contract time as a result of authorizing a change in methods or equipment under this paragraph.

**80-06 Temporary suspension of the work.** The Owner shall have the authority to suspend the work wholly, or in part, for such period or periods the Owner may deem necessary, due to unsuitable weather, or other conditions considered unfavorable for the execution of the work, or for such time necessary due to the failure on the part of the Contractor to carry out orders given or perform any or all provisions of the contract.

In the event that the Contractor is ordered by the Owner, in writing, to suspend work for some unforeseen cause not otherwise provided for in the contract and over which the Contractor has no control, the Contractor may be reimbursed for actual money expended on the work during the period of shutdown. No allowance will be made for anticipated profits. The period of shutdown shall be computed from the

effective date of the written order to suspend work to the effective date of the written order to resume the work. Claims for such compensation shall be filed with the RPR within the time period stated in the RPR's order to resume work. The Contractor shall submit with their own claim information substantiating the amount shown on the claim. The RPR will forward the Contractor's claim to the Owner for consideration in accordance with local laws or ordinances. No provision of this article shall be construed as entitling the Contractor to compensation for delays due to inclement weather or for any other delay provided for in the contract, plans, or specifications.

If it becomes necessary to suspend work for an indefinite period, the Contractor shall store all materials in such manner that they will not become an obstruction nor become damaged in any way. The Contractor shall take every precaution to prevent damage or deterioration of the work performed and provide for normal drainage of the work. The Contractor shall erect temporary structures where necessary to provide for traffic on, to, or from the airport.

**80-07 Determination and extension of contract time.** The number of calendar days shall be stated in the proposal and contract and shall be known as the Contract Time.

If the contract time requires extension for reasons beyond the Contractor's control, it shall be adjusted as follows:

**80-07.1 Contract time based on calendar days.** Contract Time based on calendar days shall consist of the number of calendar days stated in the contract counting from the effective date of the Notice to Proceed and including all Saturdays, Sundays, holidays, and non-work days. All calendar days elapsing between the effective dates of the Owner's orders to suspend and resume all work, due to causes not the fault of the Contractor, shall be excluded.

At the time of final payment, the contract time shall be increased in the same proportion as the cost of the actually completed quantities bears to the cost of the originally estimated quantities in the proposal. Such increase in the contract time shall not consider either cost of work or the extension of contract time that has been covered by a change order or supplemental agreement. Charges against the contract time will cease as of the date of final acceptance.

**80-08 Failure to complete on time.** For each calendar day or working day, as specified in the contract, that any work remains uncompleted after the contract time (including all extensions and adjustments as provided in paragraph 80-07, *Determination and Extension of Contract Time*) the sum specified in the contract and proposal as liquidated damages (LD) will be deducted from any money due or to become due the Contractor or their own surety. Such deducted sums shall not be deducted as a penalty but shall be considered as liquidation of a reasonable portion of damages including but not limited to additional engineering services that will be incurred by the Owner should the Contractor fail to complete the work in the time provided in their contract.

Schedule	Liquidated Damages Cost	Every
Administrative Phase	N/A	90 Days
Phase – 1 through 7	\$2,500	Calendar Day / Part of Day beyond scheduled opening
Phase 8	\$2,000	Calendar Day / Portion thereof beyond apron reopening
Project Completion	\$2,500	Calendar Day / Part of Day beyond schedule reopening

The total number of calendar days for construction shall be 182 calendar days (does not include the 90-day administrative phase). Durations for each phase are included in the CSPP and may be subject to change with the Owner and RPR. Permitting the Contractor to continue and finish the work or any part of it after the time fixed for its completion, or after the date to which the time for completion may have been extended, will in no way operate as a waiver on the part of the Owner of any of its rights under the contract.

**80-09 Default and termination of contract.** The Contractor shall be considered in default of their contract and such default will be considered as cause for the Owner to terminate the contract for any of the following, **but not limited to**, reasons, if the Contractor:

- a. Fails to begin the work under the contract within the time specified in the Notice to Proceed, or
- b. Fails to perform the work or fails to provide sufficient workers, equipment and/or materials to assure completion of work in accordance with the terms of the contract, or
- c. Performs the work unsuitably or neglects or refuses to remove materials or to perform anew such work as may be rejected as unacceptable and unsuitable, or
- d. Discontinues the execution of the work, or
- e. Fails to resume work which has been discontinued within a reasonable time after notice to do so, or
- f. Becomes insolvent or is declared bankrupt, or commits any act of bankruptcy or insolvency, or
- g. Allows any final judgment to stand against the Contractor unsatisfied for a period of 10 days, or
- h. Makes an assignment for the benefit of creditors, or
- i. For any other cause whatsoever, fails to carry on the work in an acceptable manner.

Should the Owner consider the Contractor in default of the contract for any reason above, the Owner shall immediately give written notice to the Contractor and the Contractor's surety as to the reasons for considering the Contractor in default and the Owner's intentions to terminate the contract.

If the Contractor or surety, within a period of 10 days after such notice, does not proceed in accordance therewith, then the Owner will, upon written notification from the RPR of the facts of such delay, neglect, or default and the Contractor's failure to comply with such notice, have full power and authority without violating the contract, to take the execution of the work out of the hands of the Contractor. The Owner may appropriate or use any or all materials and equipment that have been mobilized for use in the work and are acceptable and may enter into an agreement for the completion of said contract according to the terms and provisions thereof, or use such other methods as in the opinion of the RPR will be required for the completion of said contract in an acceptable manner.

All costs and charges incurred by the Owner, together with the cost of completing the work under contract, will be deducted from any monies due or which may become due the Contractor. If such expense exceeds the sum which would have been payable under the contract, then the Contractor and the surety shall be liable and shall pay to the Owner the amount of such excess.

**80-10 Termination for national emergencies.** The Owner shall terminate the contract or portion thereof by written notice when the Contractor is prevented from proceeding with the construction contract as a direct result of an Executive Order of the President with respect to the execution of war or in the interest of national defense.

When the contract, or any portion thereof, is terminated before completion of all items of work in the contract, payment will be made for the actual number of units or items of work completed at the contract price or as mutually agreed for items of work partially completed or not started. No claims or loss of anticipated profits shall be considered.

Reimbursement for organization of the work, and other overhead expenses, (when not otherwise included in the contract) and moving equipment and materials to and from the job will be considered, the intent being that an equitable settlement will be made with the Contractor.

Acceptable materials, obtained or ordered by the Contractor for the work and that are not incorporated in the work shall, at the option of the Contractor, be purchased from the Contractor at actual cost as shown by receipted bills and actual cost records at such points of delivery as may be designated by the RPR.

Termination of the contract or a portion thereof shall neither relieve the Contractor of their responsibilities for the completed work nor shall it relieve their surety of its obligation for and concerning any just claim arising out of the work performed.

**80-11 Work area, storage area and sequence of operations.** The Contractor shall obtain approval from the RPR prior to beginning any work in all areas of the airport. No operating runway, taxiway, or air operations area (AOA) shall be crossed, entered, or obstructed while it is operational. The Contractor shall plan and coordinate work in accordance with the approved CSPP and SPCD.

## END OF SECTION 80



## Section 90 Measurement and Payment

**90-01 Measurement of quantities.** All work completed under the contract will be measured by the RPR, or their authorized representatives, using United States Customary Units of Measurement.

The method of measurement and computations to be used in determination of quantities of material furnished and of work performed under the contract will be those methods generally recognized as conforming to good engineering practice.

Unless otherwise specified, longitudinal measurements for area computations will be made horizontally, and no deductions will be made for individual fixtures (or leave-outs) having an area of 9 square feet (0.8 square meters) or less. Unless otherwise specified, transverse measurements for area computations will be the neat dimensions shown on the plans or ordered in writing by the RPR.

Unless otherwise specified, all contract items which are measured by the linear foot such as electrical ducts, conduits, pipe culverts, underdrains, and similar items shall be measured parallel to the base or foundation upon which such items are placed.

The term “lump sum” when used as an item of payment will mean complete payment for the work described in the contract. When a complete structure or structural unit (in effect, “lump sum” work) is specified as the unit of measurement, the unit will be construed to include all necessary fittings and accessories.

When requested by the Contractor and approved by the RPR in writing, material specified to be measured by the cubic yard (cubic meter) may be weighed, and such weights will be converted to cubic yards (cubic meters) for payment purposes. Factors for conversion from weight measurement to volume measurement will be determined by the RPR and shall be agreed to by the Contractor before such method of measurement of pay quantities is used.

### Measurement and Payment Terms

Term	Description
<b>Excavation and Embankment Volume</b>	In computing volumes of excavation, the average end area method will be used unless otherwise specified.
<b>Measurement and Proportion by Weight</b>	The term “ton” will mean the short ton consisting of 2,000 pounds (907 kg) avoirdupois. All materials that are measured or proportioned by weights shall be weighed on accurate, independently certified scales by competent, qualified personnel at locations designated by the RPR. If material is shipped by rail, the car weight may be accepted provided that only the actual weight of material is paid for. However, car weights will not be acceptable for material to be passed through mixing plants. Trucks used to haul material being paid for by weight shall be weighed empty daily at such times as the RPR directs, and each truck shall bear a plainly legible identification mark.
<b>Measurement by Volume</b>	Materials to be measured by volume in the hauling vehicle shall be hauled in approved vehicles and measured therein at the point of delivery. Vehicles for this purpose may be of any size or type acceptable for the materials hauled, provided that the body is of such shape that the actual contents may be readily and accurately determined. All vehicles

Term	Description
	shall be loaded to at least their water level capacity, and all loads shall be leveled when the vehicles arrive at the point of delivery.
<b>Asphalt Material</b>	Asphalt materials will be measured by the gallon (liter) or ton (kg). When measured by volume, such volumes will be measured at 60°F (16°C) or will be corrected to the volume at 60°F (16°C) using ASTM D1250 for asphalts. Net certified scale weights or weights based on certified volumes in the case of rail shipments will be used as a basis of measurement, subject to correction when asphalt material has been lost from the car or the distributor, wasted, or otherwise not incorporated in the work. When asphalt materials are shipped by truck or transport, net certified weights by volume, subject to correction for loss or foaming, will be used for computing quantities.
<b>Cement</b>	Cement will be measured by the ton (kg) or hundredweight (km).
<b>Structure</b>	Structures will be measured according to neat lines shown on the plans or as altered to fit field conditions.
<b>Timber</b>	Timber will be measured by the thousand feet board measure (MFBM) actually incorporated in the structure. Measurement will be based on nominal widths and thicknesses and the extreme length of each piece.
<b>Plates and Sheets</b>	The thickness of plates and galvanized sheet used in the manufacture of corrugated metal pipe, metal plate pipe culverts and arches, and metal cribbing will be specified and measured in decimal fraction of inch.
<b>Miscellaneous Items</b>	When standard manufactured items are specified such as fence, wire, plates, rolled shapes, pipe conduit, etc., and these items are identified by gauge, unit weight, section dimensions, etc., such identification will be considered to be nominal weights or dimensions. Unless more stringently controlled by tolerances in cited specifications, manufacturing tolerances established by the industries involved will be accepted.
<b>Scales</b>	<p>Scales must be tested for accuracy and serviced before use. Scales for weighing materials which are required to be proportioned or measured and paid for by weight shall be furnished, erected, and maintained by the Contractor, or be certified permanently installed commercial scales. Platform scales shall be installed and maintained with the platform level and rigid bulkheads at each end.</p> <p>Scales shall be accurate within 0.5% of the correct weight throughout the range of use. The Contractor shall have the scales checked under the observation of the RPR before beginning work and at such other times as requested. The intervals shall be uniform in spacing throughout the graduated or marked length of the beam or dial and shall not exceed 0.1% of the nominal rated capacity of the scale, but not less than one pound (454 grams). The use of spring balances will not be permitted.</p> <p>In the event inspection reveals the scales have been “overweighing” (indicating more than correct weight) they will be immediately adjusted. All materials received subsequent to the last previous correct weighting-accuracy test will be reduced by the percentage of error in excess of 0.5%.</p> <p>In the event inspection reveals the scales have been under-weighing (indicating less than correct weight), they shall be immediately adjusted. No additional payment to the Contractor will be allowed for materials previously weighed and recorded.</p> <p>Beams, dials, platforms, and other scale equipment shall be so arranged that the operator and the RPR can safely and conveniently view them.</p>

Term	Description
	<p>Scale installations shall have available ten standard 50-pound (2.3 km) weights for testing the weighing equipment or suitable weights and devices for other approved equipment.</p> <p>All costs in connection with furnishing, installing, certifying, testing, and maintaining scales; for furnishing check weights and scale house; and for all other items specified in this subsection, for the weighing of materials for proportioning or payment, shall be included in the unit contract prices for the various items of the project.</p>
<b>Rental Equipment</b>	<p>Rental of equipment will be measured by time in hours of actual working time and necessary traveling time of the equipment within the limits of the work. Special equipment ordered in connection with extra work will be measured as agreed in the change order or supplemental agreement authorizing such work as provided in paragraph 90-05 <i>Payment for Extra Work</i>.</p>
<b>Pay Quantities</b>	<p>When the estimated quantities for a specific portion of the work are designated as the pay quantities in the contract, they shall be the final quantities for which payment for such specific portion of the work will be made, unless the dimensions of said portions of the work shown on the plans are revised by the RPR. If revised dimensions result in an increase or decrease in the quantities of such work, the final quantities for payment will be revised in the amount represented by the authorized changes in the dimensions.</p>

**90-02 Scope of payment.** The Contractor shall receive and accept compensation provided for in the contract as full payment for furnishing all materials, for performing all work under the contract in a complete and acceptable manner, and for all risk, loss, damage, or expense of whatever character arising out of the nature of the work or the execution thereof, subject to the provisions of Section 70, paragraph 70-18, *No Waiver of Legal Rights*.

When the “basis of payment” subsection of a technical specification requires that the contract price (price bid) include compensation for certain work or material essential to the item, this same work or material will not also be measured for payment under any other contract item which may appear elsewhere in the contract, plans, or specifications.

**90-03 Compensation for altered quantities.** When the accepted quantities of work vary from the quantities in the proposal, the Contractor shall accept as payment in full, so far as contract items are concerned, payment at the original contract price for the accepted quantities of work actually completed and accepted. No allowance, except as provided for in Section 40, paragraph 40-02, *Alteration of Work and Quantities*, will be made for any increased expense, loss of expected reimbursement, or loss of anticipated profits suffered or claimed by the Contractor which results directly from such alterations or indirectly from their own unbalanced allocation of overhead and profit among the contract items, or from any other cause.

**90-04 Payment for omitted items.** As specified in Section 40, paragraph 40-03, *Omitted Items*, the RPR shall have the right to omit from the work (order nonperformance) any contract item, except major contract items, in the best interest of the Owner.

Should the RPR omit or order nonperformance of a contract item or portion of such item from the work, the Contractor shall accept payment in full at the contract prices for any work actually completed and acceptable prior to the RPR’s order to omit or non-perform such contract item.

Acceptable materials ordered by the Contractor or delivered on the work prior to the date of the RPR’s order will be paid for at the actual cost to the Contractor and shall thereupon become the property of the Owner.

In addition to the reimbursement hereinbefore provided, the Contractor shall be reimbursed for all actual costs incurred for the purpose of performing the omitted contract item prior to the date of the RPR's order. Such additional costs incurred by the Contractor must be directly related to the deleted contract item and shall be supported by certified statements by the Contractor as to the nature the amount of such costs.

**90-05 Payment for extra work.** Extra work, performed in accordance with Section 40, paragraph 40-04, *Extra Work*, will be paid for at the contract prices or agreed prices specified in the change order or supplemental agreement authorizing the extra work.

**90-06 Partial payments.** Partial payments will be made to the Contractor at least once each month as the work progresses. Said payments will be based upon estimates, prepared by the RPR, of the value of the work performed and materials complete and in place, in accordance with the contract, plans, and specifications. Such partial payments may also include the delivered actual cost of those materials stockpiled and stored in accordance with paragraph 90-07, *Payment for Materials on Hand*. No partial payment will be made when the amount due to the Contractor since the last estimate amounts to less than five hundred dollars.

The Owner may hold retainage from prime Contractors and provide for prompt and regular incremental acceptances of portions of the prime contract, pay retainage to prime Contractors based on these acceptances, and require a contract clause obligating the prime Contractor to pay all retainage owed to the subcontractor for satisfactory completion of the accepted work within 30 days after the Owner's payment to the prime Contractor. If Option 3 is selected, the percent withheld may range from 0% to 10% but in no case may it exceed 10%. When establishing a suitable retainage value that protects the Owner's interests, give consideration that the performance and payment bonds also provide similar protection of Owner interests. Owner may elect to incrementally release retainage if owner is satisfied its interest with completion of the project are protected in an adequate manner. If Option 3 is selected, insert the following clause and specify a suitable value where indicated:

- a. From the total of the amount determined to be payable on a partial payment, 10 percent of such total amount will be deducted and retained by the Owner for protection of the Owner's interests. Unless otherwise instructed by the Owner, the amount retained by the Owner will be in effect until the final payment is made except as follows:
  - (1) Contractor may request release of retainage on work that has been partially accepted by the Owner in accordance with Section 50-14. Contractor must provide a certified invoice to the RPR that supports the value of retainage held by the Owner for partially accepted work.
  - (2) In lieu of retainage, the Contractor may exercise at its option the establishment of an escrow account per paragraph 90-08.
- b. The Contractor is required to pay all subcontractors for satisfactory performance of their contracts no later than 30 days after the Contractor has received a partial payment. Contractor must provide the Owner evidence of prompt and full payment of retainage held by the prime Contractor to the subcontractor within 30 days after the subcontractor's work is satisfactorily completed. A subcontractor's work is satisfactorily completed when all the tasks called for in the subcontract have been accomplished and documented as required by the Owner. When the Owner has made an incremental acceptance of a portion of a prime contract, the work of a subcontractor covered by that acceptance is deemed to be satisfactorily completed.
- c. When at least 95% of the work has been completed to the satisfaction of the RPR, the RPR shall, at the Owner's discretion and with the consent of the surety, prepare estimates of both the contract value and the cost of the remaining work to be done. The Owner may retain an amount not less than twice the contract value or estimated cost, whichever is

greater, of the work remaining to be done. The remainder, less all previous payments and deductions, will then be certified for payment to the Contractor.

It is understood and agreed that the Contractor shall not be entitled to demand or receive partial payment based on quantities of work in excess of those provided in the proposal or covered by approved change orders or supplemental agreements, except when such excess quantities have been determined by the RPR to be a part of the final quantity for the item of work in question.

No partial payment shall bind the Owner to the acceptance of any materials or work in place as to quality or quantity. All partial payments are subject to correction at the time of final payment as provided in paragraph 90-09, *Acceptance and Final Payment*.

The Contractor shall deliver to the Owner a complete release of all claims for labor and material arising out of this contract before the final payment is made. If any subcontractor or supplier fails to furnish such a release in full, the Contractor may furnish a bond or other collateral satisfactory to the Owner to indemnify the Owner against any potential lien or other such claim. The bond or collateral shall include all costs, expenses, and attorney fees the Owner may be compelled to pay in discharging any such lien or claim.

**90-07 Payment for materials on hand.** Partial payments may be made to the extent of the delivered cost of materials to be incorporated in the work, provided that such materials meet the requirements of the contract, plans, and specifications and are delivered to acceptable sites on the airport property or at other sites in the vicinity that are acceptable to the Owner. Such delivered costs of stored or stockpiled materials may be included in the next partial payment after the following conditions are met:

- a. The material has been stored or stockpiled in a manner acceptable to the RPR at or on an approved site.
- b. The Contractor has furnished the RPR with acceptable evidence of the quantity and quality of such stored or stockpiled materials.
- c. The Contractor has furnished the RPR with satisfactory evidence that the material and transportation costs have been paid.
- d. The Contractor has furnished the Owner legal title (free of liens or encumbrances of any kind) to the material stored or stockpiled.
- e. The Contractor has furnished the Owner evidence that the material stored or stockpiled is insured against loss by damage to or disappearance of such materials at any time prior to use in the work.

It is understood and agreed that the transfer of title and the Owner's payment for such stored or stockpiled materials shall in no way relieve the Contractor of their responsibility for furnishing and placing such materials in accordance with the requirements of the contract, plans, and specifications.

In no case will the amount of partial payments for materials on hand exceed the contract price for such materials or the contract price for the contract item in which the material is intended to be used.

No partial payment will be made for stored or stockpiled living or perishable plant materials.

The Contractor shall bear all costs associated with the partial payment of stored or stockpiled materials in accordance with the provisions of this paragraph.

**90-08 Payment of withheld funds.** At the Contractor's option, if an Owner withholds retainage in accordance with the methods described in paragraph 90-06 *Partial Payments*, the Contractor may request that the Owner deposit the retainage into an escrow account. The Owner's deposit of retainage into an escrow account is subject to the following conditions:

- a. The Contractor shall bear all expenses of establishing and maintaining an escrow account and escrow agreement acceptable to the Owner.

**b.** The Contractor shall deposit to and maintain in such escrow only those securities or bank certificates of deposit as are acceptable to the Owner and having a value not less than the retainage that would otherwise be withheld from partial payment.

**c.** The Contractor shall enter into an escrow agreement satisfactory to the Owner.

**d.** The Contractor shall obtain the written consent of the surety to such agreement.

**90-09 Acceptance and final payment.** When the contract work has been accepted in accordance with the requirements of Section 50, paragraph 50-15, *Final Acceptance*, the RPR will prepare the final estimate of the items of work actually performed. The Contractor shall approve the RPR's final estimate or advise the RPR of the Contractor's objections to the final estimate which are based on disputes in measurements or computations of the final quantities to be paid under the contract as amended by change order or supplemental agreement. The Contractor and the RPR shall resolve all disputes (if any) in the measurement and computation of final quantities to be paid within 30 calendar days of the Contractor's receipt of the RPR's final estimate. If, after such 30-day period, a dispute still exists, the Contractor may approve the RPR's estimate under protest of the quantities in dispute, and such disputed quantities shall be considered by the Owner as a claim in accordance with Section 50, paragraph 50-16, *Claims for Adjustment and Disputes*.

After the Contractor has approved, or approved under protest, the RPR's final estimate, and after the RPR's receipt of the project closeout documentation required in paragraph 90-11, *Contractor Final Project Documentation*, final payment will be processed based on the entire sum, or the undisputed sum in case of approval under protest, determined to be due the Contractor less all previous payments and all amounts to be deducted under the provisions of the contract. All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

If the Contractor has filed a claim for additional compensation under the provisions of Section 50, paragraph 50-16, *Claims for Adjustments and Disputes*, or under the provisions of this paragraph, such claims will be considered by the Owner in accordance with local laws or ordinances. Upon final adjudication of such claims, any additional payment determined to be due the Contractor will be paid pursuant to a supplemental final estimate.

**90-10 Construction warranty.**

**a.** In addition to any other warranties in this contract, the Contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, workmanship, or design furnished, or performed by the Contractor or any subcontractor or supplier at any tier.

**b.** This warranty shall continue for a period of one year from the date of final acceptance of the work, except as noted. If the Owner takes possession of any part of the work before final acceptance, this warranty shall continue for a period of one year from the date the Owner takes possession.

**c.** The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Owner real or personal property, when that damage is the result of the Contractor's failure to conform to contract requirements; or any defect of equipment, material, workmanship, or design furnished by the Contractor.

**d.** The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for one year from the date of repair or replacement.

**e.** The Owner will notify the Contractor, in writing, within seven (7) days after the discovery of any failure, defect, or damage.

**f.** If the Contractor fails to remedy any failure, defect, or damage within 14 days after receipt of notice, the Owner shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.

**g.** With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall: (1) Obtain all warranties that would be given in normal commercial practice; (2) Require all warranties to be executed, in writing, for the benefit of the Owner, as directed by the Owner, and (3) Enforce all warranties for the benefit of the Owner.

**h.** This warranty shall not limit the Owner's rights with respect to latent defects, gross mistakes, or fraud.

**90-11 Contractor Final Project Documentation.** Approval of final payment to the Contractor is contingent upon completion and submittal of the items listed below. The final payment will not be approved until the RPR approves the Contractor's final submittal. The Contractor shall:

**a.** Provide two (2) copies of all manufacturers warranties specified for materials, equipment, and installations.

**b.** Provide weekly payroll records (not previously received) from the general Contractor and all subcontractors.

**c.** Complete final cleanup in accordance with Section 40, paragraph 40-08, *Final Cleanup*.

**d.** Complete all punch list items identified during the Final Inspection.

**e.** Provide complete release of all claims for labor and material arising out of the Contract.

**f.** Provide a certified statement signed by the subcontractors, indicating actual amounts paid to the Disadvantaged Business Enterprise (DBE) subcontractors and/or suppliers associated with the project.

**g.** When applicable per state requirements, return copies of sales tax completion forms.

**h.** Manufacturer's certifications for all items incorporated in the work.

**i.** All required record drawings, as-built drawings or as-constructed drawings.

**j.** Project Operation and Maintenance (O&M) Manual(s).

**k.** Security for Construction Warranty.

**l.** Equipment commissioning documentation submitted, if required.

## **END OF SECTION 90**

Page Intentionally Blank



## Special Provisions

## SPECIAL PROVISIONS

### CHARLOTTESVILLE-ALBERMARLE AIRPORT AUTHORITY CHARLOTTESVILLE ALBERMARLE AIRPORT

#### SECTION 1

#### PROJECT INFORMATION

**1. CONTRACT PROVISIONS.** The General Provisions and these Special Provisions are applicable to all divisions and sections of the Contract Documents and Specifications. It shall be the Contractor's responsibility to so inform all parties who should be bound or influenced thereby.

In the event there are discrepancies between the technical specifications, general provisions, and the special provisions, the interpretation most advantageous to the Owner shall apply.

**2. DESCRIPTION OF WORK.** The proposed Work includes the following:

Approximately 7,580 square yards of full depth concrete apron reconstruction, installation of 1,165 linear feet of concrete transition slab underneath bituminous asphalt taxiway pavement, isolated concrete slab replacement, relocation and replacement of drainage infrastructure within the full depth concrete apron reconstruction, and apron pavement marking.

**3. LOCATION OF THE WORK.** The site of the proposed Work is at **Charlottesville Albermarle Airport**.

**4. DEFINITIONS.**

**A. ADDENDA.** Written or graphic instruments issued prior to the opening of Bids which clarify, correct or change the bidding documents or the Contract Documents.

**B. BID.** The offer or proposal of the bidder submitted on the prescribed form setting forth the prices for the Work and services to be performed.

**C. DAY.** Unless otherwise defined shall mean "calendar" day.

**D. DRAWINGS.** The drawings which show the character and scope of the Work to be performed and which have been prepared or approved by the Engineer and are referred to in the Contract Documents.

**E. ENGINEER.** The term "Engineer" in the Contract Documents means Reynolds Smith and Hills, Inc; 2600 Park Tower Drive, Suite 101, Vienna, Virginia 22180.

**F. FIELD ORDER.** A written order issued by the Engineer which orders minor changes in the work consistent with the intent of the Contract Documents but which does not involve a change in the Contract Price or the Contract Time.

The Engineer may authorize minor changes in the work not involving an adjustment in the contract price or the contract time, which are consistent with the overall intent of the Contract Documents. These may be accomplished by a field order and shall be binding on the Owner, and also on the Contractor who shall perform the change promptly. If the Contractor believes that a field order justifies an increase in the contract price

or contract time, the Contractor shall make a claim under Section 50, Subsection 50-16, Claims for Adjustment and Disputes of the General Provisions before doing the Work.

**G. FURNISH or INSTALL or PROVIDE or SUPPLY.** Unless specifically limited in the context, the word "Furnish" or the word "Install" or the word "Provide" or the word "Supply" or any combination or similar directive or usage thereof, shall mean FURNISHING AND INCORPORATION IN THE WORK including all necessary labor, materials, equipment, and anything necessary to perform the work indicated.

**H. GOOD REPAIR.** Good repair shall be construed to mean any defect, functional or structural deterioration (except that from ordinary and reasonable use) which appreciably reduces the effectiveness or efficiency of the work or improvement for the purpose intended, or any serious departure from the standards of original construction described in the Contract Documents, shall be remedied by the Contractor. Such remedy will be made without further cost to the Owner, including in part, all damages caused by such defect, deficiency, deterioration or departure, and by its repair, replacement or correction.

**I. MAY.** Permissive.

**J. REFERENCE TO TRADE OR SUBCONTRACTORS.** When only one principal contract exists for all work covered by the Contract Documents, reference to trade or subcontractors in the Contract Documents shall not create any contractual relationship between the Owner and any trade or subcontractor, with whom the principal contractor may subcontract.

**K. SAMPLES.** Samples are physical examples furnished or constructed by the Contractor to illustrate materials, equipment, workmanship or finishes, and to establish standards by which the work will be judged.

**L. "SHALL" IMPLIED.** In the interest of conciseness, some sentences, statements, and clauses used in the specifications exclude any form of the verb "shall" normally expressed in a verb phrase with verbs such as "furnish", "install", "provide", "perform", "construct", "erect", "comply", "apply", "submit", or similar "verb", but any such sentences, statements, and clauses shall be interpreted to include the applicable form of the phrase "The Contractor shall" and the requirements described therein shall be interpreted as mandatory elements of the Contract.

**M. SHALL.** Mandatory.

**N. SUBCONTRACTOR.** Party supplying labor and material or any labor for work at the site of the project for, and under separate contract or agreement with the Contractor. Nothing contained in the Contract Documents shall create any contractual relationship between the Owner and any subcontractor.

**O. SUBSTANTIAL COMPLETION.** When the work is sufficiently complete so it may be safely, conveniently and beneficially utilized by the Owner for all of the purposes for which it was intended.

**P. WILL.** Mandatory.

**Q. SEDIMENT.** Soil and other debris that have eroded and have been transported by runoff water or wind.

**R. SOLID WASTES.** Rubbish, debris, and other discarded solid materials, except hazardous waste as defined in paragraph entitled, "Hazardous Waste," resulting from industrial, commercial, and agricultural operations and from community activities.

**S. RUBBISH.** Combustible and noncombustible wastes including paper, boxes, glass, crockery, metal, lumber, cans, and bones.

**T. DEBRIS.** Combustible and noncombustible wastes such as ashes and waste materials resulting from construction or maintenance and repair work, leaves, and tree trimmings.

**U. CHEMICAL WASTES.** Salts, acids, alkalis, herbicides, pesticides, and organic chemicals.

**V. SEWAGE.** Waste characterized as domestic sanitary sewage.

**W. GARBAGE.** Refuse and scraps resulting from consumption of food.

**X. HAZARDOUS WASTES.** Hazardous substances as defined in 40 CFR 261 or as defined by applicable state and local regulations.

**Y. OILY WASTES.** Petroleum products and bituminous materials.

**Z. HAZARDOUS MATERIALS.** As defined in DOT Regulation 49 CFR 171 and listed in CFR 172.

**AA. HAZARDOUS SUBSTANCES.** As defined in EPA PL 96-510.

**5. APPLICABLE DRAWINGS.** The drawings applicable to this project are included in the Index of Drawings as included herein.

**6. PROPOSAL REQUIREMENTS.** In addition to those herein before described items to be submitted with the Bidder's Proposal, the Bidder shall submit, with his Proposal, a list of all Subcontractors the Bidder proposes to use on the Work of this Contract.

After the Sponsor accepts the Bidder's Proposal and such Bidder is awarded a Contract, the successful Bidder may not substitute a Subcontractor listed in the Proposal without the prior written approval of the Owner. Such approval shall be obtained at least ten Calendar Days prior to the date scheduled for that Subcontractor to begin Work.

**7. CONTRACTOR'S LIABILITY INSURANCE.** The following provisions supplement the requirements specified in Special Provisions--Section 2.

The Contractor shall purchase and maintain such insurance as will protect him from claims set forth below which may arise out of or result from the Contractor's operations under the Contract, whether such operations be by himself or by any Subcontractor or by anyone directly or indirectly employed by any of them or by any one for whose acts any of them may be liable:

- (1) Claims under workmen's compensation, disability benefit and other similar employee benefits acts;
- (2) Claims for damages because of bodily injury, occupational sickness or disease, or death of his employees;
- (3) Claims for damages because of bodily injury, sickness or disease, or death of any person other than his employees;
- (4) Claims for damages insured by usual personal injury liability coverage which are sustained (1) by any person as a result of an offense directly or indirectly related to the employment of such person by the Contractor, or (2) by any other person; and
- (5) Claims for damages because of injury to or destruction of tangible property, including loss of use resulting therefrom.

General notes regarding liability:

- (a) The Comprehensive General Liability policy shall include explosion, collapse and underground (X-C-U) coverage.
- (b) The Contractual Liability shall include provisions for covering the indemnity specified under Paragraph 70-11 "Responsibility for Damage Claims" of the General Provisions.

(c) Comprehensive Automobile Liability shall include owned, leased, non-owned, and hired vehicles.

(d) The Comprehensive General Liability and Automobile Liability insurance shall include Contingent Liability and Contingent Property Damage Insurance to protect the Contractor against claims arising from the operations of Subcontractors, suppliers, vendors, or any person, firm or entity providing service to the Contractor.

(e) The Contractor's General Liability insurance shall include coverage to protect the Sponsor, Owner and Engineer from damage resulting either directly or indirectly from acts or omissions of the Contractor to existing buildings near the Work of the Contractor under the Contract, and the contents of such buildings.

(f) Certificates of the Contractor's Comprehensive Liability insurance, Comprehensive Automobile Liability insurance and Workmen's Compensation insurance shall be furnished to the Owner prior to commencement of Work. The certificates of insurance shall contain a provision that coverage afforded under the policies will not be canceled until at least 30 days prior written notice has been given to the Owner.

(g) Certificates of insurance shall be executed on AIA Document G705.

## **8. ACCESS TO THE WORK.**

Access to the Work shall be via the access routes designated on the Contract Layout Plan. The Contractor shall identify access routes with suitable signs, barricades and similar equipment. Access gates shall be locked and secured when not attended by the Contractor. The entire access route and construction site shall be kept free and clean of all debris at all times and maintained in good repair by the Contractor. All damage to the access route caused by the actions of the Contractor or his agents shall be immediately repaired to the satisfaction of the Owner.

No separate payment will be made for complying with the requirements of this paragraph "Access to the Work." No other access to these Work sites will be permitted without written approval of the Engineer. Contractor's vehicles and equipment, including vehicles and equipment of the Subcontractors and others coming under the Contractor's control, will not be permitted to traverse other airfield areas or pavements without written approval of the Engineer. Contractor's vehicles, equipment and materials may be stored in the area designated on the Plans. Upon completion of the Work, the storage area shall be cleaned up and returned to its original condition to the satisfaction of the Owner. No separate payment will be made for cleanup and restoration of the storage area. Personal services, such as canteen trucks, will not be permitted beyond this area and drivers of vehicles being operated beyond this area shall be subject to loss of permission to enter the construction site.

## **9. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.**

(1) Shop Drawings are drawings, diagrams, schedules and other data specially prepared for the Work by the Contractor or any Subcontractor, manufacturer, supplier or distributor to illustrate some portion of the Work.

(2) Product data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams or other information furnished by the Contractor to illustrate a material, product or system for some portion of the Work.

(3) Samples are physical examples which illustrate materials, equipment or workmanship and establish standards by which the Work will be judged.

(4) The Contractor shall review, approve and submit, with reasonable promptness and in such sequence as to cause no delay in the Work or in the Work of the Owner or any other separate Contractor(s), all Shop Drawings, Product Data and Samples required by the Contract Documents.

(5) By approving and submitting Shop Drawings, Product Data and Samples, the Contractor represents that he has determined and verified all materials, field measurements and field construction criteria

related thereto, or will do so, and that he has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

(6) The Contractor shall not be relieved of responsibility for any deviation from the requirements of the Contract Documents by the Engineer's approval of Shop Drawings, Product Data or Samples unless the Contractor has specifically informed the Engineer in writing of such deviation at the time of submission and the Engineer has given written approval of the specific deviation. The Contractor shall not be relieved of responsibility for errors or omissions in the Shop Drawings, Product Data or Samples by the Engineer's approval thereof.

(7) The Contractor shall direct specific attention, in writing, or on resubmitted Shop Drawings, Product Data or Samples, to revisions other than those requested by the Engineer on previous submittals.

(8) No portion of the Work requiring submission of a Shop Drawing, Product Data or Sample shall be commenced until the submittals have been approved by the Engineer. All such portions of the Work shall be in accordance with approved submittals.

(9) The Contractor shall not reproduce the Engineer's project drawings for Shop Drawing use without written approval of the Engineer.

(10) The Contractor shall submit five copies, or at Engineer's option, one reproducible copy and one print of all Shop Drawings required for the Work of the various trades unless greater quantities are specifically requested for certain equipment. Of these, three copies, or the reproducible copy, will be annotated as appropriate and returned to the Contractor with appropriate action indicated. By agreement with the Engineer, the Contractor may submit more than the required number of copies. Receipt of less than the required number of copies will be cause for withholding the Shop Drawings from being checked until receipt of the necessary additional copies. Shop Drawings shall be forwarded to **Reynolds, Smith and Hills, Inc.; 2600 Park Tower Drive, Suite 101, Vienna, Virginia 22180**, marked to the attention of **Chad A. Ackley, PE**. The Contractor's letter of submittal must conform to the typical Contractor's "Transmittal Letter" which is available from the Engineer. The quantity of transmittal letters to be submitted shall be equal to the number of sets of drawings or brochures being submitted plus one. Each drawing or part of the brochure shall be listed separately on the letter and identified as indicated thereon. Failure to do this will cause rejection of the submittal. The Engineer will return to the Contractor the same transmittal letter, with the Shop Drawing disposition noted thereon along with the drawings or brochures when the review is completed. The Contractor shall forward separate transmittal letters for submitting each group of Shop Drawings common to a Specification Section.

(11) In checking Shop Drawings prior to submittal, the Contractor is requested to note corrections or comments on the drawings in orange pencil.

(12) Drawings returned to the Contractor will be stamped "Approved," "Approved as Noted," "Returned for Corrections," or "Not Approved." Drawings stamped "Approved as Noted" need not be returned for further approval if the notations are acceptable to the Contractor and Subcontractors. Drawings stamped "Returned for Corrections" or "Not Approved" shall require new submission. Comments and corrections by the Engineer will be made in red pencil on blue or black line prints and in yellow pencil on white line prints.

(13) Samples shall be submitted to the attention of Chad A. Ackley, PE, accompanied with the same transmittal letter prescribed for Shop Drawings. Checking by Contractor of samples before transmittal is required the same as for Shop Drawings.

## **10. PROJECT DOCUMENTATION.**

(a) Project Drawings: A field set of Plans and Specifications, supplied by the Contractor, shall remain on the job site at all times and shall be available at all times to the Engineer.

The Contractor shall immediately include plainly and conspicuously on the field set of drawings, and at appropriate paragraphs in the specifications, all changes or corrections made by addenda and Change Orders as they are issued.

Approved copies of all shop drawings and other submittals are to be kept on the job site at all times and shall be available at all times to the Engineer.

Changes and deviations from the existing conditions shall be submitted in writing for approval prior to installation. In no case shall any unspecified equipment or materials be installed without prior approval by the Engineer.

(b) Record Documents:

(1) Definition: Record copies are defined to include those documents or copies relating directly to performance of the Work, which Contractor is required to prepare or maintain for Owner's records, recording the Work as actually performed. In particular, record copies show changes in the Work in relation to way in which shown and specified by original Contract Documents; and show additional information of value to Owner's records, but not indicated by original Contract Documents. Record copies include newly prepared drawings (if any are specified), marked-up copies of Contract drawings, shop drawings, Specifications, addenda and Change Orders, marked-up product data submittals, record samples, field records for variable and concealed conditions such as excavations and foundations, and miscellaneous record information on Work which is otherwise recorded only schematically or not at all.

(2) Record Drawings: Contractor shall maintain a set of record drawings at the job site. These shall be kept legible and current and shall be available for inspection at all times by the Engineer. The Contractor shall show all changes or Work added on these record drawings in a contrasting color.

(i) Mark-Up Procedure: During progress of the Work, maintain a white-print set (blue-line or black-line) of Contract drawings and shop drawings, with mark-up of actual installations which vary substantially from the Work as originally shown. Mark whatever drawing is most capable of showing actual physical condition, fully and accurately. Where shop drawings are marked up, mark cross-reference on Contract drawings at corresponding location. Mark with erasable colored pencil, using separate colors where feasible to distinguish between changes for different categories of Work at same general location. Mark-up important additional information which was either shown schematically or omitted from original drawings. Give particular attention to information on Work concealed, which would be difficult to identify or measure and record at a later date. Note alternate numbers, Change Order numbers and similar identification. Require each person preparing mark-up to initial and date mark-up and indicate name of firm. Label each sheet "PROJECT RECORD" in 1-1/2-inch high letters.

In showing changes in the Work, use the same legends as used on the original drawings. Indicate exact locations by dimensions and exact elevations by job datum. Give dimensions from a permanent point.

(ii) Preparation of Transparencies: In preparation for Certification of Substantial Completion on last major portion of the Work, review completed mark-up of record drawings and shop drawings with the Engineer. The Engineer will then proceed with preparation of a full set of corrected transparencies for Contract drawings. The Engineer will date each updated drawing and label each sheet "PROJECT RECORD" in 1-1/2-inch high letters. Printing as required herein is the responsibility of the Engineer.

(iii) Copies, Distribution: Upon completion of transparency record drawings, the Engineer shall prepare three blue-line or black-line prints of each drawing, regardless of whether changes and additional information were recorded thereon. The Engineer shall then organize each of three copies into manageable sets, bind with durable paper cover sheets, and print suitable titles, dates. Mark-up set of prints maintained during the construction period shall be bound in the same manner. The Engineer shall also organize transparencies into sets matching print sets, place set in a durable tube-type drawing container (with end caps) and mark end cap of each with suitable identification. The Engineer will retain one copy set. At completion of project, the Engineer shall submit set of mylars, with changes noted thereon, to the Owner.

(3) Record drawings shall contain the names, addresses and phone numbers of the general Contractor and major Subcontractors.

(4) The Engineer shall be the sole judge of the acceptability of the record drawings. Receipt and acceptance of the as-built drawings is a prerequisite for Final Payment.

(c) Record Specifications:

(1) During progress of the Work, maintain one copy of Specifications, including addenda, Change Orders and similar modifications issued in printed form during construction, mark-up variations (of substance) in actual Work in comparison with text of Specifications and modifications as issued. Give particular attention to substitutions, selection of options, and similar information on Work where it is concealed or cannot otherwise be readily discerned at a later date by direct observation. Note related record drawing information and product data, where applicable. Upon completion of mark-up, submit to the Engineer for Owner's records. Label front cover "PROJECT RECORD" in 1-1/2-inch high letters.

(2) Where manual is printed on one side of page only, mark variation on blank left-hand pages of project manual, facing printed right-hand pages containing original text affected by variation.

(d) Record Product Data: During progress of the Work, maintain one copy of each product data submittal, and mark-up significant variations in the actual Work in comparison with submitted information. Include both variations in product as delivered to site, and variations from manufacturer's instructions and recommendations for installation. Give particular attention to concealed products and portions of the Work which cannot otherwise be readily discerned at a later date by direct observation. Note related Change Orders and mark-up of record drawings and Specifications. Upon completion of mark-up, submit complete set of product data submittal to the Engineer for Owner's records. Label each data submittal "PROJECT RECORD" in 1-1/2-inch high letters.

(e) Record Sample Submittal: Immediately prior to date(s) of Substantial Completion, the Engineer and Owner's personnel will meet with Contractor at site and will determine if any of submitted samples maintained by Contractor during progress of the Work are to be transmitted to Owner for record purposes. Comply with the Engineer's instructions for packaging, identification marking and delivery to Owner's sample storage space. Dispose of other samples in manner specified for disposal of surplus and waste materials, unless otherwise indicated by the Engineer.

(f) Miscellaneous Record Submittals: Refer to other sections of these Specifications for requirements of miscellaneous recordkeeping and submittals in connection with actual performance of the Work. Immediately prior to date(s) of Substantial Completion, complete miscellaneous records and place in good order, properly identified and bound or filed, ready for continued use and reference. Submit to Engineer for Owner's records. Categories of requirements resulting in miscellaneous Work records are recognized to include, but not be limited to, the following:

(1) Required field records on excavations, foundations underground construction, wells and similar Work.

(2) Accurate survey showing locations and elevations of underground lines, including invert elevations of drainage piping, valves, tanks and manholes.

(3) Surveys establishing lines and levels of building.

(4) Soil treatment certification.

(5) Inspection and Test Reports: Where not processed as shop drawings or product data.

(6) Concrete mix design record.

(7) Concrete block certification.



(g) Project Closeout: Closeout is hereby defined to include general requirements near end of Contract time, in preparation for Final Acceptance, Final Payment, normal termination of Contract, occupancy by Owner and similar actions evidencing completion of the Work. Specific requirements for individual units or Work are specified in other sections. Time of closeout is directly related to Substantial Completion, and therefore may be a single-time period for entire Work or a series of time periods for individual parts of the Work which have been certified as Substantially Complete at different dates. The time variation, if any, shall be applicable to other provisions of this section.

(h) Prerequisites to Substantial Completion:

(1) Prior to requesting the Engineer's inspection for Certification of Substantial Completion, for either entire Work or portions thereof, complete the following and list no exceptions in request.

(i) In progress payment request coincident with, or first following date claimed, show 100 percent completion for portion of Work claimed as "Substantially Completed," or list incomplete items, value of incompleteness and reasons for being incomplete.

(ii) Include supporting documentation for completion as indicated in the Contract Documents.

(iii) Submit statement showing accounting of changes to the Contract sum.

(iv) Advise Owner of pending insurance change-over requirements.

(v) Obtain and submit releases enabling Owner's full and unrestricted use of the Work and access to services and utilities, including, where required, occupancy permits, operating certificates and similar releases.

(vi) Deliver tools, spare parts, extra stocks of materials and similar physical items to Owner.

(vii) Make final change-over of locks and transmit keys to Owner, and advise Owner's personnel of change-over in security provisions.

(viii) Complete start-up testing of systems, and instructions of Owner's operating-maintenance personnel. Discontinue, or change over, and remove from project site temporary facilities and services, along with construction tools and facilities, mock-ups and similar elements.

(2) Inspection Procedures: Upon receipt of Contractor's request, the Engineer will proceed with inspection or advise Contractor of prerequisites not fulfilled. Following initial inspection, the Engineer will prepare Certificate of Substantial Completion or advise Contractor of Work which must be performed prior to issuance of certificate and repeat inspection when requested and assured that Work has been substantially completed. Results of completed inspection will form initial "punch list" for Final Acceptance.

(i) Prerequisites to Final Acceptance:

(1) Prior to requesting the Engineers' final inspection for Certification of Final Acceptance as required by paragraph 50-15, Final Acceptance of the General Provisions, complete the following and list known exceptions in request:

(i) Submit certified copy of Engineer's final punch list of itemized Work to be completed or corrected, stating that each item has been completed or otherwise resolved for acceptance, endorsed and dated by the Engineer.

(ii) Submit final meter readings for utilities, measured record of stored fuel, and similar data as of time of Substantial Completion or when Owner took possession of and responsibility for corresponding elements of the Work.

(iii) Complete final cleaning up requirements, including touch-up of marred surfaces.

(iv) Touch-up and otherwise repair and restore marred exposed finishes.

(2) Reinspection Procedures: Following Substantial Completion, the Contractor shall correct or remedy all punch list items to the satisfaction of the Engineer and Owner within a two (2)-week period after the date of Substantial Completion. If subsequent inspections are necessary after the two-week period in order to eliminate all deficiencies, the cost of all subsequent inspections with respect to Owner's and Engineer's time shall be paid by the Contractor. When ready, the Contractor shall request in writing, a final inspection of the Work. Upon completion of reinspection, Engineer will prepare a Certificate of Final Acceptance or advise Contractor of Work not completed or obligations not fulfilled as required for Final Acceptance. If necessary, procedures will be repeated.

(j) Prerequisites to Final Payment:

(1) Final Payment: Final Payment will be made after Final Acceptance of the project by the Engineer and Owner upon request by the Contractor on condition that the Contractor:

(i) Furnish properly executed complete release of lien from all material men and Subcontractors who have furnished materials or labor for the Work and submit supporting documentation not previously submitted and accepted. Include certificates of insurance for products and completed operations where required.

(ii) Furnish Contractor's Affidavit of Release of Liens (2 copies) that all material men and Subcontractors have been paid in full. In the event they have not been paid in full, the Owner shall retain a sufficient sum to pay them in full and at his option, may make direct payment as provided in the appropriate Commonwealth of Virginia statutes, as amended, to obtain complete releases of lien.

(iii) Furnish Contractor's Affidavit of Debts and Claims (2 copies).

(iv) Furnish required sets of record drawings and maintenance and operating instructions of new mechanical equipment.

(v) Furnish guarantees signed by Subcontractors, material suppliers and countersigned by the Contractor for operating equipment.

(vi) Submit specific warranties, workmanship-maintenance bonds, maintenance agreements, final certifications and similar documents.

(v) Furnish a signed guarantee, in form acceptable to Engineer and Owner agreeing to repair or replace as decided by the Engineer, all Work and materials that prove defective within one (1) year (or more) from the date of Final Acceptance, including restoration of all other Work damaged in making such repairs or replacements.

(vi) Furnish consent of Surety to Final Payment.

(vii) Submit updated final statement, accounting for final changes to Contract sum.

(viii) Submit evidence of final, continuing insurance coverage complying with insurance requirements.

(ix) Certify that all social security, employment and all other taxes (city, state, federal government) have been paid.

(x) Provide receipt, as applicable, of affidavits certifying all labor standards of local, state or federal requirements have been complied with by the Contractor.

(xi) Submit actual DBE participation percentages.

(k) Record Document Submittals: Specific requirements for record documents are shown in Section, RECORD DOCUMENTS. Other requirements are indicated in the General Provisions. General submittal requirements are indicated in "Submittals" sections. Do not use record documents for construction purposes; protect from deterioration and loss in a secure, fire-resistive location; provide access to record documents for the Engineer's reference during normal working hours.

(1) Record Drawings: The Engineer shall organize record drawing sheets into manageable sets, bind with durable paper cover sheets and print suitable titles, dates and other identification on cover of each set.

(2) Record Specifications: Upon completion of mark-up, submit to the Engineer for Owner's records.

(3) Record Product Data: Upon completion of mark-up, submit complete set to the Engineer for Owner's records.

(4) Record Sample Submittal: Comply with the Engineer's instructions for packaging, identification marking and delivery to Owner's sample storage space.

(5) Miscellaneous Record Submittals: Complete miscellaneous records and place in good order, properly identified and bound or filed, ready for continued use and reference. Submit to the Engineer for Owner's records.

(6) Maintenance Manuals: Complete, place in order, properly identify and submit to the Engineer for Owner's records.

(l) Closeout Procedures: General Operating and Maintenance Instructions: Arrange for each installer or Work requiring continuing maintenance or operation to meet with Owner's personnel, at project site, to provide basic instructions needed for proper operation and maintenance of entire Work. Include instructions by manufacturer's representatives where installers are not expert in the required procedures. Review maintenance manuals, record documentation, tools, spare parts and materials, lubricants, fuel, identification system, control sequences; hazards, cleaning and similar procedures and facilities. For operational equipment, demonstrate start-up, shut-down, emergency operations, noise and vibration adjustments, safety, economy, efficiency adjustments and similar operations. Review maintenance and operations in relation with application warranties, agreements to maintain bonds, and similar continuing commitments.

## **11. FINAL CLEANING.**

(a) Provide final cleaning of the Work, at time indicated, consisting of cleaning each surface or unit of Work to normal "clean" condition.

(b) Removal of Protection: Remove temporary protection devices and facilities which were installed during course of the Work to protect previous completed Work during remainder of construction period.

(c) Compliances: Comply with safety standards and governing regulations for cleaning operations. Do not burn waste materials at site, or bury debris or excess materials on Owner's property, or discharge volatile

or other harmful or dangerous materials into drainage systems; remove waste materials from site and dispose of in a lawful manner.

Where extra materials of value remaining after completion of associated Work have become Owner's property, dispose of these as directed by owner.

**END OF SPECIAL PROVISIONS - SECTION 1**

Page Intentionally Blank

## SPECIAL PROVISIONS

### CHARLOTTESVILLE-ALBERMARLE AIRPORT AUTHORITY CHARLOTTESVILLE ALBERMARLE AIRPORT

#### SECTION 2

#### INSURANCE REQUIREMENTS

**1. REQUIREMENTS OF CONTRACTOR LIABILITY INSURANCE.** The Contractor shall procure and maintain at his own expense, during the life of this Contract, liability insurance with limits of coverage not less than the amounts as hereinafter specified. The policies shall be written by reputable companies authorized to do business in the Commonwealth of Virginia, rated no less than A-9 by A.M. BEST. All such insurance shall be subject to the approval of the Owner for adequacy of protection, and shall include a provision preventing cancellation without thirty days prior notice to the Owner in writing. At the time of execution of the Contract, the successful Bidder shall furnish the Owner evidence that appropriate insurance has been procured and will be maintained for the life of the Contract liability and compensation insurance.

The Contractor will provide protection from claims set forth below which may arise out of or result from the Contractor's performance and furnishing of the Work and the Contractor's other obligations under the Contract as follows:

1. Commercial General Liability - \$8,000,000 per loss for bodily injury, personal injury and property damage. If a general aggregate limit is used, either the general aggregate limit shall apply separately to this project/location or the general aggregate limit shall be twice the required occurrence limit.
2. Automobile Liability - \$ 3,000,000 per accident for bodily injury and property damage,
3. Employer's Liability - \$ 1,000,000 per accident for bodily injury or disease.
4. Umbrella Liability - \$ 5,000,000 aggregate limit.
5. Workers' Compensation coverage as required by law.
6. The Contractor will be required to provide a Certificate of Insurance and a copy of the additional insured endorsement, indicating:
  - Commercial General Liability insurance, including contractual liability, and defense costs outside of policy limits. Contractor's policy will be primary and be on an occurrence basis.
  - Automobile Liability insurance
  - Umbrella Liability insurance
  - Workers' Compensation insurance

In carrying out any of the Contract provisions or in exercising any power or authority granted to the Contractor by this Contract, there shall be no liability upon the Engineer, his authorized representatives, or any official of the Owner, either personally or as an official of the Owner. It is understood that in such matters they act solely as agents and representatives of the Owner. **THE CHARLOTTESVILLE-ALBEMARLE AIRPORT AUTHORITY, CHARLOTTESVILLE ALBERMARLE AIRPORT, AND THE ENGINEER SHALL BE AN ADDITIONAL**

INSURED AND PROTECTED, IN THE CONTRACTOR'S LIABILITY INSURANCE POLICY, FROM ALL CLAIMS ARISING OUT OF, OR IN CONNECTION WITH, ANY OPERATIONS CONDUCTED IN CONNECTION WITH THIS CONTRACT BY THE CONTRACTOR OR HIS SUBCONTRACTORS.

**END OF SPECIAL PROVISIONS - SECTION 2**

## SPECIAL PROVISIONS

### CHARLOTTESVILLE-ALBERMARLE AIRPORT AUTHORITY CHARLOTTESVILLE ALBERMARLE AIRPORT

#### SECTION 3

#### MISCELLANEOUS

**1. BID AND CONTRACT ACCEPTANCE.** The Charlottesville-Albemarle Airport Authority reserves the following rights: to accept or reject any or all bids; and to award the Contract to the lowest responsive and responsible Bidder whose bid is determined by the Authority to be in its best interest. Further, any and all agreements arising out of these proposals shall not be binding or valid against the Authority, its departments, officers, employees, or agents unless fully executed in writing and authorized by the Charlottesville-Albemarle Airport Authority.

**2. PROVISIONS REQUIRED BY LAW DEEMED INSERTED.** Each and every provision of law and clause required by law to be inserted in the Contract Documents shall be deemed to be inserted herein and the Contract shall be read and enforced as though it were included herein. If, for any reason, any such provision is not inserted in the Contract, or is not correctly inserted, then upon application of either party, the Contract shall forthwith be physically amended to make such insertion or correction.

**3. CORRELATION OF DOCUMENTS.**

**A.** The drawings and specifications are cooperative and supplementary. Portions of the work which can be best be illustrated by the drawings may not be included in the specifications and portions best described by the specifications may not be depicted on the drawings. All items necessary or incidental to completely construct or erect the work shall be furnished, whether called for in the specifications or shown on the drawings. Anything mentioned in the specifications and not shown on the drawings, or anything shown or mentioned on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both.

**B.** In case of disagreement between the drawings and specifications, or within either document itself, the better quality or greater quantity of work shall be estimated and included in the bid and contract price and the matter drawn to the Engineer's attention for decision.

**4. NOTICE AND SERVICE THEREOF.** Where the manner of giving notice is not otherwise provided for in the Contract Documents, any notice to the Contractor from the Owner relative to any part of the Contract shall be in writing and considered delivered and the service thereof completed, when said notice is posted, by certified or registered mail, to the Contractor at the address given in the Contractor's proposal, or at the last business address known to him who gives the notice, or delivered in person to the Contractor or his authorized representative on the site. It is mutually agreed that such notice shall be sufficient and adequate.

**5. SUBCONTRACTING.**

**A.** The Contractor may utilize the services of specialty or minority subcontractors on those parts of the work which, under normal contracting practices, are performed by specialty or minority subcontractors.

**B.** The Owner reserves the right to approve subcontractors for any work. The Contractor, if requested by the Owner, shall submit to the Owner the proposed award and such information as the Owner may require concerning any subcontractor.



**C.** The Contractor shall be as fully responsible to the Owner for the acts and omissions of his subcontractors, and of persons either directly or indirectly employed by them, or under their control, as he is for the acts and omissions of persons directly employed by him.

**D.** The Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the work to bind subcontractors to the Contractor by the terms of the Contract Documents insofar as applicable to the work of subcontractors, and to give the Contractor the same power as regards terminating any subcontract that the Owner may exercise over the Contractor under any provision of the Contract Documents.

**E.** Nothing contained in the Contract Documents shall create any contractual relationships between any subcontractor and the Owner.

## **6. PROTECTION OF PERSONS.**

**A.** The Contractor shall:

- (1) At all times protect the lives and health of his employees under the Contract;
- (2) Take all necessary precautions for the safety of all persons on or in the vicinity of the project site.
- (3) Comply with all applicable provisions of Federal, State and Municipal safety laws and building codes.
- (4) Comply with all pertinent provisions of the Manual of Accident Prevention in Construction issued by the Associated General Contractors of America, Inc., latest edition, to prevent accidents or injury to persons on or about or adjacent to the premises where the work is being performed. He shall erect and properly maintain at all times, as required by the conditions and progress of the work, all necessary safeguards for the protection of persons and shall post danger signs warning against the hazards created in part by features of construction such as protruding nails, rod hoists, well holes, falling materials, etc., and he shall designate a responsible member of his organization on the work site whose duty shall be the prevention of accidents;
- (5) Provide for all safeguards for the protection of those having Right-of-Entry during field review and observation of the work.

**B.** The Contractor shall comply with all provisions of the "Williams-Steiger Occupational Safety and Health Act of 1970" including any amendments thereto and rules and regulations issued pursuant thereto, applicable to the Work and performance of the Contract. Where a State in which work is performed has passed legislation bearing on Occupational Safety and Health, such legislation and amendments thereto, together with rules and regulations issued pursuant thereto, shall be complied with by the Contractor.

## **7. AUTHORITY OF ENGINEER.**

**A.** The Engineer, through its duly authorized representatives, shall furnish engineering services during construction of the work to the extent provided in the Contract Documents. He shall observe and review the work in the process of construction or erection. Compliance with the Contract Documents shall be the Contractor's responsibility notwithstanding such observation or review. The Engineer has authority to recommend suspension of the work to the Owner when it appears such suspension may be necessary to accomplish the proper implementation of the intent of the Contract Documents. The authority to observe, review or recommend suspension of the work, or exercise such other authority as may be granted by the Contract Documents, shall not be construed or interpreted to mean supervision of construction, which is the Contractor's responsibility, nor make the Engineer responsible for providing a safe place for the performance of work by the Contractor or by the Contractor's employees, or those of suppliers or subcontractors, or for access, visits, use, work, travel, or occupancy by any other person. The Engineer shall also have the authority to reject any work, materials, or equipment which

do not conform to the Contract Documents and to decide technical questions which arise in the execution of the work.

**B.** The Engineer shall determine the amount, quality, acceptability, and fitness of the several kinds of work, materials, equipment and supplies which are to be paid for under the Contract and shall decide questions which may arise in relation to said work and its compliance with the Contract Documents. The Engineer's estimates and decisions shall be final and conclusive, except as otherwise expressly provided in case any question shall arise between the parties to the Contract relative to the Contract Documents, the determination or decision of the Engineer shall be a condition precedent to the right of the Contractor to receive any money or payment for work under the Contract affected in any manner or to any extent by such question.

**C.** The Engineer shall decide the meaning and intent of any portion of the Contract Documents where the same may be found obscure or be in dispute.

## **8. "GOOD REPAIR" PERIOD.**

**A.** The Contractor hereby agrees to keep all work constructed under the Contract in good repair for a minimum period of one (1) year, unless a longer period is otherwise specified in the Contract Documents, from the date of acceptance of all of the work by the Owner. No provision of the Contract documents shall be valid which limits the "Good Repair" period to less than one (1) year from the date of acceptance of all of the work by the Owner. The work may be phased. If the work is phased, each phase of Work completed shall be inspected and approved for use by the Owner but shall not be accepted until all work for all phases is complete and a final inspection for all work has been performed.

**B.** It is intended that this provision shall apply whether or not bond is required, as a personal obligation of the Contractor.

**C.** The obligations of the Contractor as herein provided shall be in addition to and not in limitation of any obligations imposed upon him by special guarantees required by the Contract Documents or otherwise prescribed by law.

**9. VARIATION FROM ESTIMATED QUANTITIES.** The Contractor may reasonably expect a variation in estimated quantities such that the total payment for the completed work may range from 75 to 125 percent of the total amount of the Contract based on the estimated quantities defined in the proposal. The Contractor will not be allowed any claims for anticipated profits, for loss of profits, or for any damages because of a difference between the estimate of any item defined in the proposal and the amount of the item actually required or for the elimination of any part of the work. Funds for construction of the work herein contemplated are limited. The Owner reserves the right to eliminate or reduce the items of the proposal or any of the work as may be required to bring the cost of the work within the limits of available funds.

**10. WATER FOR CONSTRUCTION.** Water used for construction of this project will be furnished by the Contractor. The Contractor shall make the necessary arrangements with the Owner of the source of water for securing and/or transporting such water. No separate payment will be made for water used but the cost thereof shall be included in the various items of the proposal and bid schedule.

**11. LIGHTS AND POWER.** The Contractor shall provide, at his own expense, temporary lighting and facilities required for the proper prosecution and inspection of the work.

**12. COORDINATION WITH OTHERS.** In the event other contractors are doing work in the same area simultaneously with this project, the Contractor shall coordinate his proposed construction with that of the other contractors. The Contractor shall notify the Engineer of said coordination attempts and the results.

**13. TESTING, INSPECTION, AND CONTROL.** The Contractor's Quality Control (QC) program will be paid by the Contractor and reimbursed according to the C-100 specification. The Owner will pay separately for Quality Assurance (QA) testing. QA testing will be coordinated through the RPR. The Owner shall pay for all passing tests;

the Contractor shall pay for all failing tests. Charges for failing tests will be deducted from the Contractor's earnings at the end of each month when the Contractor submits his periodic pay requests. The Contractor shall furnish, at his own expense, all necessary specimens for testing of the materials, as required by the Engineer. The Contractor shall be responsible for notifying the testing laboratory to pick up the test samples. Also, the Engineer reserves the right to test at any location on the project, and at any frequency he deems necessary before, during and after incorporation of all materials into the project to satisfy himself and ensure that all materials meet the specified requirements. All materials utilized in the project must meet specification requirements before, during and after incorporation into the project. Any additional testing that the Contractor deems necessary to ensure himself that the materials he is installing meet the required specifications and/or as a proof of the authorized testing laboratory shall be solely the expense of the Contractor whether the tests pass or fail.

**14. TRADE NAMES AND MATERIALS.** No material that has been used by the Contractor for any temporary purpose whatsoever is to be incorporated in the permanent structure without written consent of the Engineer.

Where materials or equipment are specified by a trade or brand name, it is not the intention of the Owner to discriminate against an equal product of another manufacturer, but rather to set a definite standard of quality or performance, and to establish an equal basis for the evaluation of bids. Where the words "equivalent", "proper", or "equal to" are used, they shall be understood to mean that the thing referred to shall be proper, the equivalent of, or equal to some other thing, in the opinion or judgement of the Engineer. Unless otherwise specified, all materials shall be the best of their respective kinds and shall be in all cases fully equal to approved samples. Notwithstanding that the words "or equal to" or other such expressions may be used in the plans and specifications in connection with the material, manufactured article or process, the material, manufactured article or process specifically designated shall be used, unless a substitute shall be approved in writing by the Engineer and the Engineer shall have the right to require the use of such specifically designated material, article or process.

**15. PROPERTY LINES AND MONUMENTS.** The Contractor shall protect all property corner markers and any other monument, and when any such markers or monuments are in danger of being disturbed, they shall be properly referenced and if disturbed shall be reset at the expense of the Contractor.

**16. FENCES AND DRAINAGE CHANNELS.** Boundary fences or other improvements removed to permit the installation of the work shall be replaced in the same location and left in a condition as good or better than that in which they were found. Existing fences not to be removed and intersecting with new fencing (fencing outside airport property) shall be connected to the new fencing in a manner acceptable to the fence owner and the Owner and/or Engineer.

Where surface drainage channels are disturbed or blocked during construction, they shall be restored to their original condition of grade and cross section after the work of construction is completed.

**17. DISPOSAL OF WASTE AND SURPLUS EXCAVATION.** All trees, stumps, slashings, brush or other debris to be removed from the site as a preliminary to the construction work shall be removed from the property and legally disposed of in a manner approved by the Engineer and at a site approved by the Owner. No burning on site will be permitted.

All excavated earth in excess of that required for embankment and backfill shall be disposed of in a satisfactory manner as shown on the plans or as directed by the Engineer to a site approved by the Owner.

**18. AIR POLLUTION.** The Contractor shall comply with all Federal, State and Local Requirements.

**19. EXISTING UTILITIES AND SERVICE LINES.** The Contractor shall be responsible for the protection of all existing utilities or service lines crossed or exposed by his construction operations. Where existing utilities or service lines are cut, broken or damaged, the Contractor shall replace or repair the utilities or service lines with the same type of original material and construction, or better, at his own cost and expense, with the exception of those items included in the bid schedule.

**20. RECORDS OF MATERIALS PURCHASED.** By a certain time each month as defined and established at the preconstruction conference, the Contractor shall furnish to the Engineer, duplicate copies of all invoices for materials furnished to be incorporated into the work, plus a statement of all materials previously included on monthly estimates and incorporated into the work during the preceding month. This information is to be used to determine the value of materials on hand to be included in the monthly estimate for periodical payment.

**21. CONTRACTOR ACCESS TO PROJECT SITE.** The Contractor shall have a specific access route to the project site. This route is shown in the construction drawings. The Contractor shall use this route to bring all equipment and materials in. If the Contractor has a better route that will prevent damage to existing roads or provide safer access to the construction site, the Contractor shall supply a drawing showing the recommended route to the Owner and Engineer for approval at the preconstruction conference.

**22. NIGHTTIME WORK.** In phases of work requiring daytime work, the Contractor shall not perform nighttime work unless given approval in writing by the Engineer. The Contractor shall request in writing approval to perform nighttime work. If the Engineer approves said nighttime work, the Contractor shall coordinate closely with the Engineer and the Owner during any and all approved nighttime work. This includes any nighttime hauling of materials to the project site. If the Contractor wishes to perform nighttime work or haul materials at night, the Contractor shall reimburse the Owner for any nighttime inspection costs incurred by the Owner to adequately and properly inspect said nighttime work or hauling of materials.

In phases of work requiring nighttime work, the Contractor shall perform said nighttime work within the time frame allotted by the Owner and shown on the phasing plans. The Contractor shall coordinate with the Owner and Engineer each day before nighttime operations to ensure all special instructions, time limitations, directives, etc. are adhered to each night of nighttime operations. The Contractor shall not enter areas requiring nighttime construction operations until cleared to do so by the Owner. Any violation will result in a \$1,000.00 fine for each individual and each piece of equipment committing the infraction. In case of equipment breakdown during nighttime operations, the Contractor shall have on site, back up equipment, to ensure that the night work is completed on time at the end of each night shift, and the airfield is reopened to traffic per the phasing plans. At a minimum, back up equipment shall include a paver and a roller.

**23. DUST CONTROL.** The Contractor shall maintain strict dust control during the project duration. There are operational areas, aircraft parked on the airport as well as commercial facilities that perform maintenance and repair work to aircraft. Therefore, it is imperative that strict dust control be maintained so that damage or nuisance to the areas and facilities described above or airport operational areas is prevented. This dust control shall also include the dust that may occur during any construction procedure.

**24. TRIP TICKETS, INVOICES, WEIGH BILLS, ETC.** The Contractor shall be responsible for supplying any and all trip tickets, invoices, weigh bills, etc. which show the quantities actually used in the construction of the project. All said trip tickets, invoices, weigh bills, etc. shall relate directly to specific bid items. If the Contractor fails to submit said trip tickets, invoices, weigh bills, etc. to the Engineer or his authorized representative prior to or during the time of installation of materials into the project, any material overruns claimed by the Contractor at the end of the project shall not be accepted.

**25. FINAL IN-PLACE EXCAVATION & EMBANKMENT SECTIONS.** At the completion of the project, the Contractor shall submit final in-place earthwork cross sections for the entire project site affected by earthwork operations with the detailed calculations as to as-built excavation and/or embankment. The Contractor may use the cross sections provided in the plans and plot the as-built conditions on those cross section sheets along with the accompanying calculations. The Contractor shall be paid based upon the volume between the original ground line and the as-built ground line. The Contractor shall be paid based on the type of operations for which a bid price was provided.

### **END OF SPECIAL PROVISIONS - SECTION 3**

Page Intentionally Blank

## **SPECIAL PROVISIONS**

### **CHARLOTTESVILLE-ALBEMARLE AIRPORT AUTHORITY CHARLOTTESVILLE ALBEMARLE AIRPORT**

#### **SECTION 4**

#### **LISTING OF DUTIES, RESPONSIBILITIES AND LIMITATIONS OF AUTHORITY OF THE RESIDENT PROJECT REPRESENTATIVE**

The Owner and/or Engineer shall furnish a Resident Project Representative (RPR), assistants and other field staff to assist the Engineer in observing performance of the Work of the Contractor.

Through more extensive on-site observations of the Work in progress and field checks of materials and equipment by the RPR and assistants, the Engineer shall endeavor to provide further protection for the Owner against defects and deficiencies in the Work; but, the furnishing of such services will not make the Engineer responsible for or give the Engineer control over construction means, methods, techniques, sequences or procedures or for safety precautions or programs, or responsibility for the Contractor's failure to perform the Work in accordance with the Contract Documents.

The duties and responsibilities of the RPR are limited to those of the Engineer in the Engineer's agreement with the Owner and in the construction Contract Documents, and are further limited and described as follows:

A. General

The RPR is the Engineer's agent at the site, will act as directed by and under the supervision of the Engineer, and will confer with the Engineer regarding the RPR's actions. The RPR's dealings in matters pertaining to the on-site Work shall in general be with the Engineer and the Contractor keeping the Owner advised as necessary. The RPR's dealings with Subcontractors shall only be through or with the full knowledge and approval of the Contractor. The RPR shall generally communicate with the Owner with the knowledge of and under the direction of the Engineer.

B. Duties and Responsibilities of the RPR

1. Schedules: Review the progress schedule, schedule of Shop Drawing submittals and schedule of values prepared by the Contractor and consult with the Engineer concerning acceptability.
2. Conferences and Meetings: Attend meetings with the Contractor, such as preconstruction conferences, progress meetings, job conferences and other project-related meetings, and prepare and circulate copies of minutes thereof.
3. Liaison:
  - a. Serve as the Engineer's liaison with the Contractor, working principally through the Contractor's superintendent and assist in understanding the intent of the Contract Documents; and assist the Engineer in serving as the Owner's liaison with the Contractor when the Contractor's operations affect the Owner's on-site operations.
  - b. Assist in obtaining from the Owner additional details or information, when required for proper execution of the Work.
4. Shop Drawings and Samples:

- a. Record date of receipt of Shop Drawings and samples.
  - b. Receive samples which are furnished at the site by the Contractor, and notify the Engineer of availability of samples for examination.
  - c. Advise the Engineer and the Contractor of the commencement of any Work requiring a Shop Drawing or sample if the submittal has not been approved by the Engineer.
5. Review of Work, Rejection of Defective Work, Inspections and Tests:
  - a. Conduct on-site observations of the Work in progress to assist the Engineer in determining if the Work is in general proceeding in accordance with the Contract Documents.
  - b. Report to the Engineer whenever the RPR believes that any Work is unsatisfactory, faulty or defective or does not conform to the Contract Documents, or has been damaged, or does not meet the requirements of any inspection, test or approval required to be made; and advise the Engineer of Work that the RPR believes should be corrected or rejected or should be uncovered for observation, or requires special testing, inspection or approval.
  - c. Verify that tests, equipment and systems startups and operating and maintenance training are conducted in the presence of appropriate personnel, and that the Contractor maintains adequate records thereof; and observe, record and report to the Engineer appropriate details relative to the test procedures and startups.
  - d. Accompany visiting inspectors representing public or other agencies having jurisdiction over the Project, record the results of those inspections and report to the Engineer.
6. Interpretation of Contract Documents: Report to the Engineer when clarifications and interpretations of the Contract Documents are needed and transmit to the Contractor clarifications and interpretations as issued by the Engineer.
7. Modifications: Consider and evaluate the Contractor's suggestions for modifications in Drawings or Specifications and report with the RPR's recommendations to the Engineer. Transmit to the Contractor decisions as issued by the Engineer.
8. Records:
  - a. Maintain at the job site orderly files for correspondence, reports of job conferences, Shop Drawings and samples, reproductions of original Contract Documents including all Work Directive Changes, Addenda, Change Orders, Field Orders, additional Drawings issued subsequent to the execution of the Contract, the Engineer's clarifications and interpretations of the Contract Documents, progress reports, and other Project related documents.
  - b. Keep a diary or log book, recording the Contractor hours on the job site, weather conditions, data relative to questions of Work Directive Changes, Change Orders or changed conditions, list of job site visitors, daily activities, decisions, observations in general, and specific observations in more detail as in the case of observing test procedures; and send copies to the Engineer.
  - c. Record names, addresses and telephone numbers of all the Contractors, Subcontractors and major suppliers of materials and equipment.

9. Reports:
    - a. Furnish the Engineer periodic reports as required of progress of the Work and of the Contractor's compliance with the progress schedule and schedule of Shop Drawing and sample submittals.
    - b. Consult with the Engineer in advance of scheduled major tests, inspections or start of important phases of the Work.
    - c. Draft proposed Change Orders and Work Directive Changes, obtaining backup material from the Contractor and recommend to the Engineer Change Orders, Work Directive Changes, and Field Orders.
    - d. Report immediately to the Engineer and the Owner upon the occurrence of any accident.
  10. Payment Requests: Review applications for payment with the Contractor for compliance with the established procedure for their submission and forward with recommendations to the Engineer, noting particularly the relationship of the payment requested to the schedule of values, Work completed and materials and equipment delivered at the site but not incorporated in the Work.
  11. Certificates, Maintenance and Operation Manuals: During the course of the Work, verify that certificates, maintenance and operation manuals and other data required to be assembled and furnished by the Contractor are applicable to the items actually installed and in accordance with the Contract Documents, and have this material delivered to the Engineer for review and forwarding to the Owner prior to final payment for the Work.
  12. Completion:
    - a. Before the Engineer issues a Certificate of Substantial Completion, submit to the Contractor a list of observed items requiring completion or correction.
    - b. Conduct final inspection in the company of the Engineer, the Owner and the Contractor and prepare a final list of items to be completed or corrected.
    - c. Observe that all items on final list have been completed or corrected and make recommendations to the Engineer concerning acceptance.
- C. Limitations of Authority of the Resident Project Representative:
1. Shall not authorize any deviation from the Contract Documents or substitution of materials or equipment, unless authorized by the Engineer.
  2. Shall not exceed limitations of the Engineer's authority as set forth in the Contract Documents.
  3. Shall not undertake any of the responsibilities of the Contractor, Subcontractors or the Contractor's superintendent.
  4. Shall not advise on, issue directions relative to or assume control over any aspect of the means, methods, techniques, sequences or procedures of construction unless such advice or directions are specifically required by the Contract Documents.
  5. Shall not advise on, issue directions regarding or assume control over safety precautions and programs in connection with the Work.



6. Shall not accept Shop Drawing or sample submittals from anyone other than Contractor.
7. Shall not authorize the Owner to occupy the Project in whole or in part.
8. Shall not participate in specialized field or laboratory tests or inspections conducted by others except as specifically authorized by the Engineer.

**END OF SPECIAL PROVISIONS - SECTION 4**

## **SPECIAL PROVISIONS**

### **CHARLOTTESVILLE-ALBEMARLE AIRPORT AUTHORITY CHARLOTTESVILLE ALBEMARLE AIRPORT**

#### **SECTION 5**

##### **CONSTRUCTION SAFETY AND PHASING PLAN (CSPP)**

Attached herein is the Airport's Construction Safety and Phasing Plan (CSPP) that has been developed specifically for this project. The Contractor shall use the CSPP to aid in the development of the required Safety Plan Compliance Document (SPCD), as detailed in Specification C-103, Safety and Security.



May 20, 2025

## Construction Safety and Phasing Plan (CSPP) Terminal Apron Rehabilitation





## Construction Safety and Phasing Plan (CSPP)

### Terminal Apron Rehabilitation

DRAFT

May 20, 2025

Albemarle County, Virginia

Financial Project No.: 00000

Work Order No.: 6-2024

RS&H No.: 1054-1892-017

Prepared by RS&H, Inc. at the  
direction of Charlottesville Albemarle  
Airport Authority



# Table of Contents

1	Project Background.....	1
1.1	Overview.....	1
1.2	Project Scope.....	2
2	CSPP Requirements.....	3
2.1	Coordination.....	3
2.2	Pre-Bid Meeting.....	3
2.2.1	Pre-Construction Conference.....	3
2.2.2	Contractor Progress Meetings .....	4
2.2.3	Scope or Schedule Changes .....	4
2.2.4	FAA ATO Coordination.....	4
2.3	Phasing.....	4
2.4	Area and Operations Affected by Construction .....	6
2.4.1	Identification of Affected Areas.....	7
2.4.2	Mitigation of Effects.....	8
2.5	Protection of Navigation Aids (NAVAIDs) .....	9
2.6	Contractor Access .....	9
2.6.1	Location of Stockpiled Construction Materials.....	9
2.6.2	Vehicle and Pedestrian Operations .....	9
2.7	Wildlife Management.....	12
2.7.1	Trash.....	12
2.7.2	Standing Water .....	12
2.7.3	Tall Grass and Seeds .....	12
2.7.4	Poorly Maintained Fencing and Gates .....	12
2.7.5	Disruption of Existing Wildlife Habitat.....	12
2.8	Foreign Object Debris (FOD) Management .....	12
2.9	Hazardous Materials (HAZMAT) Management.....	13
2.10	Notification of Construction Activities .....	14
2.10.1	List of Responsible Representatives.....	14
2.10.2	Notices to Air Missions (NOTAMs).....	14
2.10.3	Emergency Notification Procedures .....	14
2.10.4	Coordination with ARFF .....	14
2.10.5	Notification to the FAA.....	14
2.11	Inspection Requirements .....	15

2.11.1	Daily Inspections .....	15
2.11.2	Interim Inspections.....	15
2.11.3	Final Inspection.....	15
2.12	Underground Utilities.....	15
2.13	Penalties.....	16
2.14	Special Conditions .....	16
2.15	Runway and Taxiway Visual Aids.....	16
2.15.1	General.....	16
2.15.2	Markings.....	17
2.15.3	Lighting and Visual NAVAIDs.....	17
2.16	Markings and Signs for Access Routes.....	17
2.17	Hazard Marking and Lighting.....	17
2.18	Work Zone Lighting for Nighttime Construction.....	17
2.19	Protection of Areas, Zones, and Surfaces .....	18
2.20	Other Limits of Construction .....	19

## List of Appendices

Appendix A – Construction Safety and Phasing Drawings

Appendix B – Construction Project Daily Safety Inspection Checklist

## List of Figures

Figure 1-1: Terminal Apron Rehabilitation – Project Area.....	2
---	---

# 1 Project Background

## 1.1 Overview

Aviation safety is the primary consideration at airports, especially during construction. The airport operator's Construction Safety and Phasing Plan (CSPP) and the Contractor's Safety Plan Compliance Document (SPCD) are the primary tools to ensure safety compliance when coordinating construction activities with airport operations. These documents identify all aspects of the construction project that pose a potential safety hazard to airport operations and outline respective mitigation procedures for each hazard.

The CSPP sets forth benchmarks and requirements for the project to help ensure the highest levels of safety, security, and efficiency at the airport during construction. Guideline requirements for the CSPP are developed from FAA Advisory Circular (AC) 150/5370-2G, Operational Safety on Airports During Construction. See website: [https://www.faa.gov/airports/resources/advisory\\_circulars/index.cfm/go/document.current/documentnumber/150\\_5370-2](https://www.faa.gov/airports/resources/advisory_circulars/index.cfm/go/document.current/documentnumber/150_5370-2)

The CSPP is a standalone document written to correspond with the safety and security requirements set forth in AC 150/5370-2G, current edition, latest change, the airport safety and security requirements, as well as local codes and requirements. The CSPP is to be used by all personnel involved in the project. The CSPP covers the actions of not only the construction personnel and equipment, but also the actions of inspection personnel and airport staff.

This document has been developed to minimize interruptions to airport operations, reduce construction costs, and maximize the performance and safety of construction activity on active airfield surfaces. Strict adherence to the provisions of the CSPP by all personnel assigned to or visiting the construction site is mandatory for AIP funded construction projects.

The Contractor will be required to submit a Safety Plan Compliance Document (SPCD) to the Airport describing how the Contractor will comply with the requirements set forth in this CSPP.

The SPCD will be drafted as required in AC 150/5370-2G. The SPCD must be submitted to the Airport at least one (1) week prior to the date of the pre-construction conference. The SPCD must also include a certification statement by the Contractor stating that it understands the operational safety requirements detailed in this CSPP and SPCD. The Contractor's certification statement will also assert that there will be no deviation from the approved construction practices contained within either of these documents.

In the event the Contractor's activities are found in non-compliance with the provisions of the CSPP or the SPCD, the Airport Engineer will direct the Contractor, in writing, to immediately cease those operations in violation. In addition, a safety meeting will be conducted for the purpose of reviewing those provisions in the CSPP/SPCD which were violated. The Contractor will not be allowed to resume any construction operations until the conclusion of the safety meeting and all corrective actions required by the Contractor have been implemented.

## 1.2 Project Scope

The Charlottesville Albemarle Airport (CHO), Charlottesville Albemarle Airport Authority (Authority) contracted RS&H to design a repair solution for the distressed terminal apron pavement. See Figure 1-1 for the project area.

Figure 1-1:  
Terminal Apron Rehabilitation – Project Area



The Terminal Apron Rehabilitation project entails corrective maintenance on critical areas of the apron pavement. The corrective maintenance of the apron pavement includes, but is not limited to, apron reconstruction, seven (7) isolated PCC slab replacements, installation of 15-foot-wide concrete transition slab underneath asphalt pavement adjacent to the terminal concrete apron, and relocating drainage infrastructure.

Necessary construction locations, activities, and associated costs have been identified and their impacts to airport operations have been assessed. The impact of work on Air Operations Areas (AOA) is discussed in detail below in Section 2 CSPP Requirements of this document and is depicted in the attached Phasing Exhibits G-120 through G-153 found in Appendix A. These



exhibits will be made part of the drawing set issued to the Contractor for bidding and construction.

## 2 CSPP Requirements

### 2.1 Coordination

Pre-bid and pre-construction conferences will be held to review the project scope, to discuss the operational safety requirements during construction, and to discuss the procurement process. Prior to and during construction, construction progress meetings will also be held. Scope and/or schedule changes, and FAA Air Traffic Organization (ATO) coordination, will be addressed as needed.

### 2.2 Pre-Bid Meeting

A pre-bid conference will be hosted by CHO and RS&H. One of the primary purposes of the pre-bid conference will be to clarify and explain proposed construction methods, procedures, and the operational safety measures that will be required during construction. Additional discussion items will include quality control (QC), quality assurance (QA), and the procurement process (including items such as Disadvantaged Business Enterprise goals/requirements, bonding, subcontracting, and labor). The pre-bid conference will be open to all prospective bidders. The CSPP will be reviewed and discussed with the following key attendees:

- Charlottesville Albemarle Airport Authority (Owner)
- RS&H (Designer)
- Bidding Contractors (Contractor)
- Construction Manager (Owner's Representative/RPR)

#### 2.2.1 Pre-Construction Conference

A pre-construction conference will be hosted by the Authority. The purpose of the meeting will be to thoroughly discuss critical project items such as contract requirements, operational safety measures that will be required during construction, airport security requirements, construction phasing, QC, and QA.

Representatives from the following entities will be invited to the pre-construction meeting:

- CHO
- The Authority
- Construction Manager/RPR
- CHO Operations, Access Control, and Security
- RS&H (Designer)
- QA/QC Testing Laboratory representative(s)
- Contractors and Subcontractor representative(s)

- Airline and Industry Representatives.
- Affected Utility Owners.
- Affected Tenants.
- Federal, State, and local agencies affected by the proposed construction
- FAA Washington Airport District Office (ADO)
- FAA Air Traffic Control Tower (ATCT)
- CHO Airport Rescue and Fire Fighting (ARFF)
- Contractor Safety and Security Supervisor

### 2.2.2 Contractor Progress Meetings

Weekly construction progress meetings will be held during construction to discuss work progress, schedule, budget, and to address any current and/or potential safety and security concerns. The frequency of the meetings may be adjusted as necessary. Operational safety and security will be an agenda item for all construction progress meetings.

### 2.2.3 Scope or Schedule Changes

Changes in the scope and/or duration of the project may necessitate revisions to the CSPP. Changes to this document require review and approval by the Airport and FAA prior to implementation. The FAA Washington ADO, Airport, and the Engineer will be promptly notified of any proposed changes to this CSPP. In addition, it may be necessary to coordinate proposed changes with any and all appropriate local, state, and/or federal government agencies (i.e. EPA, OSHA, TSA, etc.).

### 2.2.4 FAA ATO Coordination

Early coordination with FAA ATO is required to schedule airway facility shutdowns and restarts. It will remain the Contractor's responsibility to be aware and cognizant of all activities on the airfield and to follow those procedures referenced above for work required in, around, or near any airfield Navigational Aids (NAVAIDs).

## 2.3 Phasing

The construction phasing for this project will be coordinated by CHO Operations, the RPR, and the Airlines. The sequenced construction phases established in this CSPP have been incorporated into the project design and are reflected in the contract drawings and specifications. This project has been divided into 8 phases. A summary of work for each phase is included below. Refer to *Appendix A* for the Phasing Plans and limits of construction for each.

Both day and night work will be allowed for all phases. The slabs within 20' of the wingtip of the taxiing aircraft will be restricted to only being constructed during hours when airline and airport operations are shut down for the night (typically 12:00 AM to 4:00 AM). Slabs outside of the 20'

safety clearance can be constructed at any time of the day. Lighted barricades to close and protect the work area will be required. Steel road plates and prefabricated crane mats will be required to cover any open excavations (typical for all phases).

New slabs with apron/parking markings will receive permanent pavement markings. VSR and non-movement area boundary markings will receive an initial (half) application of pavement markings at their respective proposed location. Final cleaning of the work is required for each phase.

### **PHASE 1 – PARKING POSITION 1 AND 1B CLOSURE**

Phase 1 consists of PCC reconstruction, asphalt reconstruction within the aircraft parking area of Position 1 and the RON/Maintenance parking position, Position 1B. Within this same area, removal and relocation of the existing drainage infrastructure. Four existing concrete panels will have isolated slab replacement, outside of the PCC and asphalt reconstructed areas. Phase 1 will be constructed within a 31-day period. Only Positions 1 and 1B will be closed during this phase. There will be no other closures of the apron during this phase.

Prior to the start of Phase 1, a lead-in line for Position 2 will be marked and a temporary gate will be marked in the adjacent asphalt pavement. The lead-in line for Position 2, and the temporary gate marking will be removed at the end of Phase 1.

### **PHASE 2A – PARKING POSITION 2 CLOSURE**

Phase 2A consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 2. Phase 2 will be constructed within a 13-day period. Only Parking Position 2 will be closed during this phase. There will be no other closures of the apron during this phase.

### **PHASE 2B – PARKING POSITION 2 CLOSURE**

Phase 2B consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 2. Phase 2 will be constructed within an 11-day period. Only Parking Position 2 will be closed during this phase. There will be no other closures of the apron during this phase.

### **PHASE 3 – PARKING POSITION 3 CLOSURE**

Phase 3 consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 3. Within this same area, removal and relocation of the existing drainage infrastructure. Phase 3 will be constructed within a 31-day period. Only Parking Position 3 will be closed during this phase. There will be no other closures of the apron during this phase.

#### **PHASE 4 – PARKING POSITION 4 CLOSURE**

Phase 4 consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 4. Within this same area, removal and relocation of the existing drainage infrastructure. Phase 4 will be constructed within a 31-day period. Only Parking Position 4 will be closed during this phase. There will be no other closures of the apron during this phase.

#### **PHASE 5 – PARKING POSITION 5A CLOSURE**

Phase 5 consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 5A. Phase 5 will be constructed within a 20-day period. Only Parking Position 5A will be closed during this phase. There will be no other closures of the apron during this phase.

#### **PHASE 6 – PARKING POSITION 5B CLOSURE**

Phase 6 consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Position 5B. Within this same area, removal and relocation of the existing drainage infrastructure. Phase 6 will be constructed within a 12-day period. Only Parking Position 5B will be closed during this phase. There will be no other closures of the apron during this phase.

#### **PHASE 7 – PARKING POSITION 5C AND 5D CLOSURE**

Phase 7 consists of PCC and asphalt pavement reconstruction identified within the aircraft parking area of Positions 5C and 5D. Three existing concrete panels will have isolated slab replacement, outside of the PCC and asphalt reconstructed areas. Phase 7 will be constructed within a 28-day period. Only Parking Positions 5C and 5D will be closed during this phase. There will be no other closures of the apron during this phase.

Prior to the start of Phase 7, gate markings for Position 5E will be placed at its proposed location shown in the plans. Gate markings for Position 5E will receive full application and remain permanent throughout construction.

#### **PHASE 8 – PERMANENT PAVEMENT MARKING**

Phase 8 consists of final pavement marking application for the VSR and the non-movement area boundary marking for the apron.

## **2.4 Area and Operations Affected by Construction**

Runways, taxiways, and other airfield surfaces will remain in use by aircraft to the maximum extent possible without compromising safety. The performance of this contract will require the

partial closures and/or restrictions of airfield surfaces on a scheduled and phased basis. These areas are illustrated in the exhibits of Attachment A of this document.

## 2.4.1 Identification of Affected Areas

Reference Appendix A of this document for graphical identification of areas affected by construction operations, of particular importance are the following.

### *2.4.1.1 Closing, or partial closing, of runways, taxiways, and aprons*

Closing, or partial closing, of aprons due to phasing are identified in Section 2.3 Phasing of this document and are illustrated in the exhibits provided in Appendix A. The term 'partial closure' means a portion of the pavement is unavailable for any aircraft operation. Elements of the project work areas have been found to penetrate the Taxiway Object Free Areas (TOFA) of the surrounding airfield surfaces necessitating actions to maintain safety and separation during construction. These areas have been identified in the exhibits provided in Appendix A of this document.

### *2.4.1.2 Closing of Aircraft Rescue and Fire Fighting (ARFF) Access Routes*

Access into, through, and/or around the project work area by ARFF vehicles may be reduced during construction. It will be the Contractor's responsibility to maintain access for these emergency response vehicles for the duration of each phase of work. The Contractor will be advised that airport personnel and fire rescue vehicles always have the right-of-way during construction.

### *2.4.1.3 Closing of Access Routes Used by Airport Support Vehicles*

It is the Contractor's responsibility to maintain access for ground service equipment (GSE) vehicles servicing aircraft around the terminal for the duration of each phase of work. Barrier locations for diverting GSE and airport support vehicles are shown in Appendix A of this document. The Contractor will be instructed to work with the Engineer and RPR to ensure Airport Operations always has access to all areas of the airfield during construction.

### *2.4.1.4 Interruption of Utilities*

Several utilities have been identified within the project limits. These include but may not be limited to electrical service lines, airfield electrical lines, and storm drain lines. Storm drain lines, within the proposed pavement limits, will be interrupted for the relocation of the storm drain lines.

### *2.4.1.5 Approach/Departure Surfaces Affected by Heights of Objects*

Contractor equipment conflicts and staging area heights of objects are not anticipated to impact approach/departure surfaces. The contractor may be asked to fill out FAA Form 7460-1 Notice of Proposed Construction or Alteration for this project.

#### *2.4.1.6 Construction Areas*

These areas include the project work areas, staging areas, and Contractor haul routes near or through active airfield surfaces. Contractor haul routes will cross active airfield surfaces. All crossings will be controlled and monitored by dedicated traffic control flagmen familiar with airfield traffic control procedures on active airfield surfaces. These specific project areas are identified in the exhibits of Appendix A of this document.

### *2.4.2 Mitigation of Effects*

This CSPP has established specific requirements and operational procedures necessary to maintain the safety and efficiency of airport operations during the construction of this project. All coordination pertaining to airport operations during construction will go through the RPR and CHO. Any NOTAMs will be requested through the RPR.

#### *2.4.2.1 Temporary Changes to Runway and/or Taxiway Operations*

There are no anticipated temporary changes to runway nor taxiway operations in the affected airfield surfaces identified in Section 2.3. Required NOTAMs will be issued on the various temporary changes to aircraft access through the affected areas.

#### *2.4.2.2 Detours for ARFF and Other Aircraft Vehicles*

The project work site shall remain open to all ARFF vehicles in emergency situations. The Contractor is required to maintain access in and around the project work area for all ARFF vehicles. Proper routing of this traffic will be effectively communicated to all supervisory personnel involved in the construction project. Vehicle routing shall be maintained for GSE vehicles accessing aircraft parked at active terminal gates.

#### *2.4.2.3 Maintenance of Essential Utilities*

Special attention shall be given to preventing unscheduled interruption of utility services and facilities. Where required due to construction purposes, the FAA shall locate all their underground utilities. The Contractor shall locate and/or arrange for the location of all the underground utilities. When an underground cable or utility is damaged due to the Contractor's negligence, the Contractor shall immediately repair the affected cable or utility. Full coordination between airport staff, field inspectors, and construction personnel will be exercised to ensure that all airport power and control cables are fully protected prior to any excavation. Locations of cable and other underground utilities will be marked prior to beginning excavation.

#### *2.4.2.4 Temporary Changes to Air Traffic Control Procedures*

Changes to air traffic control procedures must be coordinated with the Airport ATO.

## 2.5 Protection of Navigation Aids (NAVAIDs)

There are no NAVAID's located within the project area or along/nearby the haul routes for the project. NAVAID protection is not anticipated for this project.

## 2.6 Contractor Access

This CSPP details those areas to which the Contractor must have access, and how Contractor personnel will access those project work areas.

### 2.6.1 Location of Stockpiled Construction Materials

Stockpiled materials and equipment storage are not permitted within the Runway Safety Area/Taxiway Safety Area (RSA/TSA), Obstacle Free Zone (OFZ) or Object Free Area (OFA) of an operational runway or taxiway. Stockpiled material shall be constrained in a manner to prevent movement resulting from either aircraft jet blast or wind conditions in excess of ten miles per hour. In addition, stockpiled material shall have silt fence located around the material to prevent FOD from moving onto the airfield pavements or polluting watercourses.

Open trenches, excavations, or stockpiled material are not permitted within the limits of safety areas of operational runways or taxiways. Stockpiled material shall not be permitted within the protected areas of the runways or allowed to penetrate any of the protected airspace.

In addition, all demolished unsuitable materials shall be removed and legally disposed of off airport property and not stockpiled on airport property.

### 2.6.2 Vehicle and Pedestrian Operations

#### 2.6.2.1 Construction Site Parking

Contractor employee personal vehicles may not be parked or driven in the AOA.

#### 2.6.2.2 Construction Equipment Parking

Contractor employees will park and service all construction vehicles in the areas designated on the Safety Plans outside of all safety or object free areas, and the Runway primary surface. If it is necessary to leave specialized equipment on a closed apron at night, the equipment must be well lighted. Employees shall also park construction vehicles in the designated staging area and outside of all object free areas when not in use by construction personnel (for example, overnight, on weekends, or during other periods when construction is not active).

#### 2.6.2.3 Access and Haul Routes

Contractor access to the project site will either be through Gate 7 or 18 via Route 606 or Dickerson Road. Any changes to haul routes, other than those shown on the Phasing Plans, must be approved by the RPR.

The Contractor shall provide enclosures, fences, barricades, or other devices where necessary to prevent access to the site or danger to the public, as approved by the RPR. The Contractor will not be permitted to use any access or haul roads other than those designated on the Contract Drawings and will be required to submit a detailed Staging Area and Haul Route Plan prior to the start of construction.

Contractor access and hauling operations are strictly limited to the haul routes shown. Contractor is responsible for any improvements and maintenance to haul routes as needed to efficiently perform construction activities.

#### *2.6.2.4 Contractor Vehicle Marking and Lighting*

Only Contractor licensed vehicles will be permitted to enter the AOA. Each Contractor licensed vehicle must display a company logo on both sides of the vehicle, as well as a yellow/amber rotating beacon affixed to the uppermost part of the vehicle that is visible from any direction, day and night. Contractor vehicle marking and lighting is the sole responsibility of the Contractor; the Airport will not provide marking or lights. Additional vehicle marking and signage guidelines can be found in *FAA AC 150/5210-5D Painting, Marking, and Lighting of Vehicles Used on an Airport*.

#### *2.6.2.5 Proper Vehicle Operations*

When inside of the AOA, Contractor vehicles will give right-of-way to passing aircraft and may only operate within the designated work area or on haul routes. During loss of communication, vehicles operating in the work area will remain within a proximity that allows safe visual contact of one another. A flagger will be required to cross active taxiways or apron, when necessary.

#### *2.6.2.6 Required Escorts*

Any construction activity taking place within the defined aircraft movement area will require the presence badged contractor personnel having radio communication with the ATCT. At no time shall active taxiways or apron be crossed by construction equipment without notification or approval/clearance by radio trained personnel.

#### *2.6.2.7 Training Requirements for Vehicle Drivers*

The Engineer will brief the Contractor on the airfield elements affected by the construction and the procedures for safely operating in aircraft movement areas. The Contractor will also be instructed on how to interpret the various signage and markings that may be encountered in the work area or on haul routes.



### *2.6.2.8 Situational Awareness*

The Contractor shall stress to his/her personnel to exercise vigilance when operating vehicles or equipment in and around aircraft movement areas, giving right-of-way to and always operating with caution around aircraft.

### *2.6.2.9 Two-Way Radio Communication Procedure*

Prior to the start of work, the Engineer will brief the Contractor on appropriate radio procedures, to include the phraseology and frequencies used at the Airport. Any contractor vehicle crossing aircraft movement areas must have the ability to make two-way radio communication with the ATCT.

#### **2.6.2.9.1 General**

The Contractor must ensure all construction personnel engaged in activities involving unescorted operation on aircraft movement areas observe the proper procedures for communications, including using appropriate radio frequencies. When operating vehicles on or near open taxiways, construction personnel must understand the critical importance of maintaining radio contact, as directed by the airport operator, with:

- Airport operations
- ATCT
- Common Traffic Advisory Frequency (CTAF), which may include UNICOM, MULTICOM.
- Automatic Terminal Information Service (ATIS). This frequency is useful for monitoring conditions on the airport. Local air traffic will broadcast information regarding construction related runway closures and "shortened" runways on the ATIS frequency.

#### **2.6.2.9.2 Areas Requiring Two-Way Radio Communications with ATCT**

Vehicle traffic crossing active movement areas must be controlled either by two-way radio with the ATCT, escort, flagman, signal light, or other means appropriate for CHO.

### *2.6.2.10 Maintenance of the Secured Area of the Airport*

#### **2.6.2.10.1 Fencing and Gates**

There are airport fencing and vehicle gates on the east side of the airfield. The Contractor shall secure any gate used for site access.

#### **2.6.2.10.2 Badging Requirements**

All training of Contractor personnel will be completed by CHO Operations/Badging Office.

## 2.7 Wildlife Management

Contractors must carefully control and continuously remove waste or loose materials that might attract wildlife. Contractor personnel must be aware of and avoid construction activities that can create wildlife hazards on airports.

### 2.7.1 Trash

Food scraps from construction personnel activity must be collected and removed daily. The feeding of animals is strictly prohibited.

### 2.7.2 Standing Water

Water shall not be allowed to collect and pool for more than any single 24-hour period.

### 2.7.3 Tall Grass and Seeds

Not applicable to this project.

### 2.7.4 Poorly Maintained Fencing and Gates

The Contractor shall immediately notify the Engineer and Airport Operations if project related activities compromise any portions of the airport perimeter fencing.

### 2.7.5 Disruption of Existing Wildlife Habitat

The proposed work will not impact any designated wildlife habitat areas. The Engineer will instruct the contractor to immediately notify the Engineer if any contractor personnel see any wildlife within the work area.

## 2.8 Foreign Object Debris (FOD) Management

Foreign object debris at airports includes any object found in an inappropriate location that can damage aircraft, equipment, or airport personnel. Foreign object debris on construction sites is typically comprised of things such as loose gravel, blowing sand, wire bristles from sweeper heads, food wrappers, and material packaging. The presence of FOD within the AOA poses a significant threat to the safety of air travel. FOD has the potential to damage aircraft during critical phases of flight, which can lead to catastrophic loss of life and airframe, and at the very least increased maintenance and operating costs. As such, these hazardous materials shall not be allowed near active aircraft movement areas, and they shall be continuously removed by the Contractor during the construction project. The construction area shall be kept clean at all times of debris that may blow onto the airfield.

### **Methods of FOD Control**

- Sweeper Equipment: The Contractor will be required to have a self-propelled street type vacuum sweeper truck on site at all times. Sweepers will operate full time to keep haul routes and work areas clean at all times.
- Dust Control Equipment: The Contractor will be required to have a water truck on site at all times for dust control.
- Training: Contractor shall provide training to all employees working within the AOA on effective FOD management. Training shall include description and consequences of FOD, FOD awareness, and housekeeping procedures.
- Housekeeping: Preventing FOD from occurring is the most effective form of FOD management. Contractor must monitor construction activities and proactively develop a plan to prevent FOD from occurring. Typical FOD prevention measures include the use of covered trash containers, covered loads, zero tolerance of littering, and tying down items which may be easily windblown.
- Ground Vehicle Tire Inspections: Prior to crossing active airfield pavement the Contractor must perform a vehicle tire check for any loose rocks that may be in the tread. Tires covered in mud must be cleaned prior to crossing active pavement to prevent tracking dirt.
- Pavement Sweeps: Prior to opening sections of pavement within a work area to aircraft traffic, the Contractor will be required to sweep the entire pavement surface (including shoulders). Metal bristled brooms are known to create FOD, and the Contractor will be required to clean all bristles from the pavement. Compressed air and vacuums can be used to clean pavement surfaces as well.
- FOD Inspections: Refer to Section 2.11 of this document for FOD inspection requirements.

## **2.9 Hazardous Materials (HAZMAT) Management**

Contractors operating construction vehicles and equipment on the airport must be prepared to expeditiously contain and clean-up spills resulting from fuel, hydraulic fluid, or other chemical fluid leaks. Transport and handling of other hazardous materials on an airport also requires special procedures. To that end, the Contractor is required to develop and implement spill prevention and response procedures for vehicle operations.

HAZMAT Procedures to be developed by the Contractor prior to the issuance of the notice to proceed including but not limited to:

- Fuel Storage Locations and Handling Procedures
- Spill Response Procedures
- Safety Data Sheets (SDS)

The Contractor shall not introduce explosives or any other hazardous materials or equipment without the prior written consent of the RPR.

## 2.10 Notification of Construction Activities

The following is information and procedures for immediate notification of airport users and the FAA of any conditions adversely affecting the operational safety of the airport.

### 2.10.1 List of Responsible Representatives

A list of responsible representatives and their contact numbers will be maintained in this document and distributed to the Contractor. Any changes in personnel will be updated immediately.

### 2.10.2 Notices to Air Missions (NOTAMs)

For the Contractor to operate within Airport property, appropriate NOTAMs will be issued by Airport Operations (with guidance from the RPR/Engineer). These notices provide information on closed, limited, or hazardous conditions to airmen and users of the Airport. A 7-day notice is required for issuance of a proper NOTAM. All construction operations will be closely coordinated with the Engineer for NOTAM issuance. CHO Operations will generate and issue NOTAMs based on Contractor construction schedule and facility impacts.

### 2.10.3 Emergency Notification Procedures

In the event of an emergency, the Contractor will immediately notify the RPR first. The RPR will contact the appropriate resolution personnel. If the emergency requires immediate medical attention, the contractor will call 911, followed by notifying Airport Operations at (434) 973-8342.

### 2.10.4 Coordination with ARFF

Weekly construction progress meetings will be held throughout the duration of the project and prior to commencement of phasing changes. During these weekly meetings, ARFF will be notified of re-routing, blocking, and restoration of emergency access routes. Contractors are required to adjust haul routes and hauling activities as necessary to accommodate ARFF operations.

### 2.10.5 Notification to the FAA

If the Contractor needs use of cranes, equipment, or other items on or near the airport taller than Part 77 elevations (for permanent features) or OFZ elevations (for temporary features), he/she must submit a new 7460-1 form to the FAA for airspace review and approval.

## 2.11 Inspection Requirements

### 2.11.1 Daily Inspections

Inspections should be conducted at least daily, but more frequently if necessary, to ensure conformance with the CSPP. A sample checklist is provided in Appendix 4 of AC 150/5370-2G. In addition to the contractor's required inspections, the work area is subject to inspection by representatives of Airport Operations, FAA, and other affected agencies to ensure compliance with the CSPP and the SPCD. The Engineer will have full-time inspectors monitoring activity throughout construction.

Pavements must be free of all dirt, sand, gravel, wire bristles, or any other objects that could cause damage to aircraft. Daily inspections must be completed to ensure all traffic control devices are in proper location and working order. The Contractor shall keep the project site and vehicles clean, employing a "clean as you go" approach throughout the project.

Airport staff and CHO Operations personnel conduct daily airfield inspections. These inspections include an inspection of all open/active airfield-paved areas and safety areas to ensure compliance with FAR Part 139.327.

### 2.11.2 Interim Inspections

Inspections should be conducted of all areas to be (re)opened to aircraft traffic to ensure the proper operation of lights and signs, for correct markings, and absence of FOD. The Contractor should conduct an inspection of the work area with airport operations personnel. The Contractor should ensure that all construction materials have been secured, all pavement surfaces have been swept clean, all transition ramps have been properly constructed, and that surfaces have been appropriately marked for aircraft to operate safely. Only if all items on the list meet with the airport operator's approval should the air traffic control tower be notified to open the area to aircraft operations. The Contractor should be required to retain a suitable workforce and the necessary equipment at the work area for any last-minute cleanup that may be requested by the airport operator prior to opening the area.

### 2.11.3 Final Inspection

A final inspection with the Contractor, Engineer, Airport, and FAA will take place prior to final acceptance of the project. Punch list inspection(s) will precede the final inspection.

## 2.12 Underground Utilities

The location of the underground utilities and FAA cables shown on the plans has been obtained from available records, but existing depths are unknown. Locations of existing and proposed underground utilities and facilities shown on the Contract Drawings have been developed from

the latest available information. Completeness and accuracy of the location and depth of utilities and facilities cannot be guaranteed.

The Contractor shall bear full responsibility for the protection of utilities. Prior to beginning any excavating operations, the Contractor is to use hand excavation, as required, to verify the depth and location of all utilities and facilities and clear them. Any underground utilities located which do not appear on the plans shall be brought to the attention of the RPR and reflected on the Contractor's Markup plans.

Contractor is responsible to contact Virginia 811 or confirm on-airport utilities (except FAA utilities which are to be located by the FAA). If using Virginia 811, the Contractor is responsible to contact Virginia 811 at least three (3) and not more than ten (10) working days prior to construction and follow the instructions contained in the Virginia 811 procedures. The Contractor is responsible for contacting all applicable utility companies.

If FAA cables are damaged during construction, repairs shall be done from point to point in accordance with FAA requirements and in the presence of an FAA Representative. If the Contractor damages any existing utilities during construction, he/she shall immediately repair the damaged item to the RPR's satisfaction, at the sole expense of the Contractor. Contractors must work 24/7 until repair is complete.

## 2.13 Penalties

Penalties for non-compliance with the plans and procedures outlined in this document vary from verbal and written warnings to suspension of the project until compliance is achieved.

## 2.14 Special Conditions

The Contractor may be required to halt construction activities during periods of low visibility conditions, snow removal, emergency situations, or VIP movements. In all cases the Contractor shall follow instructions from CHO Operations. See Section 2.6 of this document for airport safety and security measures and radio communications procedures. See Section 2.10 of this document for emergency notification procedures.

## 2.15 Runway and Taxiway Visual Aids

### 2.15.1 General

Airport markings, lighting, and signs will be clearly visible to pilots, not misleading, confusing, or deceptive. All will be secured in place to prevent movement by prop wash, jet blast, wing vortices or other wind currents and constructed of materials that would minimize the damage to an aircraft in the event of inadvertent contact.

### 2.15.2 Markings

Markings must be in compliance with the standards of *FAA AC 150/5340-1M Standards for Airport Markings*. Temporary apron gate closures will not be marked, but instead will be delineated with low-profile lighted barricades. Surface painted taxiway closure markers will not be used for this project.

### 2.15.3 Lighting and Visual NAVAIDs

The existing Taxiway Markings, Centerline Lights and Edge Lights will not be modified with this project. No NAVAID impacts are expected with this project scope.

## 2.16 Markings and Signs for Access Routes

The pavement markings and signs for construction personnel will conform to *FAA AC 150/5340-18G Standards for Airport Sign Systems*, and to the extent practicable, with *Federal Highway Administration Manual on Uniform Traffic Control Devices (MUTCD)*. Signs placed adjacent to areas used by aircraft must comply with the frangibility requirements of *FAA AC 150/5220-23A, Frangible Connections*. Access routes for the Contractor are shown in the CSPP drawings.

## 2.17 Hazard Marking and Lighting

Low-profile barricades with flashing red lights will be used for all pavement closures. The Contractor will ensure that the barricades are completely filled with water, and sand-bagged, at all times. Contractor must have a plan for daily inspection of barricades at start of work and completion of work for each shift. Cones may be utilized to establish limits of construction haul routes. Barricades will be placed end to end with no space in between except to allow ARFF access or as directed by the RPR. A Contractor's representative will be on call 24 hours a day for emergency maintenance of airport hazard lighting and barricades.

Hazard marking and lighting of excavation areas are to be in accordance with the Occupational Safety and Health Organization (OSHA) requirements. Open trenches and excavations will be prominently marked with barricades and orange flags and illuminated by flashing red light units during hours of restricted visibility and darkness, as directed by the RPR.

## 2.18 Work Zone Lighting for Nighttime Construction

Lighting equipment must adequately illuminate the work area if the construction is to be performed during nighttime hours. Refer to *FAA AC 150/5370-10H Standard Specifications for Construction of Airports* for minimum illumination levels for nighttime paving projects. Additionally, it is recommended that all support equipment, except haul trucks, be equipped with artificial illumination to safely illuminate the area immediately surrounding their work area. The lights should be positioned to provide the most natural color illuminations and contrast with minimum of shadows. The spacing must be determined by trial. Light towers should be

positioned and adjusted to aim away from ATCT cabs and active runways to prevent blinding effects. Shielding may be necessary. Light towers should be removed from the construction site when the area is reopened to aircraft operations.

## 2.19 Protection of Areas, Zones, and Surfaces

All Safety Areas, Object Free Areas, and Obstacle Free Zones will be protected from construction activity. Open trenches and excavations are not permitted within the TSA while the Taxiway is open. All trenches and excavations within a TSA must be backfilled prior to opening a Taxiway for aircraft use. Any pavement construction related drop-offs will be covered by at least one lift of asphalt prior to opening adjacent pavements to aircraft use. Pavement will be brought up to TSA grading standards as defined by FAA AC 150/5300-13B. No non-frangible obstructions or drop-offs greater than three inches in height will be permitted within active Taxiway object free areas.

If a taxiway/taxilane must be opened before excavations are backfilled, they must be covered appropriately, as approved by the RPR.

For work on and adjacent to active taxiways, runways, and aprons, the following conditions apply:

- Runway Construction Limits: Contractor may perform construction up to this limit which is 250 feet from the active runway centerline.
- Runway Safety Area (RSA): An area within 250 feet of a runway centerline.
- Runway Object Free Area (ROFA): An area within 400 feet of the runway centerline. Any equipment that is not in use (no operator available to move equipment for more than 15 minutes) must be completely removed from the ROFA.
- Taxiway Safety Area (TSA): an area within 59 feet of ADG III taxiway centerlines, 85.5 feet of ADG IV taxiway centerlines, and 107 feet of ADG V taxiway centerlines, unless otherwise noted on the plans.
- Taxilane Object Free Area (TLOFA): an area within 81 feet of ADG III taxilane centerlines, 112.5 feet of ADG IV taxilane centerlines, and 138 feet of ADG V taxilane centerlines, unless otherwise noted on the plans.
- Taxiway Object Free Area (TOFA): an area within 93 feet of ADG III taxiway centerlines, 129.5 feet of ADG IV taxiway centerlines, and 160 feet of ADG V taxiway centerlines, unless otherwise noted on the plans.
- Obstacle Free Zone (OFZ): Construction equipment and stockpiles will not penetrate the OFZ. See OFZ Typical Section on the Construction Phasing Notes and Details for elevations and dimensions of OFZ surfaces.




All construction activity within a TSA or TOFA will require an applicable NOTAM and the closure of that Taxiway, or a designated portion thereof, or a restriction to the aircraft which will be permitted to use that Taxiway during construction. The Contractor will request through the RPR a NOTAM for the closure or restriction of the required portion of the Taxiway. The request will include the times requested and the Contractor's proposed detailed schedule of this operation within the area utilizing only the requested closure times. NOTAMs require 72 hours' notice and are subject to Airport approval.

## 2.20 Other Limits of Construction

Certain work areas and sub-areas may be made available to the Contractor with advanced notice and coordination with the RPR and CHO Operations. The specific sequence of work within each phase will be determined by the Contractor. Additional limitations include but are not limited to:

- The Contractor will coordinate with the RPR, CHO personnel and ATCT for any activities within the airfield at all times.
- The Contractor will be required to halt construction activities when required by emergency crews at the airport.
- The Contractor may be required to halt construction activities in the event of VIP movements on the airport.
- The Contractor may not use tall equipment (cranes, concrete pumps, etc.) above the elevations shown on the Maximum Equipment Height Plan(s) unless a 7460-1 determination letter is issued for such equipment.
- The use of electrical blasting caps is prohibited on or within 1,000 feet of the airport property.
- The use of flare pots is prohibited within the AOA.
- Open flame, welding, or torch-cutting operations are prohibited unless adequate fire and safety precautions have been taken and the procedure is approved by the fire inspector, CHO Operations, and the RPR. No debris burning will be allowed unless authorized by the RPR.

## **Appendix A – Construction Safety and Phasing Drawings**



SAFETY AND PHASING NOTES

- 1. ALL WORK SHOWN ON THIS SHEET SHALL BE INCIDENTAL TO ITEM C-103, SAFETY AND SECURITY ITEMS AND C-105 MOBILIZATION.
- 2. SEE ADDITIONAL CONSTRUCTION SAFETY AND PHASING NOTES AND DETAILS ON SHEETS G-151 TO G-153.
- 3. PHASES OF CONSTRUCTION ARE INTENDED TO BE COMPLETED SEQUENTIALLY, STARTING WITH PHASE 1. THIS SEQUENCE IS SUBJECT TO MODIFICATION BY THE AIRPORT AT ANY TIME DURING CONSTRUCTION.
- 4. AIRCRAFT WINGWALKERS WILL BE REQUIRED TO ESCORT AIRCRAFT FROM EACH GATE PAST THE WORK LIMITS OF THE ACTIVE CONSTRUCTION PHASE. WINGWALKERS WILL ENSURE THE AIRCRAFT MAIN GEAR MAINTAINS A MINIMUM 12' DISTANCE FROM THE LOW-PROFILE BARRICADE. WINGWALKERS WILL BE PROVIDED BY THE AIRLINES, THE CONTRACTOR WILL NOT BE RESPONSIBLE FOR THIS.
- 5. LOCATION OF FLAGMEN AND BARRICADES WILL CHANGE THROUGHOUT CONSTRUCTION AND SHALL BE COORDINATED WITH THE RPR.
- 6. ALL TUGS, GSE, AND AIRCRAFT SHALL KEEP CLEAR OF PANEL REPLACEMENT AND RECONSTRUCTION AREAS. COORDINATION WILL BE REQUIRED BETWEEN AIRPORT, AIRLINES, AND CONSTRUCTION PERSONNEL. PANEL REPLACEMENT AND RECONSTRUCTION AREAS WILL BE SURROUNDED BY LOW PROFILE TEMPORARY BARRICADES AND COVERED WITH PREFABRICATED CRANE MATS AS SHOWN IN THE PHASING DETAILS.
- 7. EXISTING GATE MARKINGS, GATE LEAD-IN LINES, INTERMEDIATE HOLD LINE MARKING, AND SERVICE ROAD MARKINGS SHALL BE SURVEYED PRIOR TO REMOVAL. THE FINAL MARKING PHASE OF FULL APPLICATION SHALL BE BASED ON THE EXISTING SURVEYED LOCATIONS.
- 8. FOR TEMPORARY PAVEMENT MARKINGS SEE C-710. PAVEMENT MARKING DETAILS ARE SHOWN ON SHEETS C-851 TO C-852.
- 9. PERMANENT PAINT MARKINGS WILL BE COMPLETED DURING PHASE 8.


TIME RESTRICTIONS/WORK HOURS

- 1. ANY TIME AND RESTRICTED WORK HOURS ARE SUBJECT TO CHANGE BY AIRLINES, AIRPORT OPERATIONS, CHO PERSONNEL. DURATIONS ARE LIMITED IN THE CONSTRUCTION SCHEDULE. EXTENDED CLOSURE WILL NOT BE ACCEPTABLE TO AIRPORT OPERATIONS.
- 2. RESTRICTED HOURS ARE 12 AM - 4 AM.

CONSTRUCTION SCHEDULE	
PHASE	DURATION (CALENDAR DAYS)
ADMINISTRATIVE PHASE	90 DAYS
PHASE 1	35 DAYS
PHASE 2A	13 DAYS
PHASE 2B	11 DAYS
PHASE 3	31 DAYS
PHASE 4	31 DAYS
PHASE 5	20 DAYS
PHASE 6	12 DAYS
PHASE 7	28 DAYS
PHASE 8	1 DAY

LEGEND

- ANY TIME WORK
- RESTRICTED TIME WORK
- PHASE LIMITS
- TSA
- TOFA
- PROPOSED TAXIWAY SAFETY AREA
- PROPOSED TAXIWAY OBJECT FREE AREA



**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com

**CHO**  
AIRPORT

**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

**REVISIONS**

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE


**OVERALL  
PHASING PLAN**

SHEET NUMBER

**G-120**

**90%  
SUBMITTAL**





**LEGEND**


- ANY TIME WORK
- RESTRICTED TIME WORK
- PHASE LIMITS
- TSA
- TOFA
- PROPOSED TEMPORARY VSR BARRICADES
- TEMPORARY DETOUR SIGN

**PHASE 1 NOTES**

- DURATION = 35 CALENDAR DAYS
- PHASE 1 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, ISOLATED SLAB REPLACEMENTS, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, RELOCATION AND REPLACEMENT OF DRAINAGE INFRASTRUCTURE, AND PAVEMENT MARKINGS.
- PARKING POSITION 1B AND 1 WILL REMAIN CLOSED FOR THE DURATION OF PHASE 1. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR REROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

**SPECIAL CONSIDERATIONS**

- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

REVISIONS		
NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA


SHEET TITLE

**PHASE 1 PLAN**

SHEET NUMBER  
**G-121**

**90%  
SUBMITTAL**





LEGEND



ANY TIME WORK



RESTRICTED TIME WORK



PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



PROPOSED TEMPORARY VSR BARRICADES



TEMPORARY DETOUR SIGN



TEMPORARY ARFF ACCESS ROUTE

PHASE 2 NOTES

1. PHASE 2A = 13 DAYS; PHASE 2B = 11 DAYS. PHASE 2A AND 2B CANNOT BE WORKED ON CONCURRENTLY. PHASE 2A MUST BE COMPLETED FIRST BEFORE THE START OF PHASE 2B. THE ENTIRETY OF PHASES 2A AND 2B CANNOT LAST MORE THAN 24 CALENDAR DAYS.
2. PHASE 2 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, AND PAVEMENT MARKINGS.
3. PARKING POSITION 2 WILL REMAIN CLOSED FOR THE DURATION OF PHASE 2. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
4. LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
5. DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
6. AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
7. AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
8. NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
9. REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

SPECIAL CONSIDERATIONS

1. THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
2. ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION


REVISIONS		
NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE

**PHASE 2A PLAN**

SHEET NUMBER  
**G-122**  
**90%  
SUBMITTAL**







## TERMINAL APRON REHABILITATION

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

## REVISIONS

[illegible]

FAA NO:	X-XX-XXXX-XXX-XXXX
RS&H NO:	1054-1892-017
DATE ISSUED:	MARCH 2025
DESIGN BY:	RKH
DRAWN BY:	GNH
REVIEWED BY:	CCA


SHEET TITLE

## PHASE 2B PLAN

SHEET NUMBER

**G-123**

**90%  
SUBMITTAL**



### LEGEND



ANY TIME WORK



### RESTRICTED TIME WORK



### PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



### PROPOSED TEMPORARY VSR BARRICADES



TEMPORARY DETOUR SIGN



TEMPORARY ARFF ACCESS ROUTE

## PHASE 2 NOTES

1. PHASE 2A = 13 DAYS; PHASE 2B = 11 DAYS. PHASE 2A AND 2B CANNOT BE WORKED ON CONCURRENTLY. PHASE 2A MUST BE COMPLETED FIRST BEFORE THE START OF PHASE 2B. THE ENTIRETY OF PHASES 2A AND 2B CANNOT LAST MORE THAN 24 CALENDAR DAYS.
2. PHASE 2 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, AND PAVEMENT MARKINGS.
3. PARKING POSITION 2 WILL REMAIN CLOSED FOR THE DURATION OF PHASE 2. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
4. LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
5. DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
6. AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
7. AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
8. NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
9. REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

## SPECIAL CONSIDERATIONS

1. THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
2. ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



**HORIZONTAL SCALE: 1" = 20'**  
(WHEN PLOTTED 22X34)





**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

**REVISIONS**

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE


**PHASE 3 PLAN**

SHEET NUMBER


**G-124**

**90%  
SUBMITTAL**

**LEGEND**



ANY TIME WORK



RESTRICTED TIME WORK



PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



PROPOSED TEMPORARY VSR  
BARRICADES




TEMPORARY DETOUR SIGN

**PHASE 3 NOTES**


- DURATION = 31 CALENDAR DAYS
- PHASE 3 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, RELOCATION AND REPLACEMENT OF DRAINAGE INFRASTRUCTURE, AND PAVEMENT MARKINGS.
- PARKING POSITION 3 WILL REMAIN CLOSED FOR THE DURATION OF PHASE 3. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

**SPECIAL CONSIDERATIONS**


- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR







LEGEND



ANY TIME WORK



RESTRICTED TIME WORK



PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



PROPOSED TEMPORARY VSR BARRICADES



TEMPORARY DETOUR SIGN



TEMPORARY BAGGAGE TUG ROUTE

PHASE 4 NOTES

- DURATION = 31 CALENDAR DAYS
- PHASE 4 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, RELOCATION AND REPLACEMENT OF DRAINAGE INFRASTRUCTURE, AND PAVEMENT MARKINGS.
- PARKING POSITION 4 WILL REMAIN CLOSED FOR THE DURATION OF PHASE 4. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

SPECIAL CONSIDERATIONS

- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR



**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

REVISIONS

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA


SHEET TITLE

**PHASE 4 PLAN**


SHEET NUMBER

**G-125**


**90%  
SUBMITTAL**







LEGEND



ANY TIME WORK



RESTRICTED TIME WORK



PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



PROPOSED TEMPORARY VSR BARRICADES



TEMPORARY DETOUR SIGN




TEMPORARY BAGGAGE TUG ROUTE

PHASE 5 NOTES

- DURATION = 20 CALENDAR DAYS
- PHASE 5 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, AND PAVEMENT MARKINGS.
- PARKING POSITION 5A WILL REMAIN CLOSED FOR THE DURATION OF PHASE 5. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

SPECIAL CONSIDERATIONS

- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



**RS&H**

**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com

**CHO**  
AIRPORT

**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

REVISIONS

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE


**PHASE 5 PLAN**

SHEET NUMBER

**G-125**

**90%  
SUBMITTAL**





LEGEND


- ANY TIME WORK
- RESTRICTED TIME WORK
- PHASE LIMITS
- TSA PROPOSED TAXIWAY SAFETY AREA
- TOFA PROPOSED TAXIWAY OBJECT FREE AREA
- PROPOSED TEMPORARY VSR BARRICADES
- TEMPORARY DETOUR SIGN

PHASE 6 NOTES

- DURATION = 12 CALENDAR DAYS
- PHASE 6 WORK CONSISTS OF INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT AND PAVEMENT MARKINGS.
- PARKING POSITION 5B WILL REMAIN CLOSED FOR THE DURATION OF PHASE 6. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK. Y THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

SPECIAL CONSIDERATIONS

- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

REVISIONS

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE


**PHASE 6 PLAN**

SHEET NUMBER

**G-126**

**90%  
SUBMITTAL**





**LEGEND**



ANY TIME WORK



RESTRICTED TIME WORK



PHASE LIMITS



PROPOSED TAXIWAY SAFETY AREA



PROPOSED TAXIWAY OBJECT FREE AREA



PROPOSED TEMPORARY VSR BARRICADES



TEMPORARY DETOUR SIGN

**PHASE 7 NOTES**

- DURATION = 28 CALENDAR DAYS
- PHASE 7 WORK CONSISTS OF FULL DEPTH CONCRETE RECONSTRUCTION, ISOLATED SLAB REPLACEMENTS, INSTALLATION OF CONCRETE TRANSITION SLAB UNDERNEATH ASPHALT PAVEMENT, AND PAVEMENT MARKINGS.
- PARKING POSITION 5C AND 5D WILL REMAIN CLOSED FOR THE DURATION OF PHASE 1. NO AIRCRAFT CAN UTILIZE THESE PARKING POSITIONS UNTIL INITIAL CONCRETE POUR HAS REACHED 650 PSI FLEXURAL STRENGTH AND WHEN INITIAL PAVEMENT MARKING APPLICATION ON CONCRETE SLABS AFFECTED BY THE RECONSTRUCTION AND ISOLATED SLAB REPLACEMENTS.
- LOW-PROFILE BARRICADES ARE TO BE PLACED AT A MAX 1' OFFSET FROM PAVEMENT LIMITS. FINAL BARRICADE PLACEMENT TO BE APPROVED BY THE RPR AND AIRPORT OPERATIONS/PERSONNEL.
- DURING PHASE WORK, THE VSR WILL BE TEMPORARILY REROUTED BY CONES OR OTHER CHO APPROVED METHOD. NO TEMPORARY PAVEMENT MARKINGS WILL BE PLACED FOR VSR RE-ROUTING DURING PHASE. THE CONTRACTOR MAY NEED TO READJUST BARRICADE PLACEMENT TO ALLOW UNINTERRUPTED VSR REROUTING THROUGHOUT PHASE WORK.
- AREAS ASSIGNED UNDER RESTRICTED HOURS MUST BE COMPLETED DURING NIGHTLY CLOSURES FROM 12:00 AM - 4:00 AM. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE CLEAR FROM THE APRON AND ALL LOW-PROFILE BARRICADES (AND STEEL PLATES IF SLABS ARE REMOVED) MUST BE IN PLACE BEFORE 4:00 AM.
- AIRCRAFT PARKING POSITION MARKINGS SHALL BE PERMANENTLY MARKED AT THE END OF PHASE BEFORE REOPENING AREA TO AIR TRAFFIC. VSR AND NON-MOVEMENT AREA BOUNDARY MARKING TO BE APPLIED AT HALF APPLICATION, IN ITS NEW PROPOSED LOCATION AT END OF PHASE. SEE C-800 SERIES FOR PAVEMENT MARKING PLANS.
- NON-MOVEMENT AREA BOUNDARY MARKING AND VSR WILL BE SCHEDULED TO RECEIVE ITS FULL APPLICATION, PERMANENT MARKING DURING PHASE 8.
- REFER TO GENERAL NOTES ON SHEET G-003 FOR CIVIL LEGEND AND COVER SHEET FOR ABBREVIATIONS.

**SPECIAL CONSIDERATIONS**

- THE RPR MAY ADJUST PHASE LIMITS AND/OR SEQUENCE AS REQUIRED. ANY TIE-IN WORK REQUIRED OUTSIDE OF PRIMARY PHASE LIMITS SHOWN SHALL BE APPROVED AND COORDINATED WITH THE RPR.
- ALL TAXIWAYS ADJACENT TO WORK AREA SHALL BE OPEN AT ALL TIMES UNLESS OTHERWISE COORDINATED WITH THE RPR.



HORIZONTAL SCALE: 1" = 20'  
(WHEN PLOTTED 22X34)

**RS&H**

**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com

**CHO**  
AIRPORT

**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

**REVISIONS**

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MARCH 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE

**PHASE 7 PLAN**

SHEET NUMBER

**G-127**

**90%  
SUBMITTAL**



1. THE AREAS DESIGNATED FOR RESTRICTED HOURS. SHALL BE COVERED BY A STEEL PLATE AND/OR SURROUNDED BY LOW-PROFILE BARRICADES (TYPICALLY 10" IN HEIGHT) DURING THE AIRLINE'S NORMAL OPERATING HOURS. AIRCRAFT TAXIING NEXT TO THE COVERED AND BARRICADED AREAS SHALL MAINTAIN A MINIMUM 20' CLEARANCE FROM WINGTIP TO EDGE OF COVERED SLABS. HOWEVER, THERE ARE INSTANCES WHEN AN AIRCRAFT CANNOT MAINTAIN A MINIMUM 20' WINGTIP CLEARANCE TO THE EDGE OF SLAB REPLACEMENT OR RECONSTRUCTION; ESPECIALLY IN THE AREAS ADJACENT TO OPEN GATES. IN THAT SITUATION, A MINIMUM 12' CLEARANCE FROM THE MAIN GEAR TO THE EDGE OF COVERED SLABS. SEE DETAIL 2 ON SHEET G-153.
2. THIS CONSTRUCTION SAFETY AND PHASING PLAN IS A GENERAL DESCRIPTION OF WORK TO BE PERFORMED. A DETAILED SEQUENCE OF WORK SHALL BE DEVELOPED BY THE CONTRACTOR AND SUBMITTED FOR APPROVAL. THE CONTRACTOR SHALL NOT DEVIATE FROM THE APPROVED SEQUENCE OF WORK WITHOUT THE PRIOR WRITTEN APPROVAL OF THE RPR.
3. THE CONTRACTOR SHALL NOTE THAT EXISTING CONSTRUCTION PROJECTS MAY BE ONGOING WITHIN OR ADJACENT TO THE LIMITS OF THIS CONTRACT AT THE TIME THE NTP IS ISSUED. THE CONTRACTOR SHALL COORDINATE PROJECT WORK LIMITS AND SITE ACCESS WITH OTHER CONTRACTORS THROUGH THE RPR.
4. THE CONTRACTOR MAY BE UTILIZING THE SAME INGRESS/EGRESS GATES AS OTHER POTENTIALLY CONCURRENT PROJECTS.
5. THE CONTRACTOR SHALL SUBMIT A TWO WEEK WORK SCHEDULE ONE WEEK PRIOR TO COMMENCEMENT OF ANY WORK. THE CONTRACTOR SHALL COORDINATE THE WORK SCHEDULE THROUGH THE RPR, WITH THE FAA, CHO OPERATIONS, AND OTHER WORK ON THE AOA REQUIRING THE ISSUING OF A NOTICE TO AIRMEN (NOTAM) BY THE AIRPORT.
6. THE CONTRACTOR WILL WORK CLOSELY WITH THE RPR IN COORDINATING SCHEDULES TO MINIMIZE CONFLICTS AND TO COMPLETE THE PROJECT IN A TIMELY MANNER.
7. FOR ACCESS TO THE SITE, VEHICULAR & EQUIPMENT TRAVEL ON AIRPORT, AND AIRPORT SECURITY, THE CONTRACTOR MUST ADHERE TO SPECIAL PROVISIONS IN CONTRACT DOCUMENTS.
8. AS OUTLINED IN AC 150/5370-2G, PARA 2.14, THE CONTRACTOR SHALL CONDUCT INSPECTIONS DAILY, BUT MORE FREQUENTLY IF NECESSARY TO ENSURE CONFORMANCE WITH THE CSPP.
9. THE CONTRACTOR SHALL SUPPLY AND PLACE LOW PROFILE BARRICADES AS DIRECTED BY THE RPR. BARRICADES SHALL BE PLACED AT ALL LOCATIONS WHERE PROPOSED WORK AREAS ADJOIN ACTIVE TAXIWAYS AND WHERE EXCAVATIONS ON THE AIRFIELD REQUIRE A TEMPORARY COVER.
10. THE CONTRACTOR IS REQUIRED TO MAINTAIN CLEAN AIRFIELD PAVEMENTS AT CROSSING LOCATIONS. FLAGPERSON REQUIRED TO PERFORM VISUAL INSPECTION OF AIRFIELD PAVEMENTS AT CROSSING LOCATIONS AFTER EACH CROSSING/PRIOR TO OPENING TO TRAFFIC.
11. THE CONTRACTOR SHALL DELINEATE THE PERIMETER OF WORK AREA WITH LIGHTED BARRICADES OR OTHER METHODS AS APPROVED BY RPR. ON PAVEMENT, TSA AND RSA SHALL BE DELINEATED WITH LOW PROFILE BARRICADES. OFF PAVEMENT, TSA AND RSA SHALL BE DELINEATED BY SURVEY STAKES, AS APPROVED BY THE RPR.
12. THE CONTRACTOR SHALL ACQUAINT THEIR SUPERVISORS AND EMPLOYEES WITH THE AIRPORT ACTIVITY AND OPERATIONS THAT ARE INHERENT TO THE CHARLOTTESVILLE-ALBEMARLE AIRPORT AND SHALL CONDUCT THEIR CONSTRUCTION ACTIVITIES TO CONFORM TO ALL ROUTINE AND EMERGENCY AIR TRAFFIC REQUIREMENTS AND GUIDELINES FOR SAFETY SPECIFIED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL SAFETY DEVICES AS REQUIRED FOR THE PROTECTION OF THEIR PERSONNEL.
13. PROTECTION OF ALL PERSONS SHALL BE PROVIDED THROUGHOUT THE PROGRESS OF THE WORK. THE WORK SHALL PROCEED IN SUCH A MANNER AS TO PROVIDE SAFE CONDITIONS FOR ALL WORKERS AND AIRPORT PERSONNEL. THE SEQUENCE OF OPERATION SHALL BE SUCH THAT MAXIMUM PROTECTION IS AFFORDED TO CONSTRUCTION AND NON-CONSTRUCTION PERSONNEL. TO ENSURE THAT PERSONNEL AND WORKERS IN THE AREA ARE PROTECTED, THE CONTRACTOR MUST PROVIDE SAFETY MEASURES TO GUARD AGAINST INJURY.
14. DURING PERFORMANCE OF THIS CONTRACT, THE AIRPORT RUNWAYS, TAXIWAYS AND AIRCRAFT HOLDING APRONS SHALL REMAIN IN USE BY AIRCRAFT TO THE MAXIMUM EXTENT POSSIBLE. ALL AIRCRAFT TRAFFIC IN THESE AREAS SHALL HAVE PRIORITY OVER CONTRACTOR'S TRAFFIC. THE OWNER RESERVES THE RIGHT TO ORDER THE CONTRACTOR, AT ANY TIME, TO VACATE ANY AREA NECESSARY TO MAINTAIN SAFE AIRCRAFT OPERATIONS. USE OF AREAS NEAR THE CONTRACTOR'S WORK WILL BE CONTROLLED TO MINIMIZE DISTURBANCE TO THE CONTRACTOR'S OPERATION. THE CONTRACTOR SHALL NOT ALLOW UNAUTHORIZED PERSONS TO ENTER OR REMAIN IN ANY AIRPORT AREA WHICH WOULD BE HAZARDOUS TO PERSONS OR TO AIRCRAFT OPERATIONS.
15. ALL WORK IS TO BE COORDINATED TO KEEP RUNWAY AND TAXIWAY INTERSECTIONS OPEN FOR TAXIING TO AND FROM THE TERMINAL. CAREFUL COORDINATION AND COMMUNICATION MUST BE MAINTAINED WITH THE RPR, OPERATIONS, AND TOWER AS TO WHEN EACH RUNWAY AND TAXIWAY IS OPEN OR CLOSED.
16. WORK WITHIN THE OFA MAY NOT PROCEED, NOR MAY VEHICLES ENCR OACH WITHIN THIS AREA UNTIL THE APPROPRIATE NOTAMS HAVE BEEN ISSUED.
17. ALL CONSTRUCTION VEHICLES THAT ROUTINELY OPERATE ON THE AIRPORT AIRSIDE WILL BE MARKED AND LIGHTED IN ACCORDANCE WITH THE REQUIREMENTS OF FAA AC 150/5370-2G (CURRENT VERSION). ALL VEHICLES MUST HAVE COMPANY NAME PERMANENTLY AFFIXED ON THE FRONT AND BE PROPERLY INSURED AS PER THIS CONTRACT'S LIMITS. ANY VEHICLE OPERATING IN THE ACTIVE AREA DURING THE HOURS OF DARKNESS, TIMES OF LOW VISIBILITY, OR IN THE RUNWAY SAFETY AREA AT ANY TIME, SHALL BE EQUIPPED WITH A FLASHING AMBER (YELLOW) DOME TYPE LIGHT MOUNTED ON TOP OF THE VEHICLE AND OF SUCH INTENSITY TO CONFORM WITH FAA REQUIREMENTS. NO PERSONAL VEHICLES ARE PERMITTED WITHIN THE AOA. ALL VEHICLES USED ON THE AIRPORT DURING CONSTRUCTION SHALL HAVE REQUIRED SIGNAGE, SAFETY FLAGS, AND BEACON AS SET FORTH IN THE SPECIFICATIONS. ANY PERSON NOT ADHERING TO THE PROPER OPERATION OF A VEHICLE OR NOT OPERATING WITHIN THE DESIGNATED AREA ON THE AIRPORT SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND NOT ALLOWED TO CONTINUE WORK ON THE PROJECT.
18. DURING TIMES WHEN SAFETY OF FLIGHT OPERATIONS COULD BE IMPAIRED, OR WHEN EQUIPMENT IS IDLE, ALL CONTRACTOR'S BOOMS, TOWERS, AND OTHER MOVABLE APPENDAGES SHALL BE LOWERED TO THE MAXIMUM EXTENT AND PARKED OFFSITE OR IN A LOCATION DIRECTED BY THE RPR.
19. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BRIEF ALL OF THE CONTRACTOR'S AND SUBCONTRACTOR'S EMPLOYEES ON THE FAA OPERATING AND SAFETY REQUIREMENTS. A COMPREHENSIVE SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) SHALL BE SUBMITTED TO THE RPR FOR REVIEW AND APPROVAL. THE APPROVED SAFETY PLAN MAY CONTAIN DEVIATIONS FROM THE CRITERIA OUTLINED IN FAA AC 150/5370-2G (CURRENT VERSION) SO LONG AS THEY ARE BASED UPON A COMMITMENT BY AIRPORT OPERATOR AND USERS TO PROVIDE THE MAXIMUM CONSTRUCTION CLEARANCES POSSIBLE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT WITHIN THE LIMITS IMPOSED BY LOCAL CONDITIONS.
20. THE CONTRACTOR SHALL RESPOND IMMEDIATELY TO DIRECTION FROM THE OWNER, FAA, OR THE RPR REGARDING AIRSIDE OPERATIONS.
21. THE CONTRACTOR SHALL COORDINATE DAILY CONSTRUCTION OPERATION WITH THE RPR EACH DAY PRIOR TO BEGINNING WORK.
22. THE CONTRACTOR SHALL PREVENT ANY MATERIAL ASSOCIATED WITH THE CONTRACTOR'S OPERATIONS FROM BLOWING, SPILLING, OR BEING TRANSPORTED ONTO ACTIVE PAVEMENT (PAVEMENT OPEN TO AIRCRAFT TRAFFIC) WHERE IT CAN POSE A FOD HAZARD TO AIRCRAFT. THE CONTRACTOR SHALL IMMEDIATELY REMOVE ANY FOD MATERIAL RESULTING FROM THEIR ACTIVITIES, FROM ACTIVE OPERATIONAL PAVEMENT AND SHALL BE RESPONSIBLE FOR ANY DAMAGE WHICH RESULTS. IN ADDITION, ALL PAVEMENTS ADJACENT TO CONTRACTOR WORK AREAS WILL BE

24. THE SAFETY PLAN FOR THIS SPECIFIC PROJECT MUST INCLUDE ALL ITEMS SPECIFIED IN THE ADVISORY CIRCULARS REFERENCED IN THE SAFETY NOTICES (FAA AC 150/5370-2G, FAA AC 150/5300-13B). THE CONTRACTOR MUST SUBMIT FOUR COPIES OF THE "SAFETY PLAN COMPLIANCE DOCUMENT (SPCD)" TO THE RPR FOR APPROVAL 10 DAYS PRIOR TO MOBILIZING ON THE JOB.

25. ALL CONTRACTOR/SUBCONTRACTOR EMPLOYEES WHICH WILL OPERATE A VEHICLE IN THE NON-MOVEMENT PORTION OF THE AOA SHALL CONTACT CHO OPERATIONS AND SCHEDULE TRAINING. MOVEMENT AREA DRIVER TRAINING WILL NOT BE PROVIDED. VEHICLES WILL NOT COMMUNICATE WITH THE TOWER.

26. THE MAXIMUM CONSTRUCTION TRAFFIC SPEED ON ALL AIRPORT PROPERTY SHALL BE 15 MPH.

27. EMERGENCY VEHICLE ACCESS SHALL BE MAINTAINED AT ALL TIMES ON THE EXISTING PAVEMENT ON THE AOA SIDE OF THE SECURITY FENCE. MAINTAIN ALL EXISTING MEANS OF EGRESS FREE FROM OBSTRUCTIONS INCLUDING BUT NOT LIMITED TO TEMPORARY OR PERMANENT CONSTRUCTION, STAGED MATERIALS, TOOLS AND EQUIPMENT AT ALL TIMES.

28. ALL CONSTRUCTION TRAFFIC MUST REMAIN ON THE VSR, OR DESIGNATED HAUL ROUTES, MAINTAINING A DISTANCE OF AT LEAST 25 FEET FROM ANY PARKED AIRCRAFT AT ALL TIMES.

29. FAA AC, ORDERS AND REGULATIONS, THE FOLLOWING PUBLICATIONS CONTAIN DEFINITIONS/DESCRIPTIONS OF CRITICAL AIRPORT OPERATING AREAS. THE AREAS DEFINED BELOW PERTAIN TO AIRFIELD SAFETY REQUIREMENTS AND ARE REFERENCED THROUGHOUT THE CONTRACT DOCUMENTS. COPIES OF THESE PUBLICATIONS ARE AVAILABLE THROUGH THE FAA:

- A. AC 150/5370-2G, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", CURRENT EDITION AT TIME OF BID, SETS FORTH GUIDELINES TO ASSIST AIRPORT OPERATORS IN COMPLYING WITH FAR PART 139, "CERTIFICATION AND OPERATION: LAND AIRPORTS SERVING CERTAIN AIR CARRIERS" AND WITH THE REQUIREMENTS OF FEDERALLY FUNDED CONSTRUCTION PROJECTS
- B. FAA FAR PART 77 "OBJECTS AFFECTING NAVIGABLE AIRSPACE", CURRENT EDITION:
  - 1. ESTABLISHES STANDARDS FOR DETERMINING OBSTRUCTIONS TO NAVIGATE AIRSPACE. CIVIL AIRPORT IMAGINARY SURFACES ARE DEFINED IN THE PUBLICATION.
  - 2. SETS FORTH REQUIREMENTS FOR NOTICE OF CERTAIN PROPOSED CONSTRUCTION OR ALTERATION. NOTICE OF CONSTRUCTION PROVIDES A BASIS FOR RECOMMENDATIONS FOR IDENTIFYING THE CONSTRUCTION OF ALTERATION IN ACCORDANCE WITH AC 70/7460-1M "OBSTRUCTION MARKING AND LIGHTING". CURRENT EDITION AT TIME OF BID.
- C. AC 150/5300-13B, CH.1 "AIRPORT DESIGN", CURRENT EDITION AT TIME OF BID, ESTABLISHES DESIGN, OPERATIONAL, AND MAINTENANCE STANDARDS FOR AIRPORTS. STANDARD TERMS USED IN THE CONTRACT PLANS AND SPECIFICATIONS ARE DEFINED BELOW:
  - 1. OBJECT FREE AREA - A TWO DIMENSIONAL GROUND AREA SURROUNDING RUNWAYS, TAXIWAYS, AND TAXILANES, WHICH IS CLEAR OF OBJECTS EXCEPT FOR OBJECTS WHOSE LOCATION IS FIXED BY FUNCTION
  - 2. SAFETY AREA - THE SURFACE ADJACENT TO RUNWAYS, TAXIWAYS, AND TAXILANES OVER WHICH AIRCRAFT SHOULD, IN DRY WEATHER, BE ABLE TO CROSS AT NORMAL SPEEDS WITHOUT INCURRING SIGNIFICANT DAMAGE. A SAFETY AREA IS GRADED, DRAINED AND COMPACTED. IT IS FREE OF ANY HOLES, TRENCHES, BUMPS OR OTHER SIGNIFICANT SURFACE VARIATIONS OR OBJECTS OTHER THAN THOSE WHICH MUST BE THERE BECAUSE OF THEIR ESSENTIAL AERONAUTICAL FUNCTION. THE SAFETY AREA REQUIRES THE CAPABILITY OF SUPPORTING MAINTENANCE VEHICLES AND AIRCRAFT RESCUE AND FIRE FIGHTING (ARFF) VEHICLES UNDER NORMAL (DRY) CONDITIONS.

30. ALL TRUCKS HAULING DEBRIS FROM THE AIRPORT OR MATERIAL TO THE PROJECT SHALL BE EQUIPPED WITH TAILGATES AND COVER TARPS WHICH CLOSE TIGHTLY AND DO NOT PERMIT DEBRIS TO SPILL FROM THE TRUCK. TRUCK BEDS SHALL BE SWEEPED CLEAN AT THE TAILGATE BEFORE ENTERING THE AOA OR LEAVING THE WORK AREA. SIDEBOARDS SHALL BE KEPT IN GOOD REPAIR. TRUCKS MUST BE EQUIPPED WITH TAILGATES OF GREATER THAN THE FEDERAL SAFETY STANDARD, A LEGAL LIMIT OR HIGHER THAN THE SIDEBOARDS. TRUCKS NOT MEETING THESE REQUIREMENTS OR THAT ALLOW MATERIAL TO BE WINDBLOWN OR TO ESCAPE THEIR CONTAINMENT BEDS ONTO THE ROADWAYS OR AIRCRAFT APRONS WILL BE REMOVED FROM THE PROJECT AT THE RPR'S DIRECTION. THE RPR WILL MONITOR CONTRACTOR ACTIVITIES ACCORDINGLY.

33. THE CONTRACTOR SHALL MAINTAIN A CLEAN CONSTRUCTION AREA. NO TRASH, FOOD OR ANY OTHER MATERIAL THAT MAY ATTRACT WILDLIFE SHALL BE LEFT IN THE CONSTRUCTION/ AREAS.

35. CONTRACT DURATION, MILESTONES AND LIQUIDATED DAMAGES ARE OUTLINED IN CONTRACT SPECIFICATIONS.

37. CONTRACTOR MUST BE AWARE OF JET BLAST AND TAKE PRECAUTIONS TO PROTECT HIS WORKERS IN ACCORDANCE WITH HIS APPROVED SAFETY PLAN. JET BLAST IS NOT ONLY THE WIND, BUT ALSO ITEMS THAT MAY BE CARRIED BY THE WIND.





1. BARRICADES SHALL BE INSTALLED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE RPR AND AS REQUIRED BY THE CONTRACTOR TO PROTECT THE WORK AREA. THE PHASE DURING WHICH EACH BARRICADE IS TO REMAIN IN PLACE IS INDICATED BY THE PHASING DRAWINGS. BARRICADES SHALL BE INSTALLED AT THE BEGINNING OF EACH PHASE AND SHALL REMAIN IN PLACE THROUGHOUT THE PHASE. IF THE CONTRACTOR MUST TEMPORARILY REMOVE ANY OF THE BARRICADES (TO ALLOW CONSTRUCTION TRAFFIC TO TRAVEL INTO OR OUT OF THE CONSTRUCTION AREA, OR TO COMPLETE CONSTRUCTION AT THE PHASE BOUNDARY), THE CONTRACTOR SHALL PROVIDE A FLAGMAN TO PREVENT AIRCRAFT OR VEHICLE TRAFFIC FROM INADVERTENTLY TRAVELING INTO THE CONSTRUCTION AREA UNTIL THE BARRICADE IS REPLACED AT ITS ORIGINAL POSITION.
2. LOW PROFILE BARRICADES SHALL BE WATER-FILLED TYPE BARRICADES DESCRIBED IN THE SPECIFICATIONS AND SHALL BE USED (AT A MINIMUM) TO BLOCK ACCESS TO A CLOSED RUNWAY, TAXIWAYS WITH HARD CLOSURES, TAXILANES, TAXIWAYS WITH TEMPORARY CLOSURES, OR TO IDENTIFY PANELS THAT CANNOT BE DRIVEN ON. CONTRACTOR TO PROVIDE AND SECURE LOW PROFILE BARRICADES BY SAND BAGS, OR OTHER METHOD APPROVED BY THE RPR, TO WEIGH DOWN THE BARRICADES TO PREVENT MOVEMENT BY JET BLAST.
3. BARRICADES SHALL BE CONNECTED WITH NO SPACE IN BETWEEN FROM END TO END EXCEPT TO ALLOW CONSTRUCTION OR AS DIRECTED BY THE RPR. BARRICADES SHALL BE INSPECTED DAILY (LIGHTS AND WEIGHT) AND REPLACED WHEN DEFECTIVE.
4. INSTALL BARRICADES ON PAVEMENT EDGE NEAR EXCAVATED CUTS AND ADJACENT TO AIRCRAFT OPERATIONAL PAVEMENTS, AROUND PERIMETER OF WORK AREAS, AS DIRECTED BY RPR.
5. ALL FLASHING RED LOW PROFILE BARRIER LIGHTS MUST REMAIN OPERABLE DURING PERIODS OF LOW VISIBILITY AND DARKNESS.
6. THE CONTRACTOR SHALL PROVIDE LIGHTED BARRICADES AS REQUIRED IN THIS CONTRACT DURING THE CONSTRUCTION OF THE ENTIRE PROJECT AS PER THE SPECIFICATIONS.
7. THE COLOR OF BARRICADES SHALL BE INTERNATIONAL ORANGE AND WHITE WITH ALTERNATING ORANGE/WHITE CHEVRON STRIPES ON EXPOSED SIDES.
8. THE BARRICADES SHALL BE PLACED AT THE MINIMUM DISTANCE SHOWN ON THE PHASING PLANS UNLESS COORDINATED WITH THE RPR.
9. BARRICADES NEED TO SHIFT FREQUENTLY DURING CONSTRUCTION. CONTRACTOR SHALL INCLUDE COSTS RELATED TO SHIFTING TO FACILITATE WORK IN HIS PAY ITEM FOR TEMPORARY CONSTRUCTION ITEMS.
10. THE CONTRACTOR SHALL FURNISH, MAINTAIN, AND REMOVE THE BARRICADES AS DIRECTED BY THE RPR. THE COST ASSOCIATED WITH THIS WORK SHALL BE INCLUDED IN THE C-106 TEMPORARY CONSTRUCTION ITEMS PAY ITEM.
11. THE CONTRACTOR MUST PROVIDE A POINT OF CONTACT THAT MUST BE AVAILABLE 24/7 BY PHONE AND ABLE TO BE ON SITE TO REPLACE OR FURNISH ADDITIONAL BARRICADES IN THE EVENT THEY NEED TO BE REPLACED DURING NON-WORKING HOURS.
12. THE CONTRACTOR SHALL CHECK ALL LIGHTS ON A DAILY BASIS AND REPLACE ANY BULBS OR BATTERIES AS NEEDED EACH DAY.



1. SIGN LOCATIONS SHALL BE COORDINATED WITH THE RPR OR CHO OPERATIONS.
2. TEMPORARY SIGNS SHALL BE CONSTRUCTED TO WITHSTAND 200 MPH WINDS AND JET BLAST FROM AIRCRAFT WITHOUT BENDING OR CHANGING SHAPE.
3. ANY WORK WITHIN TSA SHALL BE COMPLETED AT NIGHT DURING CLOSURE OF THE TAXIWAY. TAXIWAYS MAY REMAIN OPEN DURING THE DAY TO AIRCRAFT OPERATIONS, WITHOUT RESTORING THE TSA OR TOFA, SUBJECT TO THE FOLLOWING RESTRICTIONS:
  - 3.1. TAXIING SPEED IS LIMITED TO 10 MPH.
  - 3.2. APPROPRIATE NOTAMS ADVISING TAXIING PILOTS MUST BE ISSUED PRIOR TO THE START OF ANY WORK WITHIN TSA OR TOFA.
  - 3.3. LOW PROFILE LIGHTED BARRICADES ARE INSTALLED AT THE EDGE OF REMAINING PAVEMENT.
  - 3.4. APPROPRIATE TEMPORARY ORANGE CONSTRUCTION SIGNS ARE INSTALLED PER THE REQUIREMENTS OF AC 150/5370-2G, FAA ENGINEERING BRIEF 93, MUTCD, AND THE CSPP. CONTRACTOR SHALL PROVIDE PHASING PLAN, SUPPORTED BY DRAWINGS AND SIGN SCHEDULE FOR THE INSTALLATION OF ORANGE CONSTRUCTION SIGNS, WITHIN THE SPCD.
  - 3.5. CONTRACTOR MUST COVER OPEN TRENCHES AND EXCAVATIONS WITH STEEL CRANE MATS DURING HOURS OF NORMAL OPERATIONS.
  - 3.6. 20-FOOT CLEARANCE IS MAINTAINED BETWEEN THE EQUIPMENT AND MATERIALS AND ANY PART OF THE AIRCRAFT (INCLUDES WINGTIP OVERHANG). IF SUCH CLEARANCE CAN ONLY BE MAINTAINED IF AN AIRCRAFT DOES NOT HAVE FULL USE OF THE ENTIRE TAXIWAY WIDTH, THEN IT WILL BE NECESSARY TO MOVE PERSONNEL AND EQUIPMENT FOR THE PASSAGE OF THAT AIRCRAFT.
  - 3.7. FLAGGERS FURNISHED BY THE CONTRACTOR MUST BE USED TO DIRECT AND CONTROL CONSTRUCTION EQUIPMENT AND PERSONNEL TO A PRE-ESTABLISHED SETBACK DISTANCE FOR SAFE PASSAGE OF AIRCRAFT.
4. SIGNS WILL BE USED DURING ALL PHASES WHEN PORTIONS OF THE VSR CANNOT BE ACCESSED. SIGNS SHALL BE PLACED ON EITHER SIDE OF THE WORK AREA TO DIVERT EASTBOUND AND WESTBOUND GSE DRIVING PATHS.
5. TEMPORARY MOUNTING DETAILS SHALL BE PROVIDED BY THE CONTRACTOR DURING SHOP DRAWING REVIEW. MOUNTING SHALL BE FRANGIBLE AND NO PERMANENT PART OF THE MOUNTING SHALL PROTRUDE UP MORE THAN 12 INCHES ABOVE FINISHED GRADE. ENSURE MOUNTING PROCEDURE SUBMITTED WITH SHOP DRAWINGS.
6. COSTS FOR SIGNS SHALL BE INCLUDED IN ITEM C-106-1.
7. SIGN SHALL MATCH DETOUR SIGN, M4-9, IN ACCORDANCE WITH MUTCD STANDARDS. SIGN IS TO BE LOCATED HIGH ENOUGH TO ALLOW EASY VIEWING FROM ALL GSE VEHICLES ENTERING THE APRON.
8. SIGNS SHALL BE PROPERTY OF THE AIRPORT AFTER CONSTRUCTION HAS BEEN COMPLETED.



**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

## TERMINAL APRON REHABILITATION

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

[illegible]

SHEET TITLE

**CONSTRUCTION  
SAFETY AND  
PHASING NOTES  
AND DETAILS 2**

---




SHEET NUMBER

**G-152**

---

**90%  
SUBMITTAL**








1 **AIRCRAFT TAXIING SAFETY CLEARANCE DURING CONSTRUCTION ON SLABS WITH ANY TIME WORK HOURS**  
Scale: NTS

NOTES:

- IT IS REQUIRED THAT PCC OBTAIN STRENGTH OF 650 PSI FLEXURAL WITHIN 10 DAYS OF POUR PER SPEC P-501 BEFORE THE SLAB CAN BE OPENED AND AIRCRAFT CAN OPERATE ON IT.
- CONTRACTOR SHALL SUPPLY AN ADEQUATE NUMBER AND SIZES OF CRANE MATS OR SIMILAR MATERIAL TO COVER VOID CAUSED BY REMOVED CONCRETE. CRANE MATS SHALL BE SURROUNDED WITH LOW PROFILE BARRICADES. ALL COSTS TO SUPPLY AND MAINTAIN MATERIALS TO COVER VOID LEFT BY REMOVING CONCRETE PANEL SHALL BE INCIDENTAL TO THE P-501 AND C-106 PAY ITEMS



2 **AIRCRAFT TAXIING SAFETY CLEARANCE DURING CONSTRUCTION ON SLABS WITH RESTRICTED WORK HOURS**  
Scale: NTS

**RS&H**

**RS&H, Inc**  
2600 PARK TOWER DR  
SUITE 101  
Vienna, VA 22180  
(703) 207-4791  
www.rsandh.com

**CHO**  
AIRPORT

**CHARLOTTESVILLE  
ALBEMARLE  
AIRPORT**

**TERMINAL  
APRON  
REHABILITATION**

100 BOWEN LOOP, #200  
CHARLOTTESVILLE, VA 22911

NOT FOR CONSTRUCTION

**REVISIONS**

NO.	DATE	ISSUED FOR

FAA NO: X-XX-XXXX-XXX-XXXX  
RS&H NO: 1054-1892-017  
DATE ISSUED: MAY 2025  
DESIGN BY: RKH  
DRAWN BY: GNH  
REVIEWED BY: CCA

SHEET TITLE

**CONSTRUCTION  
SAFETY AND  
PHASING NOTES  
AND DETAILS 3**

SHEET NUMBER

**G-153**

**90%  
SUBMITTAL**

## **Appendix B – Construction Project Daily Safety Inspection Checklist**

**APPENDIX D. CONSTRUCTION PROJECT DAILY SAFETY INSPECTION CHECKLIST**

The situations identified below are potentially hazardous conditions that may occur during airport construction projects. Safety area encroachments, unauthorized and improper ground vehicle operations, and unmarked or uncovered holes and trenches near aircraft operating surfaces pose the most prevalent threats to airport operational safety during airport construction projects. The list below is one tool that the airport operator or contractor may use to aid in identifying and correcting potentially hazardous conditions. It should be customized as appropriate for each project including information such as the date, time and name of the person conducting the inspection.

**Table D-1. Potentially Hazardous Conditions**

<b>Item</b>	<b>Action Required (Describe)</b>	<b>No Action Required (Check)</b>
Excavation adjacent to runways, taxiways, and aprons improperly backfilled.		
Mounds of earth, construction materials, temporary structures, and other obstacles near any open runway, taxiway, or taxi lane; in the related Object Free area and aircraft approach or departure areas/zones; or obstructing any sign or marking.		
Runway resurfacing projects resulting in lips exceeding 3 inch (7.6 cm) from pavement edges and ends.		
Heavy equipment (stationary or mobile) operating or idle near AOA, in runway approaches and departures areas, or in OFZ.		
Equipment or material near NAVAIDs that may degrade or impair radiated signals and/or the monitoring of navigation and visual aids. Unauthorized or improper vehicle operations in localizer or glide slope critical areas, resulting in electronic interference and/or facility shutdown.		
Tall and especially relatively low visibility units (that is, equipment with slim profiles) — cranes, drills, and similar objects — located in critical areas, such as OFZ and		



<b>Item</b>	<b>Action Required (Describe)</b>	<b>No Action Required (Check)</b>
approach zones.		
Improperly positioned or malfunctioning lights or unlighted airport hazards, such as holes or excavations, on any apron, open taxiway, or open taxi lane or in a related safety, approach, or departure area.		
Obstacles, loose pavement, trash, and other debris on or near AOA. Construction debris (gravel, sand, mud, paving materials) on airport pavements may result in aircraft propeller, turbine engine, or tire damage. Also, loose materials may blow about, potentially causing personal injury or equipment damage.		
Inappropriate or poorly maintained fencing during construction intended to deter human and animal intrusions into the AOA. Fencing and other markings that are inadequate to separate construction areas from open AOA create aviation hazards.		
Improper or inadequate marking or lighting of runways (especially thresholds that have been displaced or runways that have been closed) and taxiways that could cause pilot confusion and provide a potential for a runway incursion. Inadequate or improper methods of marking, barricading, and lighting of temporarily closed portions of AOA create aviation hazards.		
Wildlife attractants — such as trash (food scraps not collected from construction personnel activity), grass seeds, tall grass, or standing water — on or near airports.		
Obliterated or faded temporary markings on active operational areas.		
Misleading or malfunctioning obstruction lights. Unlighted or unmarked obstructions in the approach to any open runway pose aviation hazards.		

<b>Item</b>	<b>Action Required (Describe)</b>	<b>No Action Required (Check)</b>
Failure to issue, update, or cancel NOTAMs about airport or runway closures or other construction related airport conditions.		
Failure to mark and identify utilities or power cables. Damage to utilities and power cables during construction activity can result in the loss of runway / taxiway lighting; loss of navigation, visual, or approach aids; disruption of weather reporting services; and/or loss of communications.		
Restrictions on ARFF access from fire stations to the runway / taxiway system or airport buildings.		
Lack of radio communications with construction vehicles in airport movement areas.		
Objects, regardless of whether they are marked or flagged, or activities anywhere on or near an airport that could be distracting, confusing, or alarming to pilots during aircraft operations.		
Water, snow, dirt, debris, or other contaminants that temporarily obscure or derogate the visibility of runway/taxiway marking, lighting, and pavement edges. Any condition or factor that obscures or diminishes the visibility of areas under construction.		
Spillage from vehicles (gasoline, diesel fuel, oil) on active pavement areas, such as runways, taxiways, aprons, and airport roadways.		
Failure to maintain drainage system integrity during construction (for example, no temporary drainage provided when working on a drainage system).		

<b>Item</b>	<b>Action Required (Describe)</b>	<b>No Action Required (Check)</b>
Failure to provide for proper electrical lockout and tagging procedures. At larger airports with multiple maintenance shifts/workers, construction contractors should make provisions for coordinating work on circuits.		
Failure to control dust. Consider limiting the amount of area from which the contractor is allowed to strip turf.		
Exposed wiring that creates an electrocution or fire ignition hazard. Identify and secure wiring, and place it in conduit or bury it.		
Site burning, which can cause possible obscuration.		
Construction work taking place outside of designated work areas and out of phase.		

Page Intentionally Blank

Technical Specifications

## **Item C-100 Contractor Quality Control Program (CQCP)**

**100-1 General.** Quality is more than test results. Quality is the combination of proper materials, testing, workmanship, equipment, inspection, and documentation of the project. Establishing and maintaining a culture of quality is key to achieving a quality project. The Contractor shall establish, provide, and maintain an effective Contractor Quality Control Program (CQCP) that details the methods and procedures that will be taken to assure that all materials and completed construction required by this contract conform to contract plans, technical specifications and other requirements, whether manufactured by the Contractor, or procured from subcontractors or vendors. Although guidelines are established and certain minimum requirements are specified here and elsewhere in the contract technical specifications, the Contractor shall assume full responsibility for accomplishing the stated purpose.

The Contractor shall establish a CQCP that will:

- a. Provide qualified personnel to develop and implement the CQCP.
- b. Provide for the production of acceptable quality materials.
- c. Provide sufficient information to assure that the specification requirements can be met.
- d. Document the CQCP process.

The Contractor shall not begin any construction or production of materials to be incorporated into the completed work until the CQCP has been reviewed and approved by the Resident Project Representative (RPR). No partial payment will be made for materials subject to specific quality control (QC) requirements until the CQCP has been reviewed and approved.

The QC requirements contained in this section and elsewhere in the contract technical specifications are in addition to and separate from the quality assurance (QA) testing requirements. QA testing requirements are the responsibility of the RPR or Contractor as specified in the specifications.

A Quality Control (QC)/Quality Assurance (QA) workshop with the Engineer, Resident Project Representative (RPR), Contractor, subcontractors, testing laboratories, and Owner's representative must be held prior to start of construction. The QC/QA workshop will be facilitated by the Contractor. The Contractor shall coordinate with the Airport and the RPR on time and location of the QC/QA workshop. Items to be addressed, at a minimum, will include:

- a. Review of the CQCP including submittals, QC Testing, Action & Suspension Limits for Production, Corrective Action Plans, Distribution of QC reports, and Control Charts.
- b. Discussion of the QA program.
- c. Discussion of the QC and QA Organization and authority including coordination and information exchange between QC and QA.
- d. Establish regular meetings to discuss control of materials, methods and testing.
- e. Establishment of the overall QC culture.

### **100-2 Description of program.**

**a. General description.** The Contractor shall establish a CQCP to perform QC inspection and testing of all items of work required by the technical specifications, including those performed by subcontractors. The CQCP shall ensure conformance to applicable specifications and plans with respect to materials, off-

site fabrication, workmanship, construction, finish, and functional performance. The CQCP shall be effective for control of all construction work performed under this Contract and shall specifically include surveillance and tests required by the technical specifications, in addition to other requirements of this section and any other activities deemed necessary by the Contractor to establish an effective level of QC.

**b. Contractor Quality Control Program (CQCP).** The Contractor shall describe the CQCP in a written document that shall be reviewed and approved by the RPR prior to the start of any production, construction, or off-site fabrication. The written CQCP shall be submitted to the RPR for review and approval at least 10 calendar days before the CQCP Workshop. The Contractor's CQCP and QC testing laboratory must be approved in writing by the RPR prior to the Notice to Proceed (NTP).

The CQCP shall be organized to address, as a minimum, the following:

1. QC organization and resumes of key staff
2. Project progress schedule
3. Submittals schedule
4. Inspection requirements
5. QC testing plan
6. Documentation of QC activities and distribution of QC reports
7. Requirements for corrective action when QC and/or QA acceptance criteria are not met
8. Material quality and construction means and methods. Address all elements applicable to the project that affect the quality of the pavement structure including subgrade, subbase, base, and surface course. Some elements that must be addressed include, but is not limited to mix design, aggregate grading, stockpile management, mixing and transporting, placing and finishing, quality control testing and inspection, smoothness, laydown plan, equipment, and temperature management plan.

The Contractor must add any additional elements to the CQCP that is necessary to adequately control all production and/or construction processes required by this contract.

**100-3 CQCP organization.** The CQCP shall be implemented by the establishment of a QC organization. An organizational chart shall be developed to show all QC personnel, their authority, and how these personnel integrate with other management/production and construction functions and personnel.

The organizational chart shall identify all QC staff by name and function, and shall indicate the total staff required to implement all elements of the CQCP, including inspection and testing for each item of work. If necessary, different technicians can be used for specific inspection and testing functions for different items of work. If an outside organization or independent testing laboratory is used for implementation of all or part of the CQCP, the personnel assigned shall be subject to the qualification requirements of paragraphs 100-03a and 100-03b. The organizational chart shall indicate which personnel are Contractor employees and which are provided by an outside organization.

The QC organization shall, as a minimum, consist of the following personnel:

**a. Program Administrator.** The Contractor Quality Control Program Administrator (CQCPA) must be a full-time on-site employee of the Contractor, or a consultant engaged by the Contractor. The CQCPA must have a minimum of five (5) years of experience in QC pavement construction with prior QC experience on a project of comparable size and scope as the contract.

Included in the five (5) years of paving/QC experience, the CQCPA must meet at least one of the following requirements:

- (1) Professional Engineer with one (1) year of airport paving experience.

(2) Engineer-in-training with two (2) years of airport paving experience.

(3) National Institute for Certification in Engineering Technologies (NICET) Civil Engineering Technology Level IV with three (3) years of airport paving experience.

(4) An individual with four (4) years of airport paving experience, with a Bachelor of Science Degree in Civil Engineering, Civil Engineering Technology or Construction.

The CQCPA must have full authority to institute any and all actions necessary for the successful implementation of the CQCP to ensure compliance with the contract plans and technical specifications. The CQCPA authority must include the ability to immediately stop production until materials and/or processes are in compliance with contract specifications. The CQCPA must report directly to a principal officer of the construction firm. The CQCPA may supervise the Quality Control Program on more than one project provided that person can be at the job site within two (2) hours after being notified of a problem.

**b. QC technicians.** A sufficient number of QC technicians necessary to adequately implement the CQCP must be provided. These personnel must be either Engineers, engineering technicians, or experienced craftsman with qualifications in the appropriate field equivalent to NICET Level II in Civil Engineering Technology or higher, and shall have a minimum of two (2) years of experience in their area of expertise.

The QC technicians must report directly to the CQCPA and shall perform the following functions:

- (1) Inspection of all materials, construction, plant, and equipment for conformance to the technical specifications, and as required by paragraph 100-6.
- (2) Performance of all QC tests as required by the technical specifications and paragraph 100-8.
- (3) Performance of tests for the RPR when required by the technical specifications.

Certification at an equivalent level of qualification and experience by a state or nationally recognized organization will be acceptable in lieu of NICET certification.

**c. Staffing levels.** The Contractor shall provide sufficient qualified QC personnel to monitor each work activity at all times. Where material is being produced in a plant for incorporation into the work, separate plant and field technicians shall be provided at each plant and field placement location. The scheduling and coordinating of all inspection and testing must match the type and pace of work activity. The CQCP shall state where different technicians will be required for different work elements.

**100-4 Project progress schedule.** Critical QC activities must be shown on the project schedule as required by Section 80, paragraph 80-03, *Execution and Progress*.

**100-5 Submittals schedule.** The Contractor shall submit a detailed listing of all submittals (for example, mix designs, material certifications) and shop drawings required by the technical specifications. The listing can be developed in a spreadsheet format and shall include as a minimum:

- a. Specification item number
- b. Item description
- c. Description of submittal
- d. Specification paragraph requiring submittal
- e. Scheduled date of submittal

**100-6 Inspection requirements.** QC inspection functions shall be organized to provide inspections for all definable features of work, as detailed below. All inspections shall be documented by the Contractor as specified by paragraph 100-9.



Inspections shall be performed as needed to ensure continuing compliance with contract requirements until completion of the particular feature of work. Inspections shall include the following minimum requirements:

**a.** During plant operation for material production, QC test results and periodic inspections shall be used to ensure the quality of aggregates and other mix components, and to adjust and control mix proportioning to meet the approved mix design and other requirements of the technical specifications. All equipment used in proportioning and mixing shall be inspected to ensure its proper operating condition. The CQCP shall detail how these and other QC functions will be accomplished and used.

**b.** During field operations, QC test results and periodic inspections shall be used to ensure the quality of all materials and workmanship. All equipment used in placing, finishing, and compacting shall be inspected to ensure its proper operating condition and to ensure that all such operations are in conformance to the technical specifications and are within the plan dimensions, lines, grades, and tolerances specified. The CQCP shall document how these and other QC functions will be accomplished and used.

#### **100-7 Contractor QC testing facility.**

**a.** For projects that include Item P-401, Item P-403, and Item P-404, the Contractor shall ensure facilities, including all necessary equipment, materials, and current reference standards, are provided that meet requirements in the following paragraphs of ASTM D3666, *Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials*:

8.1.3 Equipment Calibration and Checks;

8.1.9 Equipment Calibration, Standardization, and Check Records;

8.1.12 Test Methods and Procedures

**b.** For projects that include P-501, the Contractor shall ensure facilities, including all necessary equipment, materials, and current reference standards, are provided that meet requirements in the following paragraphs of ASTM C1077, *Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation*:

7 Test Methods and Procedures

8 Facilities, Equipment, and Supplemental Procedures

**100-8 QC testing plan.** As a part of the overall CQCP, the Contractor shall implement a QC testing plan, as required by the technical specifications. The testing plan shall include the minimum tests and test frequencies required by each technical specification Item, as well as any additional QC tests that the Contractor deems necessary to adequately control production and/or construction processes.

The QC testing plan can be developed in a spreadsheet fashion and shall, as a minimum, include the following:

**a.** Specification item number (e.g., P-401)

**b.** Item description (e.g., Hot Mix Asphalt Pavements)

**c.** Test type (e.g., gradation, grade, asphalt content)

**d.** Test standard (e.g., ASTM or American Association of State Highway and Transportation Officials (AASHTO) test number, as applicable)

**e.** Test frequency (e.g., as required by technical specifications or minimum frequency when requirements are not stated)

**f.** Responsibility (e.g., plant technician)

**g. Control requirements (e.g., target, permissible deviations)**

The QC testing plan shall contain a statistically-based procedure of random sampling for acquiring test samples in accordance with ASTM D3665. The RPR shall be provided the opportunity to witness QC sampling and testing.

All QC test results shall be documented by the Contractor as required by paragraph 100-9.

**100-9 Documentation.** The Contractor shall maintain current QC records of all inspections and tests performed. These records shall include factual evidence that the required QC inspections or tests have been performed, including type and number of inspections or tests involved; results of inspections or tests; nature of defects, deviations, causes for rejection, etc.; proposed remedial action; and corrective actions taken.

These records must cover both conforming and defective or deficient features, and must include a statement that all supplies and materials incorporated in the work are in full compliance with the terms of the contract. Legible copies of these records shall be furnished to the RPR daily. The records shall cover all work placed subsequent to the previously furnished records and shall be verified and signed by the CQCPA.

Contractor QC records required for the contract shall include, but are not necessarily limited to, the following records:

**a. Daily inspection reports.** Each Contractor QC technician shall maintain a daily log of all inspections performed for both Contractor and subcontractor operations. These technician's daily reports shall provide factual evidence that continuous QC inspections have been performed and shall, as a minimum, include the following:

- (1) Technical specification item number and description
- (2) Compliance with approved submittals
- (3) Proper storage of materials and equipment
- (4) Proper operation of all equipment
- (5) Adherence to plans and technical specifications
- (6) Summary of any necessary corrective actions
- (7) Safety inspection
- (8) Photographs and/or video

The daily inspection reports shall identify all QC inspections and QC tests conducted, results of inspections, location and nature of defects found, causes for rejection, and remedial or corrective actions taken or proposed.

The daily inspection reports shall be signed by the responsible QC technician and the CQCPA. The RPR shall be provided at least one copy of each daily inspection report on the work day following the day of record. When QC inspection and test results are recorded and transmitted electronically, the results must be archived.

**b. Daily test reports.** The Contractor shall be responsible for establishing a system that will record all QC test results. Daily test reports shall document the following information:

- (1) Technical specification item number and description
- (2) Test designation
- (3) Location
- (4) Date of test
- (5) Control requirements

- (6) Test results
- (7) Causes for rejection
- (8) Recommended remedial actions
- (9) Retests

Test results from each day's work period shall be submitted to the RPR prior to the start of the next day's work period. When required by the technical specifications, the Contractor shall maintain statistical QC charts. When QC daily test results are recorded and transmitted electronically, the results must be archived.

**100-10 Corrective action requirements.** The CQCP shall indicate the appropriate action to be taken when a process is deemed, or believed, to be out of control (out of tolerance) and detail what action will be taken to bring the process into control. The requirements for corrective action shall include both general requirements for operation of the CQCP as a whole, and for individual items of work contained in the technical specifications.

The CQCP shall detail how the results of QC inspections and tests will be used for determining the need for corrective action and shall contain clear rules to gauge when a process is out of control and the type of correction to be taken to regain process control.

When applicable or required by the technical specifications, the Contractor shall establish and use statistical QC charts for individual QC tests. The requirements for corrective action shall be linked to the control charts.

**100-11 Inspection and/or observations by the RPR.** All items of material and equipment are subject to inspection and/or observation by the RPR at the point of production, manufacture or shipment to determine if the Contractor, producer, manufacturer or shipper maintains an adequate QC system in conformance with the requirements detailed here and the applicable technical specifications and plans. In addition, all items of materials, equipment and work in place shall be subject to inspection and/or observation by the RPR at the site for the same purpose.

Inspection and/or observations by the RPR does not relieve the Contractor of performing QC inspections of either on-site or off-site Contractor's or subcontractor's work.

#### **100-12 Noncompliance.**

**a.** The Resident Project Representative (RPR) will provide written notice to the Contractor of any noncompliance with their CQCP. After receipt of such notice, the Contractor must take corrective action.

**b.** When QC activities do not comply with either the CQCP or the contract provisions or when the Contractor fails to properly operate and maintain an effective CQCP, and no effective corrective actions have been taken after notification of non-compliance, the RPR will recommend the Owner take the following actions:

- (1) Order the Contractor to replace ineffective or unqualified QC personnel or subcontractors and/or
- (2) Order the Contractor to stop operations until appropriate corrective actions are taken.

### **METHOD OF MEASUREMENT**

**100-13 Basis of measurement and payment.** Not used; CQCP shall be incidental to Item C-105 Mobilization.

## **BASIS OF PAYMENT**

### **100-14 Payment will be made under:**

~~[ Item C-100 Contractor Quality Control Program (CQCP) ]~~

## **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

National Institute for Certification in Engineering Technologies (NICET)

ASTM International (ASTM)

ASTM C1077	Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D3666	Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials

## **END OF ITEM C-100**

Page Intentionally Blank

## Item C-102 Temporary Air and Water Pollution, Soil Erosion, and Siltation Control

### DESCRIPTION

**102-1.** This item shall consist of temporary control measures as shown on the plans or as ordered by the Resident Project Representative (RPR) during the life of a contract to control pollution of air and water, soil erosion, and siltation through the use of silt fences, berms, dikes, dams, sediment basins, fiber mats, gravel, mulches, grasses, slope drains, and other erosion control devices or methods.

Temporary erosion control shall be in accordance with the approved erosion control plan; the approved Construction Safety and Phasing Plan (CSPP) and AC 150/5370-2, *Operational Safety on Airports During Construction*. The temporary erosion control measures contained herein shall be coordinated with the permanent erosion control measures specified as part of this contract to the extent practical to assure economical, effective, and continuous erosion control throughout the construction period.

Temporary control may include work outside the construction limits such as borrow pit operations, equipment and material storage sites, waste areas, and temporary plant sites.

Temporary control measures shall be designed, installed and maintained to minimize the creation of wildlife attractants that have the potential to attract hazardous wildlife on or near public-use airports.

### MATERIALS

**102-2.1 Grass.** **Not Used.** ~~Grass that will not compete with the grasses sown later for permanent cover per Item T-901 shall be a quick-growing species (such as ryegrass, Italian ryegrass, or cereal grasses) suitable to the area providing a temporary cover. Selected grass species shall not create a wildlife attractant.~~

**102-2.2 Mulches.** **Not Used.** ~~Mulches may be hay, straw, fiber mats, netting, bark, wood chips, or other suitable material reasonably clean and free of noxious weeds and deleterious materials per Item T-908. Mulches shall not create a wildlife attractant.~~

**102-2.3 Fertilizer.** **Not Used.** ~~Fertilizer shall be a standard commercial grade and shall conform to all federal and state regulations and to the standards of the Association of Official Agricultural Chemists.~~

**102-2.4 Slope drains.** **Not Used.** ~~Slope drains may be constructed of pipe, fiber mats, rubble, concrete, asphalt, or other materials that will adequately control erosion.~~

**102-2.5 Silt fence.** **Not Used.** ~~Silt fence shall consist of polymeric filaments which are formed into a stable network such that filaments retain their relative positions. Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of six months of expected usable construction life. Silt fence shall meet the requirements of ASTM D6461.~~

**102-2.6 Inlet Protection.** Inlet protection will be provided by inlet filter bags and shall conform to the detail for Inlet Protection provided on the Erosion and Sedimentation Control plans, notes, and details.

**102-2.7 Trench Drain Protection.** Trench drain protection will be provided by filter fabric and shall conform to the detail for Trench Drain Protection provided on the Erosion and Sedimentation Control plans, notes, and details.

**102-2.8 Other.** All other materials shall meet commercial grade standards and shall be approved by the RPR before being incorporated into the project.

## CONSTRUCTION REQUIREMENTS

**102-3.1 General.** In the event of conflict between these requirements and pollution control laws, rules, or regulations of other federal, state, or local agencies, the more restrictive laws, rules, or regulations shall apply.

The RPR shall be responsible for assuring compliance to the extent that construction practices, construction operations, and construction work are involved.

**102-3.2 Schedule.** Prior to the start of construction, the Contractor shall submit schedules in accordance with the approved Construction Safety and Phasing Plan (CSPP) and the plans for accomplishment of temporary and permanent erosion control work for clearing and grubbing; grading; construction; paving; and structures at watercourses. The Contractor shall also submit a proposed method of erosion and dust control on haul roads and borrow pits and a plan for disposal of waste materials. Work shall not be started until the erosion control schedules and methods of operation for the applicable construction have been accepted by the RPR.

**102-3.3 Construction details.** The Contractor will be required to incorporate all permanent erosion control features into the project at the earliest practicable time as outlined in the plans and approved CSPP. Except where future construction operations will damage slopes, the Contractor shall perform the permanent seeding and mulching and other specified slope protection work in stages, as soon as substantial areas of exposed slopes can be made available. Temporary erosion and pollution control measures will be used to correct conditions that develop during construction that were not foreseen during the design stage; ~~that are needed prior to installation of permanent control features; or that are needed temporarily to control erosion that develops during normal construction practices, but are not associated with permanent control features on the project.~~

Where erosion may be a problem, schedule and perform clearing and grubbing operations so that grading operations and permanent erosion control features can follow immediately if project conditions permit. Temporary erosion control measures are required if permanent measures cannot immediately follow grading operations. The RPR shall limit the area of clearing and grubbing, excavation, borrow, and embankment operations in progress, commensurate with the Contractor's capability and progress in keeping the finish grading, mulching, seeding, and other such permanent control measures current with the accepted schedule. If seasonal limitations make such coordination unrealistic, temporary erosion control measures shall be taken immediately to the extent feasible and justified as directed by the RPR.

The Contractor shall provide immediate permanent or temporary pollution control measures to minimize contamination of adjacent streams or other watercourses, lakes, ponds, or other areas of water impoundment as directed by the RPR. If temporary erosion and pollution control measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the work as scheduled or directed by the RPR, the work shall be performed by the Contractor and the cost shall be incidental to this item.

The RPR may increase or decrease the area of erodible earth material that can be exposed at any time based on an analysis of project conditions.

The erosion control features installed by the Contractor shall be maintained by the Contractor during the construction period.

Provide temporary structures whenever construction equipment must cross watercourses at frequent intervals. Pollutants such as fuels, lubricants, bitumen, raw sewage, wash water from concrete mixing operations, and other harmful materials shall not be discharged into any waterways, impoundments or into natural or manmade channels.

**102-3.4 Installation, maintenance and removal of silt fence.** Not Used. ~~Silt fences shall extend a minimum of 16 inches (41 cm) and a maximum of 34 inches (86 cm) above the ground surface. Posts~~

~~shall be set no more than 10 feet (3 m) on center. Filter fabric shall be cut from a continuous roll to the length required minimizing joints where possible. When joints are necessary, the fabric shall be spliced at a support post with a minimum 12 inch (300 mm) overlap and securely sealed. A trench shall be excavated approximately 4 inches (100 mm) deep by 4 inches (100 mm) wide on the upslope side of the silt fence. The trench shall be backfilled and the soil compacted over the silt fence fabric. The Contractor shall remove and dispose of silt that accumulates during construction and prior to establishment of permanent erosion control. The fence shall be maintained in good working condition until permanent erosion control is established. Silt fence shall be removed upon approval of the RPR.~~

## METHOD OF MEASUREMENT

**102-4.1** Temporary erosion and pollution control work required will be performed as scheduled or directed by the RPR. Completed and accepted work will be measured as follows:

- a. Installation and removal of filter bag inlet protection will be measured by each. Maintenance of filter bag inlet protection shall be incidental to the installation and removal.
- b. Installation and removal of trench drain protection will be measured by linear foot. Maintenance of trench drain protection shall be incidental to the installation and removal.

**102-4.2** Control work performed for protection of construction areas outside the construction limits, such as borrow and waste areas, haul roads, equipment and material storage sites, and temporary plant sites, will not be measured and paid for directly but shall be considered as a subsidiary obligation of the Contractor.

## BASIS OF PAYMENT

**102-5.1** Accepted quantities of temporary water pollution, soil erosion, and siltation control work ordered by the RPR and measured as provided in paragraph 102-4.1 will be paid for under:

Item C-102-5.1	Installation and Removal of Inlet Protection – per each
Item C-102-5.2	Installation and Removal of Trench Drain Protection – per linear foot

Where other directed work falls within the specifications for a work item that has a contract price, the units of work shall be measured and paid for at the contract unit price bid for the various items.

Temporary control features not covered by contract items that are ordered by the RPR will be paid for in accordance with Section 90, paragraph 90-05 *Payment for Extra Work*.

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Advisory Circulars (AC)

AC 150/5200-33	<i>Hazardous Wildlife Attractants on or Near Airports</i>
AC 150/5370-2	<i>Operational Safety on Airports During Construction</i>



ASTM International (ASTM)

ASTM D6461                      *Standard Specification for Silt Fence Materials*

United States Department of Agriculture (USDA)

FAA/USDA Wildlife Hazard Management at Airports, A Manual for Airport Personnel

**END OF ITEM C-102**

## ITEM C-103 SAFETY AND SECURITY

### GENERAL

**103-1.1** The provisions of this safety and security plan and associated procedures are applicable within the boundaries of the Philadelphia International Airport. A complete understanding of all procedures and requirements contained herein is required to ensure safety during construction. *The Airport has completed a Construction Safety and Phasing Plan (CSPP), which is included as an appendix of the Project Manual. It is required that the contractor comply with this CSPP at all times during the project. The Contractor shall be required to submit for approval a Safety Plan Compliance Document (SPCD) which details how the contractor will comply with the CSPP.* This safety plan is a part of this Contract and deviations from the requirements established herein will be sufficient cause for Contract termination.

Required reference material associated with this safety plan includes:

FAA AC 150/5200-18, Airport Safety Self-Inspection  
FAA AC 150/5210-5, Painting, Marking and Lighting of Vehicles Used on an Airport  
FAA AC 150/5370-2, Operational Safety on Airports During Construction

These documents are available online at [http://www.faa.gov/airports/resources/advisory\\_circulars](http://www.faa.gov/airports/resources/advisory_circulars) or can be provided upon request.

### CONTRACTOR SAFETY AND SECURITY OFFICER

**103-2.1 CONTRACTOR SAFETY AND SECURITY OFFICER (CSSO).** The Contractor shall appoint its on-site Construction Superintendent or other qualified individual(s) as its duly authorized representative to serve as Contractor Safety and Security Officer (CSSO) for the duration of the Contract. The CSSO shall thoroughly understand the safety and security requirements of the Contract, the necessity for them and shall have sufficient authority to implement its provisions without significant deviation. The Contractor shall notify the Construction Manager in writing of the name of the individual(s) selected for the assignment.

The CSSO shall represent the Contractor on safety and security requirements compliance. The CSSO shall be especially knowledgeable regarding the requirements of FAA AC's 150/5200-18, Airport Self Inspection Guide and 150/5370-2 Operational Safety on Airports During Construction, latest edition.

**103-2.2 RESPONSIBILITIES OF THE CONTRACTOR SAFETY AND SECURITY OFFICER.** Prior to the desired date for commencement of any work on the project, the CSSO shall accomplish the following:

**a.** Develop and submit in writing a detailed work sequence schedule with dates and times specified for all milestone events. This sequence schedule shall be subject to the approval of the Construction Manager. To assure adequate time for coordination, this document shall be submitted at least one week prior to the date of the Pre-construction Conference.

**b.** Develop and submit in writing a detailed outline of the procedures to be followed to maintain

safety and security of both Contractor operations and the integrity of airport landside and airside operations during the prosecution of contract work. This plan shall detail, in addition, the procedures to be followed in the event of an accident or fire involving Contractor personnel and the Contractor's efforts to maintain fire protection and security. These procedures shall be subject to the approval of the Construction Manager and reflect any change as may be deemed necessary.

c. Conduct at least one meeting of all Contractor supervisory personnel prior to the start of contract work. The purpose of this meeting is to review the approved Work sequence schedule and safety and security procedures. Attendance at this meeting by the CSSO, all Contractor supervisory personnel and the Construction Manager is mandatory. This meeting shall also be open to other employees of the Contractor and others as the Construction Manager may deem appropriate. Minutes of this meeting shall be taken by the CSSO, copies provided to each supervisor and kept on file in the Contractor's construction office for periodic review and updating.

d. Develop a safety and security orientation program and provide a briefing for all employees of the Contractor and subcontractors that will be used on the project. A similar briefing will be given to new employees prior to their use on contract work. In addition, the CSSO shall be responsible for briefing, from time to time, all Contractor personnel on any changes to safety and security measures deemed necessary.

e. Submit a Safety Plan Compliance Document (SPCD) to the airport operator describing how it will comply with the requirements of the CSPP and supplying any details that could not be determined before contract award. The SPCD must include a certification statement by the contractor that indicates it understands the operational safety requirements of the CSPP and it asserts it will not deviate from the approved CSPP and SPCD unless written approval is granted by the airport operator. Any construction practice proposed by the contractor that does not conform to the CSPP and SPCD may impact the airport's operational safety and will require a revision to the CSPP and SPCD and re-coordination with the airport operator and the FAA in advance.

1) **The Safety Plan Compliance Document (SPCD) should include a general statement by the construction contractor that he/she has read and will abide by the CSPP.** In addition, the SPCD must include all supplemental information that could not be included in the CSPP prior to the contract award. The contractor statement should include the name of the contractor, the title of the project CSPP, the approval date of the CSPP, and a reference to any supplemental information (that is, "I, Name of Contractor, have read the Title of Project CSPP, approved on Date, and will abide by it as written and with the following additions as noted:"). The supplemental information in the SPCD should be written to match the format of the CSPP indicating each subject by corresponding CSPP subject number and title. If no supplemental information is necessary for any specific subject, the statement, "No supplemental information," should be written after the corresponding subject title. The SPCD should not duplicate information in the CSPP:

i. **Coordination.** Discuss details of proposed safety meetings with the airport operator and with contractor employees and subcontractors.

ii. **Phasing.** Discuss proposed construction schedule elements, including:

1. Duration of each phase.
2. Daily start and finish of construction, including "night only" construction.
3. Duration of construction activities during:

- iii. **Areas and operations affected by the construction activity.** These areas and operations should be identified in the CSPP and should not require an entry in the SPCD.
- iv. **Protection of NAVAIDs.** Not applicable.
- v. **Contractor access.** Provide the following:
  - 1. Details on how the contractor will maintain the integrity of the airport security fence (gate guards, daily log of construction personnel, and other).
  - 2. Details on how the contractor will escort material delivery vehicles.
- vi. **Wildlife management.** Discuss the following:
  - 1. Methods and procedures to prevent wildlife attraction.
  - 2. Wildlife reporting procedures.
- vii. **Foreign Object Debris (FOD) management.** Discuss equipment and methods for control of FOD, including construction debris and dust.
- viii. **Hazardous material (HAZMAT) management.** Discuss equipment and methods for responding to hazardous spills.
- ix. **Notification of construction activities.** Provide the following:
  - 1. Contractor points of contact.
  - 2. Contractor emergency contact.
  - 3. Listing of tall or other requested equipment proposed for use on the airport and the timeframe for submitting 7460-1 forms not previously submitted by the airport operator.
- x. **Inspection requirements.** Discuss daily (or more frequent) inspections and special inspection procedures.
- xi. **Underground utilities.** Discuss proposed methods of identifying and protecting underground utilities.
- xii. **Penalties.** Any penalties are identified in the CSPP.
- xiii. **Special conditions.** Discuss proposed actions for each special condition identified in the CSPP.
- xiv. **Runway and taxiway visual aids.** Not applicable.
- xv. **Marking and signs for access routes.** Discuss proposed methods of demarcating access routes for vehicle drivers.
- xvi. **Hazard marking and lighting.** Discuss proposed equipment and methods for identifying excavation areas.
- xvii. **Protection of runway and taxiway safety areas, including object free areas, obstacle free zones, and approach/departure surfaces.** Discuss proposed equipment and methods for protection of work area within the taxiway object free area.

xviii. **Other limitations on construction** should be identified in the CSPP and should not require an entry in the SPCD.

- 2) Have available at all times copies of the CSPP and SPCD for reference by the airport operator and its representatives, and by subcontractors and contractor employees.
- 3) Ensure that construction personnel are familiar with safety procedures and regulations on the airport. Provide a point of contact who will coordinate an immediate response to correct any construction-related activity that may adversely affect the operational safety of the airport. Contractor shall provide 24-hour coverage.
- 4) Identify in the SPCD the contractor's on-site employees responsible for monitoring compliance with the CSPP and SPCD during construction. At least one of these employees must be on-site whenever active construction is taking place.
- 5) Conduct inspections sufficiently frequently to ensure construction personnel comply with the CSPP and SPCD and that there are no altered construction activities that could create potential safety hazards.
- 6) Restrict movement of construction vehicles and personnel to permitted construction areas by flagging, barricading, erecting temporary fencing, or providing escorts, as appropriate and as specified in the CSPP and SPCD.
- 7) Ensure that no contractor employees, employees of subcontractors or suppliers, or other persons enter any part of the air operations area (AOA) from the construction site unless authorized.
- 8) The Contractor shall submit and receive approval of SPCD prior to issuance of Notice to Proceed.

## **CONSTRUCTION SEQUENCING**

**103-3.1 CONSTRUCTION SEQUENCE.** The Contractor shall prepare a construction schedule and submit to the Construction Manager within 15 days from the date of award of the Contract.

## **MARKING AND LIGHTING**

**103-4.1** Proper marking and lighting of areas on the airfield associated with the construction shall be the responsibility of the Contractor and shall be described by the SPCD. This will include properly marking and lighting closed runways, taxiways, taxilanes, and aprons, the limits of construction, material storage areas, equipment storage areas, haul routes, parking areas and other areas defined as required for the Contractor's exclusive use. The Contractor shall erect and maintain around the perimeter of these areas suitable marking and warning devices visible for day and night use. Temporary barricades, flagging, and flashing warning lights shall be required at critical access points. The type and location of marking and warning devices will be approved by the Construction Manager.

Special emphasis shall be given to open trenches, excavations, heavy equipment marshalling areas, and stockpiled material located in the airport operations area, which shall be predominantly marked by the

Contractor with flags and lighted by approved light units during hours of restricted visibility and darkness. All marking shall be in accordance with FAA Advisory Circular (AC) 150/5340-1, latest edition.

## TRAFFIC CONTROL

**103-5.1 VEHICLE IDENTIFICATION.** The Contractor shall establish and maintain a list of Contractor and subcontractor vehicles authorized to operate on the site. Contractor employee vehicles shall be restricted to the Contractor's staging area and are not allowed in the Airport Operations Area (AOA) at any time. To be authorized to operate on the airport, each Contractor or subcontractor's vehicle shall:

a. be marked/flagged for high daytime visibility and lighted for nighttime operations. Vehicles that are not marked and/or lighted shall be escorted by a vehicle appropriately marked and/or lighted. Vehicles requiring escort shall be identified on the list.

b. be identified with the name and/or logo of the Contractor and be of sufficient size to be identified at a distance. Vehicles needing intermittent identification could be marked with tape or with commercially available magnetically attached markers. Vehicles that are not appropriately identified shall be escorted by a vehicle that conforms to this requirement. Vehicles requiring escort shall be identified on the list.

c. be operated in a manner that does not compromise the safety of either landside or airside airport operations. If, in the opinion of the Construction Manager, any vehicle is operated in a manner not fully consistent with this requirement, the Construction Manager has the right to restrict operation of the vehicle or prohibit its use on the airport.

**103-5.2 ACCESS TO THE SITE OF CONSTRUCTION.** The Contractor's access to the site shall be as shown on the Contract Layout Plan. No other access points shall be allowed unless approved by the Construction Manager. All Contractor traffic authorized to enter the site shall be experienced in the route or guided by Contractor personnel. The Contractor shall be responsible for traffic control to and from the various construction areas on the site, and for the operation and security of the access gate to the site. A Contractor's flagman or traffic control person shall monitor and coordinate all Contractor traffic at the access gate with Airport Security. The Contractor shall not permit any unauthorized construction personnel or traffic on the site. Access gates to the site shall be locked and secured at all times when not attended by the Contractor. If the Contractor chooses to leave any access gate open, it shall be attended by Contractor personnel who are familiar with the requirements of the Airport Security Program. The Contractor is responsible for the immediate cleanup of any debris deposited along the access route as a result of his construction traffic. Directional signing from the access gate along the delivery route to the storage area, plant site or work site shall be as directed by the Construction Manager. In addition, the following requirements are applicable:

a. All Contractor traffic authorized to travel on the airport shall have been briefed as part of the Contractor's construction safety and security orientation program, be thoroughly familiar with the access procedures and route for travel or be escorted by personnel authorized by the Contractor Safety and Security Officer (CSSO).

b. The Contractor shall install work site identification signs at the authorized access point(s). If, in the opinion of the Construction Manager, directional signs are needed for clarity, they shall be installed

along the route authorized for access to each construction site.

c. Under no circumstance will Contractor personnel be permitted to drive their individually owned vehicles to any construction site on the airport. All vehicles must be parked in the area designated for employee parking and out of secured airport property.

d. In addition to the inspection and cleanup required at the end of each shift, the Contractor is responsible for the immediate cleanup of any debris generated along the construction site access route(s) as a result of construction related traffic or operations whether or not created by Contractor personnel.

**103-5.3 MATERIAL SUPPLIERS.** All material suppliers, subcontractors and visitors to the work site are obligated to follow the same safety and security operating procedures as the Contractor. All material suppliers shall make their deliveries using the same access points and routes as the Contractor and shall be advised of the appropriate delivery procedures at the time the materials order is placed. The Contractor shall not use the Airport address for any delivery but shall use the street address appropriate to the location of the entrance of the work site. If it is not practical to conform to the vehicle identification requirements of Section 103-5.1 and the safety and security operations program requirements of Section 103-2.2, the Contractor shall be prepared to escort all suppliers, subcontractors and visitors while they are on the airport.

**103-5.4 PERSONNEL IDENTIFICATION.** All employees, agents, vendors, invitees, etc. of the Contractor or subcontractors requiring access to the construction site shall, conform to the Security Program.

## GENERAL SAFETY REQUIREMENTS

**103-6.1** All Contractor vehicles that are authorized to operate on the airport outside of the designated construction area limits or haul routes as defined herein shall display in full view above the vehicle a flashing amber (yellow) dome-type light or a three-foot by three-foot, or larger, orange and white checkerboard flag, each checkerboard color being one-foot square. Vehicles must be under control of a Contractor mobile (two-way) radio operator (flagmen) monitoring the Airport frequency. Vehicle operators must be vigilant for conflict with any aircraft and give way to any operating aircraft.

All Contractor vehicles that are required to operate outside of the construction area limits as defined herein and cross active runways, taxiways, aprons, or runway approach clear zones shall do so under the direct control of a flagman who is monitoring the Airport frequency. Flagmen and two-way radios shall be furnished by the Contractor. Flagmen shall be instructed in the use of two-way radios prior to use. All aircraft traffic on runways, taxiways and aprons shall have priority over Contractor's traffic.

Construction vehicles not in use for extended periods during the work day, or during nights and weekends (nonwork periods) shall be parked away from active runways, taxiways, and aprons in designated vehicle marshalling areas.

**103-6.2** In order to protect all aircraft traffic, aviation related businesses, terminal apron areas, etc. from potential damage caused by foreign object debris (FOD) generated by construction activities, the Contractor shall provide a vacuum truck as required at the startup of construction to daily vacuum all pavements affected by construction. The vacuum truck shall remain on-site for the duration of the project and shall be available at the discretion of the Owner to vacuum pavement areas adjacent to the construction areas to ensure no FOD is present on pavements within 500 feet of any construction area. Protecting the aircraft, airport tenants, users, public, etc. against FOD is a critical safety issue therefore

the cost of the vacuum truck will be included in the cost established for this specification item.

## **CONSTRUCTION CONTROL**

**103-7.1** A primary and alternate responsible Contractor's representative shall be designated by the Contractor. The Contractor's representatives shall be available locally on a 24-hour basis. Names of the primary and alternate, including phone number, shall be made available to the Construction Manager by the Contractor. The Contractor shall insure that the names and phone numbers are kept current and made available to the Construction Manager.

## **CONSTRUCTION TECHNIQUES**

**103-8.1** Construction shall be planned and conducted throughout this project in such a manner as to allow the maintenance of completely safe airport operations. Every effort shall be made to reduce the impact of construction activity on overall airport operations. To this end the Contractor's activities shall be conducted in such a manner so as to preclude, except where absolutely required, open excavations, trenches, ditches and above ground obstacles such as booms on cranes or obstacle markers such as wooden saw horses. The primary responsibility for assuring that the safest possible construction techniques are followed rests with the Contractor Safety and Security Officer (CSSO).

## **METHOD OF MEASUREMENT**

**103-9.1** Based upon the contract lump sum price for "Safety and Security" partial payments will be allowed as follows:

- a. A negotiated percentage based on documentable costs will be paid with the first pay request. The amount will be negotiated between the Owner, Contractor and Engineer prior to the first pay request.
- b. Each subsequent pay request will include equal payments derived as follows: 100% less the negotiated initial payment divided by the total duration of the project in months.
- c. The final equal installment will be paid after final inspection and delivery of all project close-out materials as outlined in the Contract Documents is complete.

The Owner reserves the right to adjust the above payment schedule if agreed to by the Owner, Contractor and Engineer. Should a payment adjustment occur, the remaining Safety and Security cost will be adjusted such that it is paid in equal installments spread over the remainder of the project duration.

The item of Safety and Security shall be measured as a lump sum item when required and furnished for the life of the Contract.

## **BASIS OF PAYMENT**

**103-10.** Payment shall be made for airport safety and security measures for personnel or materials related to this specification item and incidentally required to satisfy the specified objective(s) under item C-103, Safety and Security. This compensation shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item.



Payment shall be made under:

Item C-103-1                      Safety and Security - per lump sum

In the event the contract completion date is extended or additional work is added to the project, no additional payment will be made for safety and security unless otherwise addressed by change order.

**END OF ITEM C-103**

## ITEM C-104 PROJECT STAKEOUT AND AS-BUILT SURVEY

### DESCRIPTION

**104-1.1 GENERAL.** Under this item, the Contractor shall do all necessary surveying and project stakeout required to construct all elements of the Project as shown on the Contract Drawings and specified in the Specifications. This shall include but not be limited to stakeout, layout and elevations for excavations, embankments, pavements, structures, forms and appurtenances as shown and required, consistent with the current practices and shall be performed by a Commonwealth of Virginia licensed professional land surveyor. The stakeout survey shall proceed immediately following the Notice to Proceed or as soon as authorized by the Construction Manager in accordance with the phasing of the construction and shall be expeditiously progressed to completion in a manner and at a rate satisfactory to the Construction Manager and/or Engineer. The Contractor shall keep the Construction Manager fully informed as to the progress of the stakeout survey.

All survey work shall be provided under the direction of a Commonwealth of Virginia licensed professional land surveyor or approved equal.

**104-1.2 SITE CONDITIONS.** At least fifteen (15) working days prior to commencing construction operations in an area which may involve crossing existing underground utility facilities, the Contractor shall notify the RPR of each underground utility facility shown on the plans.

When coordinated through the RPR, the FAA will assist the Contractor in locating existing FAA cables, the Contractor shall provide marking paint, and flags or stakes for identification of existing underground systems.

The existence of any known buried wires, conduits, junction boxes, ducts, or other facilities is shown in a general way only. It will be the duty of the Contractor, to visit the site and make an exact determination of the existence and location of any facilities prior to commencing any work.

Immediately prior to the initiation of excavation, the Contractors shall engage the service of a utility locating service (via local "One Call" or similar services) and marking of utilities on-site. Periodic updates to the locating and marking shall be performed as required to maintain the locations or to expand the work area.

The Contractor will be responsible for making the exact determination of the location and condition of such facilities and any costs shall be paid for locating services by the Contractor if fees apply. In all areas where existing system are in close proximity (within 10') to new installations, the Contractor shall soft dig (pothole/vacuum excavation/hand-dig) to identify the exact location of existing infrastructure. Contractor shall soft dig six (6) feet on either side of the marked obstruction (12' total width) on 250' intervals or at mid points between manholes/handholes. The contractor shall identify (locations and depth) and protect existing systems prior to the initiation of any new installation.

## MATERIALS

**104-2.1** All instruments, equipment, stakes and any other material necessary to perform the work satisfactorily shall be provided by the Contractor.

All stakes used shall be of a type approved by the Construction Manager. It shall be the Contractor's responsibility to maintain these stakes in their proper position and location at all times.

## CONSTRUCTION METHODS

The Contractor may obtain from the RPR, copies of contract drawings from previous construction projects, examine these drawings, and verify at the site the location of below grade utilities in the vicinity of work performed under this Contract.

**104-3.1 DAMAGE TO EXISTING SYSTEMS.** Should the Contractor come into contact with and/or damage existing underground system including but not limited to, sanitary sewers, drainage, gas, electrical utilities, airfield electrical system, FAA systems, aviation fuel, communications lines, domestic water, etc. the Contractor shall immediately stop work until the extent of the damage can be assessed. Any damage caused to any existing utilities by the Contractor shall be repaired to the satisfaction of the owner at no cost to the utility owner.

If damage has occurred, the Contractor shall coordinate repairs with the respective agency. Items damaged by the Contractor's workers or equipment or his subcontractors shall be repaired or replaced immediately at the Contractor's expense.

If FAA systems are damaged, the Contractor shall notify the FAA immediately. The Contractor shall purchase the specific materials required by the FAA to completely repair the damaged system. If the FAA deems the system "sensitive" the FAA may elect to perform the repair with internal FAA Tech Ops staff with the assistance of the Contractor's staff. The Contractor shall provide all required material to the FAA staff.

If the damage to existing system is extensive, the Contractor may be required to relocate crews to alternate work areas on site to allow productive project work while the repairs to the damaged system are being performed. If the relocation of work is required as the result of damage caused by the Contractor, the Contractor shall relocate to an alternate work site and shall be entitled to no compensation.

**104-3.2 INTERRUPTIONS.** Interruptions of existing drainage systems may be necessary during construction. The Contractor shall provide reliable connections to provide temporary continuity of flow during construction where required.

The Contractor shall trim trees, brush and other interfering objects, not inconsistent with the Contract Drawings, from survey lines in advance of all survey work to permit accurate and unimpeded work by his stakeout survey crews.

**104-3.3 STAKEOUT.** The exact position of all work shall be established from control points, baseline transit points or other points of similar nature which are shown on the Contract Drawings and/or modified by the Engineer. Prior to any layout of works to be constructed, the Contractor shall verify the location and accuracy of all control points provided in the plans. Any error, apparent discrepancy or absence in or of data shown or required for accurately accomplishing the stakeout survey shall be referred to the

Construction Manager and Engineer for interpretation or furnishing when such is observed or required.

The Contractor shall, at a minimum, place two offset stakes or references at 100-foot intervals at each centerline station and at such intermediate locations as the Construction Manager may direct. From computations and measurements made by the Contractor, these stakes shall be clearly and legibly marked with the correct centerline station number, offset and cut or fill so as to permit the establishment of the exact centerline location and elevation during construction. If markings become faded or blurred for any reason, the markings shall be restored by the Contractor at the request of the Construction Manager. He shall locate and place all cut, fill, slope, fine grade or other stakes and points, as the engineer may direct, for the proper progress of the work. All control points shall be properly guarded and flagged for easy identification.

Drainage structures shall be staked out by the Contractor at the locations and elevations shown on the Contract Drawings or specified by the Engineer thru the Construction Manager.

Alignments for installation of visual barriers (i.e., orange safety fence) along the runway/taxiway safety and object free areas shall be staked out by the Contractor at the locations shown on the Contract Drawings or as directed by the Construction Manager.

Reference points, baselines, stakes and benchmarks for stockpiles shall be established by the Contractor.

The Contractor shall be responsible for the accuracy of his work and shall maintain all reference points, stakes, etc., throughout the life of the Contract. Damaged or destroyed points, benchmarks or stakes, or any reference points made inaccessible by the progress of the construction, shall be replaced or transferred by the Contractor. Any of the above points which may be destroyed or damaged shall be transferred by the Contractor before they are damaged or destroyed. All control points shall be referenced by ties to acceptable objects and recorded. Any alterations or revisions in the ties shall be so noted and the information furnished to the Construction Manager immediately. All stakeout survey work shall be referenced to the centerlines shown on the Contract Drawings. All computations necessary to establish the exact position of the work from control points shall be made and preserved by the Contractor. All computations, survey notes and other records shall be made available to the Construction Manager and/or Engineer upon request and shall become the property of the Owner and delivered to the Construction Manager no later than the date of acceptance of the Contract.

The Contractor shall furnish, at his expense, all horizontal and vertical control, all staking and layout of construction work called for on the plans. The Construction Manager, Engineer and Owner shall not be responsible for such work. However, the Owner and Engineer reserve the right to check all said lines, grades, and measurements with their appointed surveyor. Should the Owner's surveyor detect errors in said lines, grades, and measurements, the contractor shall pay for all said surveying costs and subsequent surveying costs performed to verify correction of errors found in said lines, grades and measurements. Definition of an error shall be a discrepancy of 1/4" or more. In the case of a discrepancy between the technical specifications and this defined tolerance, the more severe tolerance shall govern.

During the progress of the construction work, the Contractor will be required to furnish all of the surveying and stakeout incidental to the proper location by line and grade for each phase of the work. For paving and any other operation requiring extreme accuracy, the Contractor will re-stake with pins or other acceptable hubs located directly adjacent to the work at a spacing directed by the Construction Manager.

Any existing stakes, iron pins, survey monuments or other markers defining property lines which may be disturbed during construction shall be properly tied into fixed reference points before being disturbed and accurately reset in their proper position upon completion of the work.

Just prior to completion of the Contract, the Contractor shall reestablish, if necessary, and retie all control points as permanently as possible and to the satisfaction of the Construction Manager.

**104-3.2** The Contractor shall be required to submit cross sectional data to the Engineer prior to the Contractor submittal of the monthly application for payment so that the Engineer can verify the quantities of various earthwork and materials volumes for payment. All cross sectional data provided at any time will be in AutoCAD V2016 or higher format only. No other formats will be accepted. If the data is submitted in another format other than AutoCAD, no earthwork or other materials volumes will be calculated and approved for payment. The earthwork shall include, but not be limited to, unclassified excavation, embankment, new or existing subbase courses, new or existing base courses, sand/asphalt subgrade, topsoil, etc.

**104-3.5 AS-BUILT SURVEY.** Upon completion of the work, after Substantial Completion and before Final Acceptance, the Contractor shall supply to the Construction Manager a complete as-built survey of the entire limits of the project, including repair limits. All survey points, including horizontal and vertical control, property corners, section corner and reference (hereinafter referred to as "survey point") shall be clearly marked and referenced prior to construction. These survey points must be sufficiently referenced so that they can be reestablished after construction if they are disturbed. All survey data shall be state plane coordinates, NAD 83 datum. Elevations shall be provided in NGVD 88 datum unless otherwise noted by the Construction Manager.

This as-built survey will be a complete physical features survey of the entire project site. If any work is done outside the limits of construction for any reason, this limit of survey will be increased to include this area plus 10 feet. This survey shall be certified by a Virginia Licensed Professional Land Surveyor as meeting the minimum Technical Standards for topographic surveys as set forth in Virginia code. The survey data must be supplied as a signed and sealed drawing (11" x 17" maximum size) at a minimum scale of 1"=50' and be electronically submitted in AutoCAD V2016 or later on electronic media. Signed and sealed copies of all field notes, sketches and calculations must be submitted concurrently with the as-built survey. Larger scale details shall be provided to clarify any complicated or complex areas. A separate point database file shall be electronically submitted in TXT or ASCII format, with each point on a single row with comma delimited columns with data ordered as follows: point number, northing, easting, elevation, and description.

The as-built survey is to be supplied to the Construction Manager for review and approval not more than thirty (30) calendar days after substantial completion for the project has been given. If the acceptable as-built survey is not supplied within the required time, the Owner reserves the right to perform the required survey and bill the Contractor for this work.

## **METHOD OF MEASUREMENT**

**104-4.1** Payment will be made at the lump sum price bid for this item.

## **BASIS OF PAYMENT**

**104-5.1** Verification of existing underground utilities shall be paid for at the contract unit price for Project Survey and Stakeout. Prior the initiation of construction, the Contractor shall be responsible for the verification of existing conditions, including airfield drainage investigation and airfield circuit investigation to determine active and inactive circuits. The Project Survey and Stakeout pay item shall be inclusive of all cost and efforts to locate, identify, trace, expose and protect the existing systems and cabling that are located with the area of work. This item also includes the preparation of a detailed report of the investigations depicting all the locations of existing utilities in the project area. The Contractor shall coordinate all locating efforts with the RPR & FAA, local utilities, and others deemed necessary. This pay item shall be inclusive of marking and staking of all existing conditions that impact or are potentially in conflict with the proposed installation. In all areas where existing system are in close proximity to new installations, the Contractor shall soft dig (Pothole) to identify the exact location of existing infrastructure or cabling on the intervals identified above. The Contractor shall identify locations and depth of these conditions prior to the initiation of any new installation. This price shall be full compensation for furnishing all materials, equipment, subcontracts, preparation of report and for all preparation, maintenance and installation of these materials, and for all labor, equipment, tools, and incidentals necessary to complete this item.

Seventy-five percent (75%) of this item will be paid based on the percentage of work paid for a month vs. the total project cost. The remaining twenty-five percent (25%) will be paid after the as-built survey has been given the Construction Manager and approved.

This item will not be increased or decreased based on changes to the total contract amount.

Payment will be made under:

Item C-104-1	Project Stakeout and As-Built Survey – per lump sum
--------------	---

In the event the contract completion date is extended or additional work is added to the project, no additional payment will be made for the survey and stakeout unless otherwise addressed by change order.

## **END OF ITEM C-104**

Page Intentionally Blank

## Item C-105 Mobilization

**105-1 Description.** This item of work shall consist of, but is not limited to, work and operations necessary for the movement of personnel, equipment, material and supplies to and from the project site for work on the project except as provided in the contract as separate pay items.

**105-2 Mobilization limit.** Mobilization shall be limited to 10 percent of the total project cost.

**105-3 Posted notices.** Prior to commencement of construction activities, the Contractor must post the following documents in a prominent and accessible place where they may be easily viewed by all employees of the prime Contractor and by all employees of subcontractors engaged by the prime Contractor: Equal Employment Opportunity (EEO) Poster “Equal Employment Opportunity is the Law” in accordance with the Office of Federal Contract Compliance Programs Executive Order 11246, as amended; Davis Bacon Wage Poster (WH 1321) - DOL “Notice to All Employees” Poster; and Applicable Davis-Bacon Wage Rate Determination. These notices must remain posted until final acceptance of the work by the Owner.

**105-4 Engineer/RPR field office.** The Contractor shall provide dedicated space for the use of the field RPR and inspectors, as a field office for the duration of the project. This space shall be located conveniently near the construction and shall be separate from any space used by the Contractor. The Contractor shall furnish water, sanitary facilities, heat, air conditioning, and electricity in accordance with local building codes.

**105-5 Permit Fees.** The Contractor shall pay all permit fees required by Albemarle County and/or other applicable state agencies.

## METHOD OF MEASUREMENT

**105-5 Basis of measurement and payment.** Based upon the contract lump sum price for “Mobilization” partial payments will be allowed as follows:

- a. With first pay request, 25%.
- b. When 25% or more of the original contract is earned, an additional 25%.
- c. When 50% or more of the original contract is earned, an additional 40%.
- d. After Final Inspection, Staging area clean-up and delivery of all Project Closeout materials as required by Section 90, paragraph 90-11, *Contractor Final Project Documentation*, the final 10%.
- e. No additional payment will be made for demobilization and remobilization due to weather related shutdowns, suspensions of work, or for other mobilization activities.

## BASIS OF PAYMENT

**105-6 Payment will be made under:**

Item C-105-6.1	Mobilization – per lump sum
Item C-105-6.2	Permit Fees – per lump sum



## **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Office of Federal Contract Compliance Programs (OFCCP)

Executive Order 11246, as amended

EEOC-P/E-1 – Equal Employment Opportunity is the Law Poster

United States Department of Labor, Wage and Hour Division (WHD)

WH 1321 – Employee Rights under the Davis-Bacon Act Poster

**END OF ITEM C-105**

## ITEM C-106 TEMPORARY CONSTRUCTION ITEMS

### DESCRIPTION

**106-1.1** This item consists of furnishing all labor, materials and equipment for temporary construction items necessary for the safe and proper execution of work and not otherwise included in other contract bid items. The Contractor will be expected to supply and utilize the items listed below and other items contained in the plans and specifications. Temporary construction items to be provided include, but are not limited to the following: flaggers, steel plates for temporary covering of excavations and structures as required, temporary excavation shoring, construction barricades, signage coverings, test pitting, and men and equipment as needed to keep all areas free of debris.

### MATERIALS AND PLACEMENT

**106-2.1 CONSTRUCTION BARRICADES.** Construction barricades shall be constructed in accordance with the details shown in the plans and shall be placed in accordance with the Work Area Plans and Phasing Notes. The Contractor shall furnish, place, and maintain temporary barricades as required and/or as directed by the Construction Manager. Contractor must provide enough barricades as required to segregate work areas from active aircraft and/or vehicular operations. Barricades shall be low mass and easily collapsible. Also, the Contractor shall furnish suitable and sufficient direction and warning signs, battery powered red warning lights (at least 10 candelas for steady burning) of the type approved by the Construction Manager.

Lights, barricades, and other protective devices shall be relocated as required to conform to airport operations. The Contractor will not be paid separately for furnishing, placing, relocating and maintaining barricades, lights, danger signals, etc., and shall make due allowance in the bid, in the applicable items of work, to cover such non-productive costs.

The Contractor shall provide an on-site representative who is available 24-hours per day, seven days per week to maintain barricade lights as well as alignment of the barricades that may be affected by aircraft or ground service equipment operations.

**106-2.2 PORTABLE FLOODLIGHTING.** Portable floodlighting shall be provided, as required, for construction which occurs during nighttime operations. The Contractor shall provide sufficient units so that all work areas are illuminated to a level of 5 horizontal foot-candles. Back-up floodlighting shall be provided on-site. The lighting levels shall be calculated and measured in accordance with the current standards of the Illumination Engineering Society.

**106-2.3 CRANE MATS.** Crane mats of adequate size and thickness shall be furnished as necessary to cover temporary excavations for safety purposes. Mats shall be securely fastened down and shall be adequate to safely support any anticipated loadings by errant tugs or other ground service equipment operating on the apron.

**106-2.4 HAUL ROUTES.** Contractor haul routes have been designated on the Plans. It shall be the Contractor's responsibility to inspect existing roads so that he may assess their condition properly. If the Contractor deems necessary, he shall be responsible for supplying materials to maintain the haul roads and drainage devices to adequately support his construction equipment. New haul roads shall be constructed of suitable materials, and will be maintained by the Contractor. All pipe culverts, headwalls, structures and

miscellaneous items under or adjacent to the haul routes shall be inspected prior to construction and restored to their pre-construction condition if damaged, at the Contractor's expense. The Contractor shall make repairs as directed by the Construction Manager.

Haul roads shall be restored to their pre-construction condition after construction is completed, unless otherwise noted on the Plans.

**106-2.5 MAINTENANCE OF TRAFFIC ON PUBLIC ROADWAYS.** Contractor shall conform to local and/or state requirements when using public roadways and/or where the project's construction traffic enters and exits public roadways. When required by local/state regulations, the Contractor shall secure required permitting for the use of public roadways and/or procure the appropriate signage indicating hauling routes, construction entrance locations, or locations where trucks will be entering/existing roadways to and from Airport property.

Construction signage to be placed shall be at physical locations where traffic will enter/exit public roads in each direction. Contractor shall also be required to place signage at defined distances away from egress points to alert public traffic of upcoming construction access on either side of that entrance. Signage to be installed shall be per VDOT standards, with locations approved by the Construction Manager prior to construction. At no time shall the Contractor enter public roadways without signage being in place and approved. Signage shall be accompanied by strobe lighting as required by VDOT standards during dusk/dawn/night construction. Lighting shall remain operational during construction. All signage, and necessary lighting, marking, etc. shall be maintained throughout construction and shall be removed upon completion of the Contract.

**106-2.6 MECHANICAL VACUUM SWEEPERS.** Cleaning and maintenance of all paved areas by the use of vacuum type mechanical sweepers will be required as directed by the Construction Manager or Airport Operations. The use of a power broom may be allowed if it can remove all debris from the pavement surface without damage to surrounding area (i.e. parked aircraft or hangar buildings) by the throwing of rocks. The removal of dirt, sand, rocks and other debris from all active pavement areas within the work site or as used for haul routes is of the highest important and must be done continuously during construction. Also, dust control by the use of water trucks or other methods will be as directed by the Construction Manager throughout the project duration. Contractor shall submit list of proposed equipment to the Construction Manager prior to commencement of work.

**106-2.7 RADIOS.** The Contractor is required to provide and maintain one (1) radio for the Construction Manager and as many radios as required for the Contractor, including his on-site crews and subcontractors; and to monitor the CTAF/Unicom frequency of the Airport at the crossings indicated on the drawings with a minimum of two (2) spare radios and four (4) spare batteries. Radio contact (listening only) is required at all times while the Contractor has personnel and equipment on the project site, inside the secured Air Operations Area (AOA) and as directed by the Construction Manager. Use of radios shall be as directed by the Construction Manager.

The frequency utilized for two-way radio transmissions shall be selected by the Contractor and approved by the Construction Manager but shall not conflict with or overlay any of the Airport's radio frequencies. The Contractor's personnel required to have radio equipment shall, at minimum, include the Project Superintendent, gate guards, and others who may be working in a separate and remote area. Sufficient numbers of radios shall be deployed to allow each remote area to have direction communications ability.

**106-2.8 VEHICLE FLAGS AND IDENTIFICATION MARKINGS.** Contractor shall outfit construction vehicles and equipment accessing the secure AOA with checkered flags as detailed in the Plans. Contractor shall also be required to provide company name/identification of vehicles accessing the

secure area with door placards and/or magnets on both sides. Identification shall be as required by current Charlottesville Albemarle Airport (CHO) regulations at the time of the Bid.

**106-2.9 EQUIPMENT.** Red lights shall be placed on stationary equipment, materials, and other obstructions in areas which may be critical to aircraft ground movement as required. Hazardous areas, in which no part of an aircraft may enter, are indicated by use of barricades with alternate orange and white markings. These barricades are supplemented with orange flags a minimum of 20 by 20 inches square and made and installed so that they are always in the extended position and properly oriented. For nighttime use, the barricades shall be supplemented with red lights having a constant burn. The intensity of the lights and spacing for barricades, flags, and lights must be such to adequately define and delineate the hazardous area.

**106-2.10 SIGN AND LIGHT COVERS.** The Contractor shall provide a secured opaque material covering existing guidance signs and runway/taxiway lights which correspond with the required runway and taxiway closures as shown the phasing plans. The Contractor shall submit to the Construction Manager, for approval, materials to be used prior to installation.

**106-2.11 OTHER MISCELLANEOUS ITEMS.** Any other items not listed herein but which are associated directly or indirectly with temporary construction related work shall, by reference, be included in the requirements of this specification. No additional payment will be made for any temporary construction related item not specifically listed herein. The Contractor shall be responsible for providing any and all items necessary to ensure a safe, secure and functioning project construction site.

## **SPECIAL CONSTRUCTION PERSONNEL**

**106-3.1 SAFETY PERSONNEL/GATE GUARDS.** Safety personnel/gate guards shall be trained and approved by CHO prior to commencing construction. Only approved personnel shall act as safety personnel/gate guards. Training of Contractor personnel shall be as required at the time of the Bid or Notice to Proceed (NTP). When they occur, Contractor shall be required to adhere to security practices and modifications as dictated by the Transportation Security Administration (TSA), CHO, or other regulatory agency. Modification to security practices in place shall be as directed by the Construction Manager.

**106-3.2 FLAGMEN.** Flagmen shall be provided, as necessary, to control the Contractor's traffic during the prosecution of work (i.e., into and out of the secured AOA or along public traffic routes). All Contractor vehicles or equipment that are required to cross active airfield pavement only shall do so under the direct control of a competent flagman equipped with an aviation band radio monitoring the appropriate ATC frequency and with the approval of the Construction Manager.

## **METHOD OF MEASUREMENT**

**106-4.1** Based upon the contract lump sum price for "Temporary Construction Items" partial payments will be allowed as follows:

- a. The first payment of 25 percent will be included in the first progress estimate following the initiation of construction work.
- b. Each subsequent pay request will include equal payments derived as follows: 100 percent less the initial payment divided by the total duration of the project in months.

c. The final equal installment will be paid after final inspection and delivery of all project close-out materials as outlined in the Contract Documents is complete.

The Owner reserves the right to adjust the above payment schedule if agreed to by the Owner, Contractor and Engineer. Should a payment adjustment occur, the remaining Maintenance of Traffic and Temporary Construction Items cost will be adjusted such that it is paid in equal installments spread over the remainder of the project duration.

### **BASIS OF PAYMENT**

Payment will be made under:

Item C-106-1	Temporary Construction Items (Maintenance & Protection of Traffic) – per lump sum
--------------	---

### **END OF ITEM C-106**

## Item C-110 Method of Estimating Percentage of Material Within Specification Limits (PWL)

**110-1 General.** When the specifications provide for acceptance of material based on the method of estimating percentage of material within specification limits (PWL), the PWL will be determined in accordance with this section. All test results for a lot will be analyzed statistically to determine the total estimated percent of the lot that is within specification limits. The PWL is computed using the sample average ( $\bar{X}$ ) and sample standard deviation ( $S_n$ ) of the specified number ( $n$ ) of sublots for the lot and the specification tolerance limits,  $L$  for lower and  $U$  for upper, for the particular acceptance parameter. From these values, the respective Quality index,  $Q_L$  for Lower Quality Index and/or  $Q_U$  for Upper Quality Index, is computed and the PWL for the lot for the specified  $n$  is determined from Table 1. All specification limits specified in the technical sections shall be absolute values. Test results used in the calculations shall be to the significant figure given in the test procedure.

There is some degree of uncertainty (risk) in the measurement for acceptance because only a small fraction of production material (the population) is sampled and tested. This uncertainty exists because all portions of the production material have the same probability to be randomly sampled. The Contractor's risk is the probability that material produced at the acceptable quality level is rejected or subjected to a pay adjustment. The Owner's risk is the probability that material produced at the rejectable quality level is accepted.

It is the intent of this section to inform the Contractor that, in order to consistently offset the Contractor's risk for material evaluated, production quality (using population average and population standard deviation) must be maintained at the acceptable quality specified or higher. In all cases, it is the responsibility of the Contractor to produce at quality levels that will meet the specified acceptance criteria when sampled and tested at the frequencies specified.

**110-2 Method for computing PWL.** The computational sequence for computing PWL is as follows:

- a. Divide the lot into  $n$  sublots in accordance with the acceptance requirements of the specification.
- b. Locate the random sampling position within the subplot in accordance with the requirements of the specification.
- c. Make a measurement at each location, or take a test portion and make the measurement on the test portion in accordance with the testing requirements of the specification.
- d. Find the sample average ( $\bar{X}$ ) for all subplot test values within the lot by using the following formula:

$$\bar{X} = (x_1 + x_2 + x_3 + \dots + x_n) / n$$

Where:  $\bar{X}$  = Sample average of all subplot test values within a lot

$x_1, x_2, \dots, x_n$  = Individual subplot test values

$n$  = Number of subplot test values

- e. Find the sample standard deviation ( $S_n$ ) by use of the following formula:

$$S_n = [(d_1^2 + d_2^2 + d_3^2 + \dots + d_n^2)/(n-1)]^{1/2}$$

Where:  $S_n$  = Sample standard deviation of the number of subplot test values in the set

$d_1, d_2, \dots, d_n$  = Deviations of the individual subplot test values  $x_1, x_2, \dots$  from the average value  $\bar{X}$

that is:  $d_1 = (x_1 - \bar{X}), d_2 = (x_2 - \bar{X}) \dots d_n = (x_n - \bar{X})$

$n$  = Number of subplot test values

**f.** For single sided specification limits (i.e.,  $L$  only), compute the Lower Quality Index  $Q_L$  by use of the following formula:

$$Q_L = (\bar{X} - L) / S_n$$

Where:  $L$  = specification lower tolerance limit

Estimate the percentage of material within limits (PWL) by entering Table 1 with  $Q_L$ , using the column appropriate to the total number ( $n$ ) of measurements. If the value of  $Q_L$  falls between values shown on the table, use the next higher value of PWL.

**g.** For double-sided specification limits (i.e.,  $L$  and  $U$ ), compute the Quality Indexes  $Q_L$  and  $Q_U$  by use of the following formulas:

$$Q_L = (\bar{X} - L) / S_n$$

and

$$Q_U = (U - \bar{X}) / S_n$$

Where:  $L$  and  $U$  = specification lower and upper tolerance limits

Estimate the percentage of material between the lower ( $L$ ) and upper ( $U$ ) tolerance limits (PWL) by entering Table 1 separately with  $Q_L$  and  $Q_U$ , using the column appropriate to the total number ( $n$ ) of measurements, and determining the percent of material above  $P_L$  and percent of material below  $P_U$  for each tolerance limit. If the values of  $Q_L$  fall between values shown on the table, use the next higher value of  $P_L$  or  $P_U$ . Determine the PWL by use of the following formula:

$$PWL = (P_U + P_L) - 100$$

Where:  $P_L$  = percent within lower specification limit

$P_U$  = percent within upper specification limit

## EXAMPLE OF PWL CALCULATION

**Project:** Example Project

**Test Item:** Item P-401, Lot A.

### A. PWL Determination for Mat Density.

#### 1. Density of four random cores taken from Lot A.

A-1 = 96.60

A-2 = 97.55

A-3 = 99.30

A-4 = 98.35

$n = 4$

**2. Calculate average density for the lot.**

$$X = (x_1 + x_2 + x_3 + \dots + x_n) / n$$

$$X = (96.60 + 97.55 + 99.30 + 98.35) / 4$$

$$X = 97.95\% \text{ density}$$

**3. Calculate the standard deviation for the lot.**

$$S_n = [((96.60 - 97.95)^2 + (97.55 - 97.95)^2 + (99.30 - 97.95)^2 + (98.35 - 97.95)^2) / (4 - 1)]^{1/2}$$

$$S_n = [(1.82 + 0.16 + 1.82 + 0.16) / 3]^{1/2}$$

$$S_n = 1.15$$

**4. Calculate the Lower Quality Index  $Q_L$  for the lot. ( $L=96.3$ )**

$$Q_L = (X - L) / S_n$$

$$Q_L = (97.95 - 96.30) / 1.15$$

$$Q_L = 1.4348$$

**5. Determine PWL by entering Table 1 with  $Q_L = 1.44$  and  $n = 4$ .**

$$PWL = 98$$

**B. PWL Determination for Air Voids.****1. Air Voids of four random samples taken from Lot A.**

$$A-1 = 5.00$$

$$A-2 = 3.74$$

$$A-3 = 2.30$$

$$A-4 = 3.25$$

**2. Calculate the average air voids for the lot.**

$$X = (x_1 + x_2 + x_3 + \dots + x_n) / n$$

$$X = (5.00 + 3.74 + 2.30 + 3.25) / 4$$

$$X = 3.57\%$$

**3. Calculate the standard deviation  $S_n$  for the lot.**

$$S_n = [((3.57 - 5.00)^2 + (3.57 - 3.74)^2 + (3.57 - 2.30)^2 + (3.57 - 3.25)^2) / (4 - 1)]^{1/2}$$

$$S_n = [(2.04 + 0.03 + 1.62 + 0.10) / 3]^{1/2}$$

$$S_n = 1.12$$

**4. Calculate the Lower Quality Index  $Q_L$  for the lot. ( $L = 2.0$ )**

$$Q_L = (X - L) / S_n$$

$$Q_L = (3.57 - 2.00) / 1.12$$

$$Q_L = 1.3992$$

**5. Determine  $P_L$  by entering Table 1 with  $Q_L = 1.41$  and  $n = 4$ .**

$$P_L = 97$$

**6. Calculate the Upper Quality Index  $Q_U$  for the lot. ( $U = 5.0$ )**

$$Q_U = (U - X) / S_n$$

$$Q_U = (5.00 - 3.57) / 1.12$$



$$Q_U = 1.2702$$

7. Determine  $P_U$  by entering Table 1 with  $Q_U = 1.29$  and  $n = 4$ .

$$P_U = 93$$

8. Calculate Air Voids PWL

$$PWL = (P_L + P_U) - 100$$

$$PWL = (97 + 93) - 100 = 90$$

### EXAMPLE OF OUTLIER CALCULATION (REFERENCE ASTM E178)

**Project:** Example Project

**Test Item:** Item P-401, Lot A.

#### A. Outlier Determination for Mat Density.

1. Density of four random cores taken from Lot A arranged in descending order.

$$A-3 = 99.30$$

$$A-4 = 98.35$$

$$A-2 = 97.55$$

$$A-1 = 96.60$$

2. From ASTM E178, Table 1, for  $n=4$  an upper 5% significance level, the critical value for test criterion = 1.463.

3. Use average density, standard deviation, and test criterion value to evaluate density measurements.

a. For measurements greater than the average:

If (measurement - average)/(standard deviation) is less than test criterion, then the measurement is not considered an outlier.

For A-3, check if  $(99.30 - 97.95) / 1.15$  is greater than 1.463.

Since 1.174 is less than 1.463, the value is not an outlier.

b. For measurements less than the average:

If (average - measurement)/(standard deviation) is less than test criterion, then the measurement is not considered an outlier.

For A-1, check if  $(97.95 - 96.60) / 1.15$  is greater than 1.463.

Since 1.135 is less than 1.463, the value is not an outlier.

**Note:** In this example, a measurement would be considered an outlier if the density were:

$$\text{Greater than } (97.95 + 1.463 \times 1.15) = 99.63\%$$

OR

$$\text{less than } (97.95 - 1.463 \times 1.15) = 96.27\%.$$

**Table 1. Table for Estimating Percent of Lot Within Limits (PWL)**

Percent Within Limits ( $P_L$ and $P_U$ )	Positive Values of Q ( $Q_L$ and $Q_U$ )							
	n=3	n=4	n=5	n=6	n=7	n=8	n=9	n=10
99	1.1541	1.4700	1.6714	1.8008	1.8888	1.9520	1.9994	2.0362
98	1.1524	1.4400	1.6016	1.6982	1.7612	1.8053	1.8379	1.8630
97	1.1496	1.4100	1.5427	1.6181	1.6661	1.6993	1.7235	1.7420
96	1.1456	1.3800	1.4897	1.5497	1.5871	1.6127	1.6313	1.6454
95	1.1405	1.3500	1.4407	1.4887	1.5181	1.5381	1.5525	1.5635
94	1.1342	1.3200	1.3946	1.4329	1.4561	1.4717	1.4829	1.4914
93	1.1269	1.2900	1.3508	1.3810	1.3991	1.4112	1.4199	1.4265
92	1.1184	1.2600	1.3088	1.3323	1.3461	1.3554	1.3620	1.3670
91	1.1089	1.2300	1.2683	1.2860	1.2964	1.3032	1.3081	1.3118
90	1.0982	1.2000	1.2290	1.2419	1.2492	1.2541	1.2576	1.2602
89	1.0864	1.1700	1.1909	1.1995	1.2043	1.2075	1.2098	1.2115
88	1.0736	1.1400	1.1537	1.1587	1.1613	1.1630	1.1643	1.1653
87	1.0597	1.1100	1.1173	1.1192	1.1199	1.1204	1.1208	1.1212
86	1.0448	1.0800	1.0817	1.0808	1.0800	1.0794	1.0791	1.0789
85	1.0288	1.0500	1.0467	1.0435	1.0413	1.0399	1.0389	1.0382
84	1.0119	1.0200	1.0124	1.0071	1.0037	1.0015	1.0000	0.9990
83	0.9939	0.9900	0.9785	0.9715	0.9671	0.9643	0.9624	0.9610
82	0.9749	0.9600	0.9452	0.9367	0.9315	0.9281	0.9258	0.9241
81	0.9550	0.9300	0.9123	0.9025	0.8966	0.8928	0.8901	0.8882
80	0.9342	0.9000	0.8799	0.8690	0.8625	0.8583	0.8554	0.8533
79	0.9124	0.8700	0.8478	0.8360	0.8291	0.8245	0.8214	0.8192
78	0.8897	0.8400	0.8160	0.8036	0.7962	0.7915	0.7882	0.7858
77	0.8662	0.8100	0.7846	0.7716	0.7640	0.7590	0.7556	0.7531
76	0.8417	0.7800	0.7535	0.7401	0.7322	0.7271	0.7236	0.7211
75	0.8165	0.7500	0.7226	0.7089	0.7009	0.6958	0.6922	0.6896
74	0.7904	0.7200	0.6921	0.6781	0.6701	0.6649	0.6613	0.6587
73	0.7636	0.6900	0.6617	0.6477	0.6396	0.6344	0.6308	0.6282
72	0.7360	0.6600	0.6316	0.6176	0.6095	0.6044	0.6008	0.5982
71	0.7077	0.6300	0.6016	0.5878	0.5798	0.5747	0.5712	0.5686
70	0.6787	0.6000	0.5719	0.5582	0.5504	0.5454	0.5419	0.5394
69	0.6490	0.5700	0.5423	0.5290	0.5213	0.5164	0.5130	0.5105
68	0.6187	0.5400	0.5129	0.4999	0.4924	0.4877	0.4844	0.4820
67	0.5878	0.5100	0.4836	0.4710	0.4638	0.4592	0.4560	0.4537
66	0.5563	0.4800	0.4545	0.4424	0.4355	0.4310	0.4280	0.4257
65	0.5242	0.4500	0.4255	0.4139	0.4073	0.4030	0.4001	0.3980
64	0.4916	0.4200	0.3967	0.3856	0.3793	0.3753	0.3725	0.3705
63	0.4586	0.3900	0.3679	0.3575	0.3515	0.3477	0.3451	0.3432
62	0.4251	0.3600	0.3392	0.3295	0.3239	0.3203	0.3179	0.3161
61	0.3911	0.3300	0.3107	0.3016	0.2964	0.2931	0.2908	0.2892
60	0.3568	0.3000	0.2822	0.2738	0.2691	0.2660	0.2639	0.2624
59	0.3222	0.2700	0.2537	0.2461	0.2418	0.2391	0.2372	0.2358
58	0.2872	0.2400	0.2254	0.2186	0.2147	0.2122	0.2105	0.2093
57	0.2519	0.2100	0.1971	0.1911	0.1877	0.1855	0.1840	0.1829
56	0.2164	0.1800	0.1688	0.1636	0.1607	0.1588	0.1575	0.1566
55	0.1806	0.1500	0.1406	0.1363	0.1338	0.1322	0.1312	0.1304
54	0.1447	0.1200	0.1125	0.1090	0.1070	0.1057	0.1049	0.1042
53	0.1087	0.0900	0.0843	0.0817	0.0802	0.0793	0.0786	0.0781
52	0.0725	0.0600	0.0562	0.0544	0.0534	0.0528	0.0524	0.0521
51	0.0363	0.0300	0.0281	0.0272	0.0267	0.0264	0.0262	0.0260
50	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

Percent Within Limits (P <sub>L</sub> and P <sub>U</sub> )	Negative Values of Q (Q <sub>L</sub> and Q <sub>U</sub> )							
	n=3	n=4	n=5	n=6	n=7	n=8	n=9	n=10
49	-0.0363	-0.0300	-0.0281	-0.0272	-0.0267	-0.0264	-0.0262	-0.0260
48	-0.0725	-0.0600	-0.0562	-0.0544	-0.0534	-0.0528	-0.0524	-0.0521
47	-0.1087	-0.0900	-0.0843	-0.0817	-0.0802	-0.0793	-0.0786	-0.0781
46	-0.1447	-0.1200	-0.1125	-0.1090	-0.1070	-0.1057	-0.1049	-0.1042
45	-0.1806	-0.1500	-0.1406	-0.1363	-0.1338	-0.1322	-0.1312	-0.1304
44	-0.2164	-0.1800	-0.1688	-0.1636	-0.1607	-0.1588	-0.1575	-0.1566
43	-0.2519	-0.2100	-0.1971	-0.1911	-0.1877	-0.1855	-0.1840	-0.1829
42	-0.2872	-0.2400	-0.2254	-0.2186	-0.2147	-0.2122	-0.2105	-0.2093
41	-0.3222	-0.2700	-0.2537	-0.2461	-0.2418	-0.2391	-0.2372	-0.2358
40	-0.3568	-0.3000	-0.2822	-0.2738	-0.2691	-0.2660	-0.2639	-0.2624
39	-0.3911	-0.3300	-0.3107	-0.3016	-0.2964	-0.2931	-0.2908	-0.2892
38	-0.4251	-0.3600	-0.3392	-0.3295	-0.3239	-0.3203	-0.3179	-0.3161
37	-0.4586	-0.3900	-0.3679	-0.3575	-0.3515	-0.3477	-0.3451	-0.3432
36	-0.4916	-0.4200	-0.3967	-0.3856	-0.3793	-0.3753	-0.3725	-0.3705
35	-0.5242	-0.4500	-0.4255	-0.4139	-0.4073	-0.4030	-0.4001	-0.3980
34	-0.5563	-0.4800	-0.4545	-0.4424	-0.4355	-0.4310	-0.4280	-0.4257
33	-0.5878	-0.5100	-0.4836	-0.4710	-0.4638	-0.4592	-0.4560	-0.4537
32	-0.6187	-0.5400	-0.5129	-0.4999	-0.4924	-0.4877	-0.4844	-0.4820
31	-0.6490	-0.5700	-0.5423	-0.5290	-0.5213	-0.5164	-0.5130	-0.5105
30	-0.6787	-0.6000	-0.5719	-0.5582	-0.5504	-0.5454	-0.5419	-0.5394
29	-0.7077	-0.6300	-0.6016	-0.5878	-0.5798	-0.5747	-0.5712	-0.5686
28	-0.7360	-0.6600	-0.6316	-0.6176	-0.6095	-0.6044	-0.6008	-0.5982
27	-0.7636	-0.6900	-0.6617	-0.6477	-0.6396	-0.6344	-0.6308	-0.6282
26	-0.7904	-0.7200	-0.6921	-0.6781	-0.6701	-0.6649	-0.6613	-0.6587
25	-0.8165	-0.7500	-0.7226	-0.7089	-0.7009	-0.6958	-0.6922	-0.6896
24	-0.8417	-0.7800	-0.7535	-0.7401	-0.7322	-0.7271	-0.7236	-0.7211
23	-0.8662	-0.8100	-0.7846	-0.7716	-0.7640	-0.7590	-0.7556	-0.7531
22	-0.8897	-0.8400	-0.8160	-0.8036	-0.7962	-0.7915	-0.7882	-0.7858
21	-0.9124	-0.8700	-0.8478	-0.8360	-0.8291	-0.8245	-0.8214	-0.8192
20	-0.9342	-0.9000	-0.8799	-0.8690	-0.8625	-0.8583	-0.8554	-0.8533
19	-0.9550	-0.9300	-0.9123	-0.9025	-0.8966	-0.8928	-0.8901	-0.8882
18	-0.9749	-0.9600	-0.9452	-0.9367	-0.9315	-0.9281	-0.9258	-0.9241
17	-0.9939	-0.9900	-0.9785	-0.9715	-0.9671	-0.9643	-0.9624	-0.9610
16	-1.0119	-1.0200	-1.0124	-1.0071	-1.0037	-1.0015	-1.0000	-0.9990
15	-1.0288	-1.0500	-1.0467	-1.0435	-1.0413	-1.0399	-1.0389	-1.0382
14	-1.0448	-1.0800	-1.0817	-1.0808	-1.0800	-1.0794	-1.0791	-1.0789
13	-1.0597	-1.1100	-1.1173	-1.1192	-1.1199	-1.1204	-1.1208	-1.1212
12	-1.0736	-1.1400	-1.1537	-1.1587	-1.1613	-1.1630	-1.1643	-1.1653
11	-1.0864	-1.1700	-1.1909	-1.1995	-1.2043	-1.2075	-1.2098	-1.2115
10	-1.0982	-1.2000	-1.2290	-1.2419	-1.2492	-1.2541	-1.2576	-1.2602
9	-1.1089	-1.2300	-1.2683	-1.2860	-1.2964	-1.3032	-1.3081	-1.3118
8	-1.1184	-1.2600	-1.3088	-1.3323	-1.3461	-1.3554	-1.3620	-1.3670
7	-1.1269	-1.2900	-1.3508	-1.3810	-1.3991	-1.4112	-1.4199	-1.4265
6	-1.1342	-1.3200	-1.3946	-1.4329	-1.4561	-1.4717	-1.4829	-1.4914
5	-1.1405	-1.3500	-1.4407	-1.4887	-1.5181	-1.5381	-1.5525	-1.5635
4	-1.1456	-1.3800	-1.4897	-1.5497	-1.5871	-1.6127	-1.6313	-1.6454
3	-1.1496	-1.4100	-1.5427	-1.6181	-1.6661	-1.6993	-1.7235	-1.7420
2	-1.1524	-1.4400	-1.6016	-1.6982	-1.7612	-1.8053	-1.8379	-1.8630
1	-1.1541	-1.4700	-1.6714	-1.8008	-1.8888	-1.9520	-1.9994	-2.0362

## **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM E178                      Standard Practice for Dealing with Outlying Observations

**END OF ITEM C-110**

Page Intentionally Blank

## **ITEM P-100 AIRPORT UTILITIES GENERAL PROVISIONS**

### **GENERAL CONSTRUCTION REQUIREMENTS**

**100-1.1 SITE CONDITIONS.** At least fifteen (15) working days prior to commencing construction operations in an area which may involve crossing existing underground utility facilities, the Contractor shall notify the RPR of each underground utility facility shown on the plans.

When coordinated through the RPR, the FAA will assist the Contractor in locating existing FAA cables, the Contractor shall provide marking paint, and flags or stakes for identification of existing underground systems.

The existence of any known buried wires, conduits, junction boxes, ducts, or other facilities is shown in a general way only. It will be the duty of the Contractor, to visit the site and make an exact determination of the existence and location of any facilities prior to commencing any work.

Immediately prior to the initiation of excavation, the Contractors shall engage the service of a utility locating service (via local "One Call" or similar services) and marking of utilities on-site. Periodic updates to the locating and marking shall be performed as required to maintain the locations or to expand the work area.

The Contractor will be responsible for making the exact determination of the location and condition of such facilities and any costs shall be paid for locating services by the Contractor if fees apply. In all areas where existing system are in close proximity (within 10') to new installations, the Contractor shall soft dig (pothole/vacuum excavation/hand-dig) to identify the exact location of existing infrastructure. Contractor shall soft dig six (6) feet on either side of the marked obstruction (12' total width) on 250' intervals or at mid points between manholes/handholes. The contractor shall identify (locations and depth) and protect existing systems prior to the initiation of any new installation.

### **ALL DATA SHALL BE RECORDED ON AS-BUILT DOCUMENTS**

The Contractor may obtain from the RPR, copies of contract drawings from previous construction projects, examine these drawings, and verify at the site the location of below grade utilities in the vicinity of work performed under this Contract.

**100-1.2 DAMAGE TO EXISTING SYSTEMS.** Should the Contractor come into contact with and/or damage existing underground system including but not limited to, sanitary sewers, drainage, gas, electrical utilities, airfield electrical system, FAA systems, aviation fuel, communications lines, domestic water, etc. the Contractor shall immediately stop work until the extent of the damage can be assessed. Any damage caused to any existing utilities by the Contractor shall be repaired to the satisfaction of the owner at no cost to the utility owner.

If damage has occurred, the Contractor shall coordinate repairs with the respective agency. Items damaged by the Contractor's workers or equipment or his subcontractors shall be repaired or replaced immediately at the Contractor's expense.

If FAA systems are damaged, the Contractor shall notify the FAA immediately. The Contractor shall

purchase the specific materials required by the FAA to completely repair the damaged system. If the FAA deems the system “sensitive” the FAA may elect to perform the repair with internal FAA Tech Ops staff with the assistance of the Contractor’s staff. The Contractor shall provide all required material to the FAA staff.

If the damage to existing system is extensive, the Contractor may be required to relocate crews to alternate work areas on site to allow productive project work while the repairs to the damaged system are being performed. If the relocation of work is required as the result of damage caused by the Contractor, the Contractor shall relocate to an alternate work site and shall be entitled to no compensation.

**100-1.3 INTERRUPTIONS.** Interruptions of existing drainage systems may be necessary during construction. The Contractor shall provide reliable connections to provide temporary continuity of flow during construction where required.

### **METHOD OF MEASUREMENT**

**100-2.1** Measurement for Verification of Existing Underground Utilities shall be incidental to C-104 Project Stakeout and As-Built Survey

### **BASIS OF PAYMENT**

**100-3.1** No separate payment shall be made for Verification of Existing Underground Utilities. It shall be considered incidental to the pay item C-104-1 Project Stakeout and As-Built Survey.

### **END OF ITEM P-100**

## Item P-101 Preparation/Removal of Existing Pavements

### DESCRIPTION

**101-1** This item shall consist of preparation of existing pavement surfaces for overlay, surface treatments, removal of existing pavement, and other miscellaneous items. The work shall be accomplished in accordance with these specifications and the applicable plans.

### EQUIPMENT AND MATERIALS

**101-2** All equipment and materials shall be specified here and in the following paragraphs or approved by the Resident Project Representative (RPR). The equipment shall not cause damage to the pavement to remain in place.

### CONSTRUCTION

#### 101-3.1 Removal of existing pavement.

The Contractor's removal operation shall be controlled to not damage adjacent pavement structure, and base material, cables, utility ducts, pipelines, or drainage structures which are to remain under the pavement.

No pavement removal shall be started until the work has been surveyed by the Contractor and the RPR has obtained from the Contractor, the survey notes of the elevations and measurements of the ground surface. The Contractor and RPR shall agree that the original ground lines shown on the original survey are accurate or agree to any adjustments made to the original ground lines.

The Contractor's removal operation shall be controlled to not damage adjacent pavement structure, and base material, cables, utility ducts, pipelines, or drainage structures which are to remain under the pavement. Contractor shall remove pavement to a depth one (1) inch above subgrade or below this elevation in areas where removal of the existing pavement exposes a surface that is below the new subgrade elevation. Top of subgrade elevation is defined in the typical sections, boring logs, and core photos. The exposed surface defined by one inch above subgrade shall be prepared in accordance with Item P-152.

**a. Concrete pavement removal.** Full depth saw cuts shall be made perpendicular to the slab surface. The Contractor shall saw through the full depth of the slab including any dowels at the joint, removing the pavement and installing new dowels as shown on the plans and per the specifications. Where the perimeter of the removal limits is not located on the joint and there are no dowels present, the perimeter shall be saw cut the full depth of the pavement. The pavement inside the saw cut shall be removed by methods which will not cause distress in the pavement which is to remain in place, such as adjacent concrete panels. All concrete pavement removed shall be disposed of off the Airport property. If the material is to be wasted on the airport site, it shall be reduced to a maximum size of [—]. Concrete slabs that are damaged by under breaking shall be repaired or removed and replaced as directed by the RPR.

The edge of existing concrete pavement against which new pavement abuts shall be protected from damage at all times. Spall and underbreak repair shall be in accordance with the plans. Any underlaying



material that is to remain in place, shall be recompact and/or replaced as shown on the plans. Adjacent areas damaged during repair shall be repaired or replaced at the Contractor's expense.

**b. Asphalt pavement removal.** Asphalt pavement to be removed shall be cut to the full depth of the asphalt pavement around the perimeter of the area to be removed. **All asphalt pavement removed shall be disposed of off the Airport property.** If the material is to be ~~[- wasted on the airport site -]~~ ~~[- incorporated into embankment -]~~, it shall be ~~[- broken to a maximum size of [ ] inches (mm). -]~~ ~~[- meet the following gradation: [ ] -]~~.

**c. Repair or removal of Base, Subbase, and/or Subgrade.** All failed material including surface, base course, subbase course, and subgrade shall be removed and repaired as shown on the plans or as directed by the RPR. Materials and methods of construction shall comply with the applicable sections of these specifications. Any damage caused by Contractor's removal process shall be repaired at the Contractor's expense.

**101-3.2 Preparation of joints and cracks prior to overlay/surface treatment.** **Not Used.** ~~Remove all vegetation and debris from cracks to a minimum depth of 1 inch (25 mm). If extensive vegetation exists, treat the specific area with a concentrated solution of a water based herbicide approved by the RPR. Fill all cracks greater than 1/4 inch (6 mm) wide with a crack sealant [ per ASTM D6690 ]. The crack sealant, preparation, and application shall be compatible with the surface treatment/overlay to be used. To minimize contamination of the asphalt with the crack sealant, underfill the crack sealant a minimum of 1/8 inch (3 mm), not to exceed 1/4 inch (6 mm). Any excess joint or crack sealer shall be removed from the pavement surface.~~

**101-3.3 Removal of Foreign Substances/contaminates prior to remarking.** Removal of foreign substances/contaminates from existing pavement that will affect the bond of the new treatment shall consist of removal of rubber, fuel spills, oil, crack sealer, at least 90% of paint, and other foreign substances from the surface of the pavement. Areas that require removal are designated on the plans and as directed by the RPR in the field during construction.

High-pressure water may be used. ~~If chemicals are used, they shall comply with the state's environmental protection regulations.~~ Removal methods used shall not cause major damage to the pavement, or to any structure or utility within or adjacent to the work area. Major damage is defined as changing the properties of the pavement, removal of asphalt causing the aggregate to ravel, or removing pavement over 1/8 inch (3 mm) deep. If it is deemed by the RPR that damage to the existing pavement is caused by operational error, such as permitting the application method to dwell in one location for too long, the Contractor shall repair the damaged area without compensation and as directed by the RPR.

Removal of foreign substances shall not proceed until approved by the RPR. Water used for high-pressure water equipment shall be provided by the Contractor at the Contractor's expense. No material shall be deposited on the pavement shoulders. All wastes shall be disposed of in areas indicated in this specification or shown on the plans.

#### **101-3.4 Concrete spall or failed asphaltic concrete pavement repair.**

**a. Repair of concrete spalls in areas to be overlaid with asphalt.** **Not Required.** ~~The Contractor shall repair all spalled concrete as shown on the plans or as directed by the RPR. The perimeter of the repair shall be saw cut a minimum of 2 inches (50 mm) outside the affected area and 2 inches (50 mm) deep. The deteriorated material shall be removed to a depth where the existing material is firm or cannot be easily removed with a geologist pick. The removed area shall be filled with asphalt mixture with aggregate sized appropriately for the depth of the patch. The material shall be compacted with equipment approved by the RPR until the material is dense and no movement or marks are visible. The material shall not be placed in lifts over 4 inches (100 mm) in depth. This method of repair applies only to pavement to be overlaid.~~

**b. Asphalt pavement repair.** **Not Required.** The Contractor shall repair all spalled concrete as shown on the plans or as directed by the RPR. The failed areas shall be removed as specified in paragraph 101-3.1b. All failed material including surface, base course, subbase course, and subgrade shall be removed. Materials and methods of construction shall comply with the applicable sections of these specifications.

**101-3.5 Cold milling.** **Not Required.** Milling shall be performed with a power-operated milling machine or grinder, capable of producing a uniform finished surface. The milling machine or grinder shall operate without tearing or gouging the underlying surface. The milling machine or grinder shall be equipped with grade and slope controls, and a positive means of dust control. All millings shall be removed and disposed [~~off Airport property~~] [~~in areas designated on the plans~~]. If the Contractor mills or grinds deeper or wider than the plans specify, the Contractor shall replace the material removed with new material at the Contractor's Expense.

**a. Patching.** **Not Required.** The milling machine shall be capable of cutting a vertical edge without chipping or spalling the edges of the remaining pavement and it shall have a positive method of controlling the depth of cut. The RPR shall layout the area to be milled with a straightedge in increments of 1 foot (30 cm) widths. The area to be milled shall cover only the failed area. Any excessive area that is milled because the Contractor doesn't have the appropriate milling machine, or areas that are damaged because of his negligence, shall be repaired by the Contractor at the Contractor's Expense.

**b. Profiling, grade correction, or surface correction.** **Not Required.** The milling machine shall have a minimum width of [~~7~~] feet ([~~2~~] m) and it shall be equipped with electronic grade control devices that will cut the surface to the grade specified. The tolerances shall be maintained within +0 inch and -1/4 inch (+0 mm and -6mm) of the specified grade. The machine must cut vertical edges and have a positive method of dust control. The machine must have the ability to [~~windrow the millings or cuttings~~] [~~remove the millings or cuttings from the pavement and load them into a truck~~]. All millings shall be removed and disposed of [~~off the airport~~] [~~in areas designated on the plans~~].

**c. Clean-up.** **Not Required.** The Contractor shall sweep the milled surface daily and immediately after the milling until all residual materials are removed from the pavement surface. Prior to paving, the Contractor shall wet down the milled pavement and thoroughly sweep and/or blow the surface to remove loose residual material. Waste materials shall be collected and removed from the pavement surface and adjacent areas by sweeping or vacuuming. Waste materials shall be removed and disposed [~~off Airport property~~] [~~in areas designated on the plans~~].

**101-3.6. Preparation of asphalt pavement surfaces prior to surface treatment.** **Not Required.** Existing asphalt pavements to be treated with a surface treatment shall be prepared as follows:

**a.** Patch asphalt pavement surfaces that have been softened by petroleum derivatives or have failed due to any other cause. Remove damaged pavement to the full depth of the damage and replace with new asphalt pavement similar to that of the existing pavement in accordance with paragraph 101-3.4b.

**b.** Repair joints and cracks in accordance with paragraph 101-3.2.

**c.** Remove oil or grease that has not penetrated the asphalt pavement by scrubbing with a detergent and washing thoroughly with clean water. After cleaning, treat these areas with an oil spot primer. [ ]

**d.** Clean pavement surface immediately prior to placing the surface treatment so that it is free of dust, dirt, grease, vegetation, oil or any type of objectionable surface film.

**101-3.7 Maintenance.** The Contractor shall perform all maintenance work necessary to keep the pavement in a satisfactory condition until the full section is complete and accepted by the RPR. The surface shall be kept clean and free from foreign material. The pavement shall be properly drained at all times. If cleaning is necessary or if the pavement becomes disturbed, any work repairs necessary shall be performed at the Contractor's expense.

**101-3.8 Preparation of Joints in Rigid Pavement prior to resealing.** Prior to application of sealant material, clean and dry the joints of all scale, dirt, dust, old sealant, curing compound, moisture and other foreign matter. The Contractor shall demonstrate, in the presence of the RPR, that the method used cleans the joint and does not damage the joint.

**101-3.8.1 Removal of Existing Joint Sealant.** All existing joint sealants will be removed by plowing or use of hand tools. Any remaining sealant and or debris will be removed by use of wire brushes or other tools as necessary. Resaw joints removing no more than 1/16 inch (2 mm) from each joint face. Immediately after sawing, flush out joint with water and other tools as necessary to completely remove the slurry.

**101-3.8.2 Cleaning prior to sealing.** Immediately before sealing, joints shall be cleaned by removing any remaining laitance and other foreign material. Allow sufficient time to dry out joints prior to sealing. Joint surfaces will be surface-dry prior to installation of sealant.

**101-3.8.3 Joint sealant.** Joint material and installation will be in accordance with Item P-605.

**101-3.9 Preparation of Cracks in Flexible Pavement prior to sealing.** **Not Required.** ~~Prior to application of sealant material, clean and dry the joints of all scale, dirt, dust, old sealant, curing compound, moisture and other foreign matter. The Contractor shall demonstrate, in the presence of the RPR, that the method used cleans the cracks and does not damage the pavement.~~

**101-3.9.1 Preparation of Crack.** **Not Required.** ~~Widen crack with [ router ] [ random crack saw ] by removing a minimum of 1/16 inch (2 mm) from each side of crack. Immediately before sealing, cracks will be blown out with a hot air lance combined with oil and water free compressed air.~~

**101-3.9.2 Removal of Existing Crack Sealant.** **Not Required.** ~~Existing sealants will be removed by [ routing ] [ random crack saw ]. Following [ routing ] [ sawing ] any remaining debris will be removed by use of a hot lance combined with oil and water free compressed air.~~

**101-3.9.3 Crack Sealant.** **Not Required.** ~~Crack sealant material and installation will be in accordance with [ Item P-605 ].~~

#### **101-3.9.4 Removal of Pipe and other Buried Structures.**

**a. Removal of Existing Pipe Material.** Remove the types of pipe as indicated on the plans. The pipe material shall be legally disposed of off-site in a timely manner following removal. Trenches shall be backfilled with material equal to or better in quality than adjacent embankment. Trenches under paved areas must be compacted to 95% of ASTM D1557 or D698.

**b. Removal of Inlets/Manholes.** Where indicated on the plans or as directed by the RPR, inlets and/or manholes shall be removed and legally disposed of off-site in a timely fashion after removal. Excavations after removal shall be backfilled with material equal or better in quality than adjacent embankment. When under paved areas must be compacted to 95% of ASTM D1557 or D698.

### **METHOD OF MEASUREMENT**

**101-4.1 Pavement removal.** The unit of measurement for pavement removal shall be the number of square yards (square meters) removed by the Contractor. Any pavement removed outside the limits of removal because the pavement was damaged by negligence on the part of the Contractor shall not be included in the measurement for payment. No direct measurement or payment shall be made for saw cutting. Saw cutting shall be incidental to pavement removal. Dowel bar installation shall be incidental to pavement removal.

**101-4.2 Removal of Foreign Substances/contaminates.** **No separate measurement will be made. The work covered by this section shall be considered a subsidiary obligation of the Contractor and covered**

~~under the other contract items. The unit of measurement for foreign Substances/contaminates removal shall be the square foot (meter).~~

**101-4.3 Removal of Pipe and other Buried Structures.** The unit of measurement for removal of pipe and other buried structures will be made at the contract unit price for each completed and accepted item. This price shall be full compensation for all labor, equipment, tools, and incidentals necessary to complete this item in accordance with paragraph 101-3.9.4.

### **BASIS OF PAYMENT**

**101-5.1 Payment.** Payment shall be made at contract unit price for the unit of measurement as specified above. This price shall be full compensation for furnishing all materials and for all preparation, hauling, and placing of the material and for all labor, equipment, tools, and incidentals necessary to complete this item.

Item P 101-5.1	Concrete Pavement Removal – per square yard
Item P 101-5.2	Asphalt Pavement Removal – per square yard
Item P-101-5.3	Removal of Storm Pipe (36-inch and less) – per linear foot
Item P-101-5.4	Removal of Inlet – per each

### **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Advisory Circulars (AC)

AC 150/5380-6	Guidelines and Procedures for Maintenance of Airport Pavements.
---------------	---

ASTM International (ASTM)

ASTM D6690	Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements
------------	--

### **END OF ITEM P-101**

Page Intentionally Blank

## Item P-152 Excavation, Subgrade, and Embankment

### DESCRIPTION

**152-1.1** This item covers excavation, disposal, placement, and compaction of all materials within the limits of the work required to construct safety areas, runways, taxiways, aprons, and intermediate areas as well as other areas for drainage, building construction, parking, or other purposes in accordance with these specifications and in conformity to the dimensions and typical sections shown on the plans.

**152-1.2 Classification.** All material excavated shall be classified as defined below:

- a. **Unclassified excavation.** Unclassified excavation shall consist of the excavation and disposal of all material, regardless of its nature.
- b. **Drainage excavation.** Drainage excavation shall consist of all excavation made for the primary purpose of drainage and includes drainage ditches, such as intercepting, inlet or outlet ditches; temporary levee construction; or any other type as shown on the plans.

**152-1.3 Unsuitable excavation.** Unsuitable material shall be disposed in designated waste areas as shown on the plans. Materials containing vegetable or organic matter, such as muck, peat, organic silt, or sod shall be considered unsuitable for use in embankment construction. Material suitable for topsoil may be used on the embankment slope when approved by the RPR.

### CONSTRUCTION METHODS

**152-2.1 General.** Before beginning excavation, grading, and embankment operations in any area, the area shall be cleared or cleared and grubbed in accordance with Item P-151.

The suitability of material to be placed in embankments shall be subject to approval by the RPR. All unsuitable material shall be disposed of in waste areas as shown on the plans. All waste areas shall be graded to allow positive drainage of the area and adjacent areas. The surface elevation of waste areas shall be specified on the plans or approved by the RPR.

When the Contractor's excavating operations encounter artifacts of historical or archaeological significance, the operations shall be temporarily discontinued and the RPR notified per Section 70, paragraph 70-20. At the direction of the RPR, the Contractor shall excavate the site in such a manner as to preserve the artifacts encountered and allow for their removal. Such excavation will be paid for as extra work.

Areas outside the limits of the pavement areas where the top layer of soil has become compacted by hauling or other Contractor activities shall be scarified and disked to a depth of 4 inches (100 mm), to loosen and pulverize the soil. Stones or rock fragments larger than 4 inches (100 mm) in their greatest dimension will not be permitted in the top 6 inches (150 mm) of the subgrade.

If it is necessary to interrupt existing surface drainage, sewers or under-drainage, conduits, utilities, or similar underground structures, the Contractor shall be responsible for and shall take all necessary precautions to preserve them or provide temporary services. When such facilities are encountered, the Contractor shall notify the RPR, who shall arrange for their removal if necessary. The Contractor, at their own expense, shall satisfactorily repair or pay the cost of all damage to such facilities or structures that may result from any of the Contractor's operations during the period of the contract.

**a. Blasting.** Blasting shall not be allowed.

**152-2.2 Excavation.** No excavation shall be started until the work has been staked out by the Contractor and the RPR has obtained from the Contractor, the survey notes of the elevations and measurements of the ground surface. The Contractor and RPR shall agree that the original ground lines shown on the original topographic mapping are accurate, or agree to any adjustments made to the original ground lines.

Digital terrain model (DTM) files of the existing surfaces, finished surfaces and other various surfaces were used to develop the design plans.

Volumetric quantities were calculated by comparing DTM files of the applicable design surfaces and generating Triangle Volume Reports. Electronic copies of DTM files and a paper copy of the original topographic map will be issued to the successful bidder.

Existing grades on the design cross sections or DTM's, where they do not match the locations of actual spot elevations shown on the topographic map, were developed by computer interpolation from those spot elevations. Prior to disturbing original grade, Contractor shall verify the accuracy of the existing ground surface by verifying spot elevations at the same locations where original field survey data was obtained as indicated on the topographic map. Contractor shall recognize that, due to the interpolation process, the actual ground surface at any particular location may differ somewhat from the interpolated surface shown on the design cross sections or obtained from the DTM's. Contractor's verification of original ground surface, however, shall be limited to verification of spot elevations as indicated herein, and no adjustments will be made to the original ground surface unless the Contractor demonstrates that spot elevations shown are incorrect. For this purpose, spot elevations which are within 0.1 foot (30 mm) of the stated elevations for ground surfaces, or within 0.04 foot (12 mm) for hard surfaces (pavements, buildings, foundations, structures, etc.) shall be considered "no change". Only deviations in excess of these will be considered for adjustment of the original ground surface. If Contractor's verification identifies discrepancies in the topographic map, Contractor shall notify the RPR in writing at least two weeks before disturbance of existing grade to allow sufficient time to verify the submitted information and make adjustments to the design cross sections or DTM's. Disturbance of existing grade in any area shall constitute acceptance by the Contractor of the accuracy of the original elevations shown on the topographic map for that area.

~~All areas to be excavated shall be stripped of vegetation and topsoil. Topsoil shall be stockpiled for future use in areas designated on the plans or by the RPR. All suitable excavated material shall be used in the formation of embankment, subgrade, or other purposes as shown on the plans. All unsuitable material shall be disposed of as shown on the plans.~~

The grade shall be maintained so that the surface is well drained at all times.

When the volume of the excavation exceeds that required to construct the embankments to the grades as indicated on the plans, the excess shall be used to grade the areas of ultimate development or disposed as directed by the RPR. When the volume of excavation is not sufficient for constructing the embankments to the grades indicated, the deficiency shall be obtained from borrow areas.

**a. Selective grading.** When selective grading is indicated on the plans, the more suitable material designated by the RPR shall be used in constructing the embankment or in capping the pavement subgrade. If, at the time of excavation, it is not possible to place this material in its final location, it shall be stockpiled in approved areas until it can be placed. The more suitable material shall then be placed and compacted as specified. Selective grading shall be considered incidental to the work involved. The cost of stockpiling and placing the material shall be included in the various pay items of work involved.

**b. Undercutting.** Rock, shale, hardpan, loose rock, boulders, or other material unsatisfactory for safety areas, subgrades, roads, shoulders, or any areas intended for turf shall be excavated to a minimum depth of 12 inches (300 mm) below the subgrade or to the depth specified by the RPR. Muck, peat,

matted roots, or other yielding material, unsatisfactory for subgrade foundation, shall be removed to the depth specified. Unsuitable materials shall be disposed off the airport. The cost is incidental to this item. The excavated area shall be backfilled with suitable material obtained from the grading operations or borrow areas and compacted to specified densities. The necessary backfill will constitute a part of the embankment. Where rock cuts are made, backfill with select material. Any pockets created in the rock surface shall be drained in accordance with the details shown on the plans. Undercutting will be paid as unclassified excavation.

**c. Over-break.** Over-break, including slides, is that portion of any material displaced or loosened beyond the finished work as planned or authorized by the RPR. All over-break shall be graded or removed by the Contractor and disposed of as directed by the RPR. The RPR shall determine if the displacement of such material was unavoidable and their own decision shall be final. Payment will not be made for the removal and disposal of over-break that the RPR determines as avoidable. Unavoidable over-break will be classified as "Unclassified Excavation."

**d. Removal of utilities.** The removal of existing structures and utilities required to permit the orderly progress of work will be accomplished by the Contractor as indicated on the plans. All existing foundations shall be excavated at least 2 feet below the top of subgrade or as indicated on the plans, and the material disposed of as directed by the RPR. All foundations thus excavated shall be backfilled with suitable material and compacted as specified for embankment or as shown on the plans.

**152-2.3 Borrow excavation.** There are no borrow sources within the boundaries of the airport property. The Contractor shall locate and obtain borrow sources, subject to the approval of the RPR. The Contractor shall notify the RPR at least 15 days prior to beginning the excavation so necessary measurements and tests can be made by the RPR. All borrow pits shall be opened to expose the various strata of acceptable material to allow obtaining a uniform product. Borrow areas shall be drained and left in a neat, presentable condition with all slopes dressed uniformly. Borrow areas shall not create a hazardous wildlife attractant.

**152-2.4 Drainage excavation.** Drainage excavation shall consist of excavating drainage ditches including intercepting, inlet, or outlet ditches; or other types as shown on the plans. The work shall be performed in sequence with the other construction. Ditches shall be constructed prior to starting adjacent excavation operations. All satisfactory material shall be placed in embankment fills; unsuitable material shall be placed in designated waste areas or as directed by the RPR. All necessary work shall be performed true to final line, elevation, and cross-section. The Contractor shall maintain ditches constructed on the project to the required cross-section and shall keep them free of debris or obstructions until the project is accepted.

**152-2.5 Preparation of cut areas or areas where existing pavement has been removed.** In those areas on which a subbase or base course is to be placed, the top 12 inches of subgrade shall be compacted to not less than 100% of maximum density for non-cohesive soils, and 95% of maximum density for cohesive soils as determined by ASTM D1557. As used in this specification, "non-cohesive" shall mean those soils having a plasticity index (PI) of less than 3 as determined by ASTM D4318.

**152-2.6 Preparation of embankment area.** ~~Not Used. All sod and vegetative matter shall be removed from the surface upon which the embankment is to be placed. The cleared surface shall be broken up by plowing or scarifying to a minimum depth of 6 inches (150 mm) and shall then be compacted per paragraph 152-2.10.~~

~~Sloped surfaces steeper than one (1) vertical to four (4) horizontal shall be plowed, stepped, benched, or broken up so that the fill material will bond with the existing material. When the subgrade is part fill and part excavation or natural ground, the excavated or natural ground portion shall be scarified to a depth of 12 inches (300 mm) and compacted as specified for the adjacent fill.~~

~~No direct payment shall be made for the work performed under this section. The necessary clearing and grubbing and the quantity of excavation removed will be paid for under the respective items of work.~~



**152-2.7 Control Strip.** The first half-day of construction of subgrade and/or embankment shall be considered as a control strip for the Contractor to demonstrate, in the presence of the RPR, that the materials, equipment, and construction processes meet the requirements of this specification. The sequence and manner of rolling necessary to obtain specified density requirements shall be determined. The maximum compacted thickness may be increased to a maximum of 12 inches (300 mm) upon the Contractor's demonstration that approved equipment and operations will uniformly compact the lift to the specified density. The RPR must witness this demonstration and approve the lift thickness prior to full production.

Control strips that do not meet specification requirements shall be reworked, re-compacted, or removed and replaced at the Contractor's expense. Full operations shall not begin until the control strip has been accepted by the RPR. The Contractor shall use the same equipment, materials, and construction methods for the remainder of construction, unless adjustments made by the Contractor are approved in advance by the RPR.

**152-2.8 Formation of embankments.** ~~Not Used.~~ The material shall be constructed in lifts as established in the control strip, but not less than 6 inches (150 mm) nor more than 12 inches (300 mm) of compacted thickness.

~~When more than one lift is required to establish the layer thickness shown on the plans, the construction procedure described here shall apply to each lift. No lift shall be covered by subsequent lifts until tests verify that compaction requirements have been met. The Contractor shall rework, re-compact and retest any material placed which does not meet the specifications.~~

~~The lifts shall be placed, to produce a soil structure as shown on the typical cross section or as directed by the RPR. Materials such as brush, hedge, roots, stumps, grass and other organic matter, shall not be incorporated or buried in the embankment.~~

~~Earthwork operations shall be suspended at any time when satisfactory results cannot be obtained due to rain, freezing, or other unsatisfactory weather conditions in the field. Frozen material shall not be placed in the embankment nor shall embankment be placed upon frozen material. Material shall not be placed on surfaces that are muddy, frozen, or contain frost. The Contractor shall drag, blade, or slope the embankment to provide surface drainage at all times.~~

~~The material in each lift shall be within  $\pm 2\%$  of optimum moisture content before rolling to obtain the prescribed compaction. The material shall be moistened or aerated as necessary to achieve a uniform moisture content throughout the lift. Natural drying may be accelerated by blending in dry material or manipulation alone to increase the rate of evaporation.~~

~~The Contractor shall make the necessary corrections and adjustments in methods, materials or moisture content to achieve the specified embankment density.~~

~~The contractor will take samples of excavated materials which will be used in embankment for testing and develop a Moisture Density Relations of Soils Report (Proctor) in accordance with ASTM D1557. A new Proctor shall be developed for each soil type based on visual classification.~~

~~Density tests will be taken by the contractor for every 3,000 square yards of compacted embankment for each lift which is required to be compacted, or other appropriate frequencies as determined by the RPR.~~

~~If the material has greater than 30% retained on the 3/4 inch (19.0 mm) sieve, follow AASHTO T-180 Annex Correction of maximum dry density and optimum moisture for oversized particles.~~

~~Rolling operations shall be continued until the embankment is compacted to not less than 100% of maximum density for non-cohesive soils, and 95% of maximum density for cohesive soils as determined by ASTM D1557. Under all areas to be paved, the embankments shall be compacted to a depth of 12 inches and to a density of not less than 100% percent of the maximum density as determined by ASTM~~

~~D1557. As used in this specification, "non-cohesive" shall mean those soils having a plasticity index (PI) of less than 3 as determined by ASTM D4318.~~

~~On all areas outside of the pavement areas, no compaction will be required on the top 4 inches (100 mm) which shall be prepared for a seedbed in accordance with Item T 901 or T 906.~~

~~The in place field density shall be determined in accordance with ASTM D1556 or ASTM 6938 using Procedure A, the direct transmission method, and ASTM D6938 shall be used to determine the moisture content of the material. The machine shall be calibrated in accordance with ASTM D6938. The Contractor's laboratory shall perform all density tests in the RPR's presence and provide the test results upon completion to the RPR for acceptance. If the specified density is not attained, the area represented by the test or as designated by the RPR shall be reworked and/or re-compacted and additional random tests made. This procedure shall be followed until the specified density is reached.~~

~~Compaction areas shall be kept separate, and no lift shall be covered by another lift until the proper density is obtained.~~

~~During construction of the embankment, the Contractor shall route all construction equipment evenly over the entire width of the embankment as each lift is placed. Lift placement shall begin in the deepest portion of the embankment fill. As placement progresses, the lifts shall be constructed approximately parallel to the finished pavement grade line.~~

~~When rock, concrete pavement, asphalt pavement, and other embankment material are excavated at approximately the same time as the subgrade, the material shall be incorporated into the outer portion of the embankment and the subgrade material shall be incorporated under the future paved areas. Stones, fragmentary rock, and recycled pavement larger than 4 inches (100 mm) in their greatest dimensions will not be allowed in the top 12 inches (300 mm) of the subgrade. Rockfill shall be brought up in lifts as specified or as directed by the RPR and the finer material shall be used to fill the voids forming a dense, compact mass. Rock, cement concrete pavement, asphalt pavement, and other embankment material shall not be disposed of except at places and in the manner designated on the plans or by the RPR.~~

~~When the excavated material consists predominantly of rock fragments of such size that the material cannot be placed in lifts of the prescribed thickness without crushing, pulverizing or further breaking down the pieces, such material may be placed in the embankment as directed in lifts not exceeding 2 feet (60 cm) in thickness. Each lift shall be leveled and smoothed with suitable equipment by distribution of spalls and finer fragments of rock. The lift shall not be constructed above an elevation 4 feet (1.2 m) below the finished subgrade.~~

~~There will be no separate measurement of payment for compacted embankment. All costs incidental to placing in lifts, compacting, discing, watering, mixing, sloping, and other operations necessary for construction of embankments will be included in the contract price for excavation, borrow, or other items.~~

**152-2.9 Proof rolling.** The purpose of proof rolling the subgrade is to identify any weak areas in the subgrade and not for compaction of the subgrade. After compaction is completed, the subgrade area shall be proof rolled with a Tandem axle Dual Wheel Dump Truck loaded to the legal limit with tires inflated to 100 psi in the presence of the RPR. Apply a minimum of three (3) coverage, or as specified by the RPR, under pavement areas. A coverage is defined as the application of one tire print over the designated area. Soft areas of subgrade that deflect more than 1 inch or show permanent deformation greater than 1 inch shall be removed and replaced with suitable material or reworked to conform to the moisture content and compaction requirements in accordance with these specifications. Removal and replacement of soft areas is incidental to this item.

**152-2.10 Compaction requirements.** The subgrade under areas to be paved shall be compacted to a depth of 12 inches and to a density of not less than 100 percent of the maximum dry density as determined by ASTM D1557. ~~The subgrade in areas outside the limits of the pavement areas shall be~~

~~compacted to a depth of 12 inches (300 mm) and to a density of not less than 95 percent of the maximum density as determined by ASTM D698.~~

The material to be compacted shall be within  $\pm 2\%$  of optimum moisture content before being rolled to obtain the prescribed compaction (except for expansive soils). When the material has greater than 30 percent retained on the  $\frac{3}{4}$  inch (19.0 mm) sieve, follow the methods in ASTM D1557. Tests for moisture content and compaction will be taken at a minimum of 1,500 S.Y. of subgrade. All quality assurance testing shall be done by the Contractor's laboratory in the presence of the RPR, and density test results shall be furnished upon completion to the RPR for acceptance determination.

The in-place field density shall be determined in accordance with ASTM D1556.

Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.

If the specified density is not attained, the entire lot shall be reworked and/or re-compacted and additional random tests made. This procedure shall be followed until the specified density is reached.

All cut-and-fill slopes shall be uniformly dressed to the slope, cross-section, and alignment shown on the plans or as directed by the RPR and the finished subgrade shall be maintained.

**152-2.11 Finishing and protection of subgrade.** Finishing and protection of the subgrade is incidental to this item. Grading and compacting of the subgrade shall be performed so that it will drain readily. All low areas, holes or depressions in the subgrade shall be brought to grade. Scarifying, blading, rolling and other methods shall be performed to provide a thoroughly compacted subgrade shaped to the lines and grades shown on the plans. All ruts or rough places that develop in the completed subgrade shall be graded, re-compacted, and retested. The Contractor shall protect the subgrade from damage and limit hauling over the finished subgrade to only traffic essential for construction purposes.

The Contractor shall maintain the completed course in satisfactory condition throughout placement of subsequent layers. No subbase, base, or surface course shall be placed on the subgrade until the subgrade has been accepted by the RPR.

**152-2.12 Haul.** All hauling will be considered a necessary and incidental part of the work. The Contractor shall include the cost in the contract unit price for the pay of items of work involved. No payment will be made separately or directly for hauling on any part of the work.

The Contractor's equipment shall not cause damage to any excavated surface, compacted lift or to the subgrade as a result of hauling operations. Any damage caused as a result of the Contractor's hauling operations shall be repaired at the Contractor's expense.

The Contractor shall be responsible for providing, maintaining and removing any haul roads or routes within or outside of the work area, and shall return the affected areas to their former condition, unless otherwise authorized in writing by the Owner. No separate payment will be made for any work or materials associated with providing, maintaining and removing haul roads or routes.

**152-2.13 Surface Tolerances.** In those areas on which a subbase or base course is to be placed, the surface shall be tested for smoothness and accuracy of grade and crown. Any portion lacking the required smoothness or failing in accuracy of grade or crown shall be scarified to a depth of at least 3 inches (75 mm), reshaped and re-compacted to grade until the required smoothness and accuracy are obtained and approved by the RPR. The Contractor shall perform all final smoothness and grade checks in the presence of the RPR. Any deviation in surface tolerances shall be corrected by the Contractor at the Contractor's expense.

- a. **Smoothness.** The finished surface shall not vary more than  $\pm \frac{1}{2}$  inch (12 mm) when tested with a 12-foot (3.7-m) straightedge applied parallel with and at right angles to the centerline. The

straightedge shall be moved continuously forward at half the length of the 12-foot (3.7-m) straightedge for the full length of each line on a 50-foot (15-m) grid.

- b. Grade.** The grade and crown shall be measured on a 50-foot (15-m) grid and shall be within +/- 0.05 feet (15 mm) of the specified grade.

On safety areas, turfed areas and other designated areas within the grading limits where no subbase or base is to be placed, grade shall not vary more than 0.10 feet (30 mm) from specified grade. Any deviation in excess of this amount shall be corrected by loosening, adding or removing materials, and reshaping.

**152-2.14 Topsoil.** ~~Not Used. When topsoil is specified or required as shown on the plans or under Item T-905, it shall be salvaged from stripping or other grading operations. The topsoil shall meet the requirements of Item T-905. If, at the time of excavation or stripping, the topsoil cannot be placed in its final section of finished construction, the material shall be stockpiled at approved locations. Stockpiles shall be located as shown on the plans and the approved CSPP, and shall not be placed on areas that subsequently will require any excavation or embankment fill. If, in the judgment of the RPR, it is practical to place the salvaged topsoil at the time of excavation or stripping, the material shall be placed in its final position without stockpiling or further re-handling.~~

~~Upon completion of grading operations, stockpiled topsoil shall be handled and placed as shown on the plans and as required in Item T-905. Topsoil shall be paid for as provided in Item T-905. No direct payment will be made for topsoil under Item P-152.~~

## METHOD OF MEASUREMENT

**152-3.1** Measurement for payment specified by the cubic yard (cubic meter) shall be computed by the comparison of digital terrain model (DTM) surfaces for computation of neat line design quantities. The end area is that bound by the original ground line established by field cross-sections and the final theoretical pay line established by cross-sections shown on the plans, subject to verification by the RPR.

**152-3.2** The quantity of unclassified excavation to be paid for shall be the number of cubic yards (cubic meters) measured in its original position. Measurement shall not include the quantity of materials excavated without authorization beyond normal slope lines, or the quantity of material used for purposes other than those directed. **All excess material from excavation is the contractor's responsibility to remove and dispose off airport property, and will be considered incidental to this item.**

**152-3.3** **No separate measurement will be made for the quantity of drainage excavation. Drainage excavation will be incidental to the removal of drainage infrastructure.** ~~The quantity of unclassified excavation to be paid for shall be the number of cubic yards (cubic meters) measured in its original position. Measurement shall not include the quantity of materials excavated without authorization beyond normal slope lines, or the quantity of material used for purposes other than those directed.~~

## BASIS OF PAYMENT

**152-4.1** Unclassified excavation payment shall be made at the contract unit price per cubic yard. This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-152-4.1	Unclassified Excavation – per cubic yard
----------------	--

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### American Association of State Highway and Transportation Officials (AASHTO)

AASHTO T-180	Standard Method of Test for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop
--------------	---

### ASTM International (ASTM)

ASTM D698	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft <sup>3</sup> (600 kN-m/m <sup>3</sup> ))
-----------	--

ASTM D1556	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method
------------	---

ASTM D1557	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft <sup>3</sup> (2700 kN-m/m <sup>3</sup> ))
------------	---

ASTM D6938	Standard Test Methods for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)
------------	--

### Advisory Circulars (AC)

AC 150/5370-2	Operational Safety on Airports During Construction Software
---------------	---

### Software

FAARFIELD – FAA Rigid and Flexible Iterative Elastic Layered Design

### U.S. Department of Transportation

FAA RD-76-66	Design and Construction of Airport Pavements on Expansive Soils
--------------	---

**END OF ITEM P-152**

## Item P-209 Crushed Aggregate Base Course

### DESCRIPTION

**209-1.1** This item consists of a base course composed of crushed aggregate base constructed on a prepared course in accordance with these specifications and in conformity to the dimensions and typical cross-sections shown on the plans.

### MATERIALS

**209-2.1 Crushed aggregate base.** Crushed aggregate shall consist of clean, sound, durable particles of crushed stone, crushed gravel, and shall be free from coatings of clay, silt, organic material, clay lumps or balls or other deleterious materials or coatings. The method used to produce the crushed gravel shall result in the fractured particles in the finished product as consistent and uniform as practicable. Fine aggregate portion, defined as the portion passing the No. 4 (4.75 mm) sieve shall consist of fines from the coarse aggregate crushing operation. The fine aggregate shall be produced by crushing stone, gravel, that meet the coarse aggregate requirements for wear and soundness. Aggregate base material requirements are listed in the following table.

**Crushed Aggregate Base Material Requirements**

Material Test	Requirement	Standard
<b>Coarse Aggregate</b>		
Resistance to Degradation	Loss: 45% maximum	ASTM C131
Soundness of Aggregates by Use of Sodium Sulfate <b>or</b> Magnesium Sulfate	Loss after 5 cycles: 12% maximum using Sodium sulfate - or - 18% maximum using magnesium sulfate	ASTM C88
Percentage of Fractured Particles	Minimum 90% by weight of particles with at least two fractured faces and 98% with at least one fractured face <sup>1</sup>	ASTM D5821
Flat Particles, Elongated Particles, or Flat and Elongated Particles	10% maximum, by weight, of flat, elongated, or flat and elongated particles <sup>2</sup>	ASTM D4791
<b>Fine Aggregate</b>		
Liquid limit	Less than or equal to 25	ASTM D4318
Plasticity Index	Not more than five (5)	ASTM D4318

<sup>1</sup> The area of each face shall be equal to at least 75% of the smallest mid-sectional area of the piece. When two fractured faces are contiguous, the angle between the planes of fractures shall be at least 30 degrees to count as two fractured faces.

<sup>2</sup> A flat particle is one having a ratio of width to thickness greater than five (5); an elongated particle is one having a ratio of length to width greater than five (5).

**209-2.2 Gradation requirements.** The gradation of the aggregate base material shall meet the requirements of the gradation given in the following table when tested per ASTM C117 and ASTM C136. The gradation shall be well graded from coarse to fine and shall not vary from the lower limit on one sieve to the high limit on an adjacent sieve or vice versa.

**Gradation of Aggregate Base**

<b>Sieve Size</b>	<b>Design Range Percentage by Weight passing</b>	<b>Contractor's Final Gradation</b>	<b>Job Control Grading Band Tolerances<sup>1</sup> (Percent)</b>
2 inch (50 mm)	100		0
1-1/2 inch (37.5 mm)	95-100		±5
1 inch (25.0 mm)	70-95		±8
3/4 inch (19.0 mm)	55-85		±8
No. 4 (4.75 mm)	30-60		±8
No. 40 <sup>2</sup> (425 µm)	10-30		±5
No. 200 <sup>2</sup> (75 µm)	0-10		±3

<sup>1</sup> The "Job Control Grading Band Tolerances for Contractor's Final Gradation" in the table shall be applied to "Contractor's Final Gradation" to establish a job control grading band. The full tolerance still applies if application of the tolerances results in a job control grading band outside the design range.

<sup>2</sup> The fraction of material passing the No 200 (75 µm) sieve shall not exceed two-thirds the fraction passing the No 40 (425 µm) sieve.

### **209-2.3 Sampling and Testing.**

**a. Aggregate base materials.** The Contractor shall take samples of the aggregate base in accordance with ASTM D75 to verify initial aggregate base requirements and gradation. Material shall meet the requirements in paragraph 209-2.1. This sampling and testing will be the basis for approval of the aggregate base quality requirements.

**b. Gradation requirements.** The Contractor shall take at least two aggregate base samples per day in the presence of the Resident Project Representative (RPR) to check the final gradation. Sampling shall be per ASTM D75. Material shall meet the requirements in paragraph 209-2.2. The samples shall be taken from the in-place, un-compacted material at sampling points and intervals designated by the RPR.

**209-2.4 Separation Geotextile.** Separation geotextile shall be Class 2, 0.02 sec<sup>-1</sup> permittivity per ASTM D4491, Apparent opening size per ASTM D4751 with 0.60 mm maximum average roll value.

## CONSTRUCTION METHODS

**209-3.1 Control strip.** The first half-day of construction shall be considered the control strip. The Contractor shall demonstrate, in the presence of the RPR, that the materials, equipment, and construction processes meet the requirements of the specification. The sequence and manner of rolling necessary to obtain specified density requirements shall be determined. The maximum compacted thickness may be increased to a maximum of 12 inches (300 mm) upon the Contractor's demonstration that approved equipment and operations will uniformly compact the lift to the specified density. The RPR must witness this demonstration and approve the lift thickness prior to full production.

Control strips that do not meet specification requirements shall be reworked, re-compacted or removed and replaced at the Contractor's expense. Full operations shall not continue until the control strip has been accepted by the RPR. The Contractor shall use the same equipment, materials, and construction methods for the remainder of construction, unless adjustments made by the Contractor are approved by the RPR.

**209-3.2 Preparing underlying subgrade and/or subbase.** The underlying subgrade and/or subbase shall be checked and accepted by the RPR before base course placing and spreading operations begin. Re-proof rolling of the subgrade or proof rolling of the subbase in accordance with Item P-152, at the Contractor's expense, may be required by the RPR if the Contractor fails to ensure proper drainage or protect the subgrade and/or subbase. Any ruts or soft, yielding areas due to improper drainage conditions, hauling, or any other cause, shall be corrected before the base course is placed. To ensure proper drainage, the spreading of the base shall begin along the centerline of the pavement on a crowned section or on the high side of the pavement with a one-way slope.

**209-3.3 Production.** The aggregate shall be uniformly blended and, when at a satisfactory moisture content per paragraph 209-3.5, the approved material may be transported directly to the placement.

**209-3.4 Placement.** The aggregate shall be placed and spread on the prepared underlying layer by spreader boxes or other devices as approved by the RPR, to a uniform thickness and width. The equipment shall have positive thickness controls to minimize the need for additional manipulation of the material. Dumping from vehicles that require re-handling shall not be permitted. Hauling over the uncompacted base course shall not be permitted.

The aggregate shall meet gradation and moisture requirements prior to compaction. The base course shall be constructed in lifts as established in the control strip, but not less than 4 inches (100 mm) nor more than 12 inches (300 mm) of compacted thickness.

When more than one lift is required to establish the layer thickness shown on the plans, the construction procedure described here shall apply to each lift. No lift shall be covered by subsequent lifts until tests verify that compaction requirements have been met. The Contractor shall rework, re-compact and retest any material placed which does not meet the specifications at the Contractor's expense.

**209-3.5 Compaction.** Immediately after completion of the spreading operations, compact each layer of the base course, as specified, with approved compaction equipment. The number, type, and weight of rollers shall be sufficient to compact the material to the required density within the same day that the aggregate is placed on the subgrade.

The field density of each compacted lift of material shall be at least 100% of the maximum density of laboratory specimens prepared from samples of the base material delivered to the jobsite. The laboratory specimens shall be compacted and tested in accordance with ASTM D1557. The moisture content of the material during placing operations shall be within  $\pm 2$  percentage points of the optimum moisture content as determined by ASTM D1557. Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.



**209-3.6 Weather limitations.** Material shall not be placed unless the ambient air temperature is at least 40°F (4°C) and rising. Work on base course shall not be conducted when the subgrade or subbase is wet or frozen or the base material contains frozen material.

**209-3.7 Maintenance.** The base course shall be maintained in a condition that will meet all specification requirements. When material has been exposed to excessive rain, snow, or freeze-thaw conditions, prior to placement of additional material, the Contractor shall verify that materials still meet all specification requirements. Equipment may be routed over completed sections of base course, provided that no damage results and the equipment is routed over the full width of the completed base course. Any damage resulting to the base course from routing equipment over the base course shall be repaired by the Contractor at the Contractor's expense.

**209-3.8 Surface tolerances.** After the course has been compacted, the surface shall be tested for smoothness and accuracy of grade and crown. Any portion lacking the required smoothness or failing in accuracy of grade or crown shall be scarified to a depth of at least 3 inches (75 mm), reshaped and recompact to grade until the required smoothness and accuracy are obtained and approved by the RPR. Any deviation in surface tolerances shall be corrected by the Contractor at the Contractor's expense. The smoothness and accuracy requirements specified here apply only to the top layer when base course is constructed in more than one layer.

**a. Smoothness.** The finished surface shall not vary more than 3/8-inch (9 mm) when tested with a 12-foot (3.7-m) straightedge applied parallel with and at right angles to the centerline. The straightedge shall be moved continuously forward at half the length of the 12-foot (3.7-m) straightedge for the full length of each line on a 50-foot (15-m) grid.

**b. Grade.** The grade and crown shall be measured on a 50-foot (15-m) grid and shall be within +0 and -1/2 inch (12 mm) of the specified grade.

**209-3.9 Acceptance sampling and testing.** Crushed aggregate base course shall be accepted for density and thickness on an area basis. Two tests shall be made for density and thickness for each 1200 square yds (1000 m<sup>2</sup>). Sampling locations will be determined on a random basis per ASTM D3665

**a. Density.** The Contractor's laboratory shall perform all density tests in the RPR's presence and provide the test results upon completion to the RPR for acceptance.

Each area shall be accepted for density when the field density is at least 100% of the maximum density of laboratory specimens compacted and tested per ASTM D1557. The in-place field density shall be determined per ASTM D1556 or ASTM D6938 using Procedure A, the direct transmission method, and ASTM D6938 shall be used to determine the moisture content of the material. The machine shall be calibrated in accordance with ASTM D6938. If the specified density is not attained, the area represented by the failed test must be reworked and/or recompact and two additional random tests made. This procedure shall be followed until the specified density is reached. Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.

**b. Thickness.** Depth tests shall be made by test holes at least 3 inches (75 mm) in diameter that extend through the base. The thickness of the base course shall be within +0 and -1/2 inch (12 mm) of the specified thickness as determined by depth tests taken by the Contractor in the presence of the RPR for each area. Where the thickness is deficient by more than 1/2-inch (12 mm), the Contractor shall correct such areas at no additional cost by scarifying to a depth of at least 3 inches (75 mm), adding new material of proper gradation, and the material shall be blended and recompact to grade. The Contractor shall replace, at his expense, base material where depth tests have been taken.

## METHOD OF MEASUREMENT

**209-4.1** The quantity of crushed aggregate base course will be determined by measurement of the number of cubic yards of material actually constructed and accepted by the RPR as complying with the plans and specifications. Base materials shall not be included in any other excavation quantities.

**209-4.2** Separation geotextile shall be measured by the number of square yards of materials placed and accepted by the RPR as complying with the plans and specifications excluding seam overlaps and edge anchoring.

## BASIS OF PAYMENT

**209-5.1** Payment shall be made at the contract unit price per cubic yard for crushed aggregate base course. This price shall be full compensation for furnishing all materials, for preparing and placing these materials, and for all labor, equipment tools, and incidentals necessary to complete the item.

**209-5.2** Payment shall be made at the contract unit price per square yard for separation geotextile. The price shall be full compensation for furnishing all labor, equipment, material, anchors, and incidentals necessary.

Payment will be made under:

Item P-209-5.1	Crushed Aggregate Base Course, 7-inch depth – per cubic yard
Item P-209-5.2	Separation Geotextile – per square yard

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### ASTM International (ASTM)

ASTM C29	Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate
ASTM C88	Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C117	Standard Test Method for Materials Finer than 75- $\mu$ m (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C142	Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM D75	Standard Practice for Sampling Aggregates
ASTM D698	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft <sup>3</sup> (600 kN-m/m <sup>3</sup> ))
ASTM D1556	Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method

ASTM D1557	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft <sup>3</sup> (2700 kN-m/m <sup>3</sup> ))
ASTM D2167	Standard Test Method for Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D2419	Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4491	Standard Test Methods for Water Permeability of Geotextiles by Permittivity
ASTM D4643	Standard Test Method for Determination of Water Content of Soil and Rock by Microwave Oven Heating
ASTM D4751	Standard Test Methods for Determining Apparent Opening Size of a Geotextile
ASTM D4791	Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D5821	Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D6938	Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)
ASTM D7928	Standard Test Method for Particle-Size Distribution (Gradation) of Fine-Grained Soils Using the Sedimentation (Hydrometer) Analysis
American Association of State Highway and Transportation Officials (AASHTO)	
M288	Standard Specification for Geosynthetic Specification for Highway Applications

**END OF ITEM P-209**

## Item P-401 Asphalt Mix Pavement

### DESCRIPTION

**401-1.1** This item shall consist of pavement courses composed of mineral aggregate and asphalt binder mixed in a central mixing plant and placed on a prepared base or stabilized course in accordance with these specifications and shall conform to the lines, grades, thicknesses, and typical cross-sections shown on the plans. Each course shall be constructed to the depth, typical section, and elevation required by the plans and shall be rolled, finished, and approved before the placement of the next course.

### MATERIALS

**401-2.1 Aggregate.** Aggregates shall consist of crushed stone, crushed gravel, crushed slag, screenings, natural sand, and mineral filler, as required. The aggregates should have no known history of detrimental pavement staining due to ferrous sulfides, such as pyrite. Coarse aggregate is the material retained on the No. 4 (4.75 mm) sieve. Fine aggregate is the material passing the No. 4 (4.75 mm) sieve.

Provide documentation that aggregate suppliers have taken steps to minimize the inclusion of ferrous sulfides or iron oxides in the aggregate to be used in the project.

**a. Coarse aggregate.** Coarse aggregate shall consist of sound, tough, durable particles, free from films of matter that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. Coarse aggregate material requirements are given in the table below.

### Coarse Aggregate Material Requirements

Material Test	Requirement	Standard
Resistance to Degradation	Loss: 40% maximum	ASTM C131
Soundness of Aggregates by Use of Sodium Sulfate <b>or</b> Magnesium Sulfate	Loss after 5 cycles: 12% maximum using Sodium sulfate - or - 18% maximum using magnesium sulfate	ASTM C88
Clay lumps and friable particles	1.0 % maximum	ASTM C142
Percentage of Fractured Particles	For pavements designed for aircraft gross weights of 60,000 pounds (27200 kg) or more: Minimum 75% by weight of particles with at least two fractured faces and 85% with at least one fractured face <sup>1</sup>	ASTM D5821
	<del>For pavements designed for aircraft gross weights less than 60,000 pounds (27200 kg): Minimum 50% by weight of particles with at least two fractured faces and 65% with at least one fractured face<sup>1</sup></del>	
Flat, Elongated, or Flat and Elongated Particles	8% maximum, by weight, of flat, elongated, or flat and elongated particles at 5:1 <sup>2</sup>	ASTM D4791
Bulk density of slag <sup>3</sup>	Weigh not less than 70 pounds per cubic foot (1.12 Mg/cubic meter)	ASTM C29.

<sup>1</sup> The area of each face shall be equal to at least 75% of the smallest mid-sectional area of the piece. When two fractured faces are contiguous, the angle between the planes of fractures shall be at least 30 degrees to count as two fractured faces.

<sup>2</sup> A flat particle is one having a ratio of width to thickness greater than five (5); an elongated particle is one having a ratio of length to width greater than five (5).

<sup>3</sup> Only required if slag is specified.

**b. Fine aggregate.** Fine aggregate shall consist of clean, sound, tough, durable, angular shaped particles produced by crushing stone, slag, or gravel and shall be free from coatings of clay, silt, or other objectionable matter. Natural (non-manufactured) sand may be used to obtain the gradation of the fine aggregate blend or to improve the workability of the mix. Fine aggregate material requirements are listed in the table below.

**Fine Aggregate Material Requirements**

<b>Material Test</b>	<b>Requirement</b>	<b>Standard</b>
Liquid limit	25 maximum	ASTM D4318
Plasticity Index	4 maximum	ASTM D4318
Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate	Loss after 5 cycles: 10% maximum using Sodium sulfate - or - 15% maximum using magnesium sulfate	ASTM C88
Clay lumps and friable particles	1.0% maximum	ASTM C142
Sand equivalent	45 minimum	ASTM D2419
Natural Sand	0% to 15% maximum by weight of total aggregate	ASTM D1073

**c. Sampling.** ASTM D75 shall be used in sampling coarse and fine aggregate.

**401-2.2 Mineral filler.** Mineral filler (baghouse fines) may be added in addition to material naturally present in the aggregate. Mineral filler shall meet the requirements of ASTM D242.

**Mineral Filler Requirements**

<b>Material Test</b>	<b>Requirement</b>	<b>Standard</b>
Plasticity Index	4 maximum	ASTM D4318

**401-2.3 Asphalt binder.** Asphalt binder shall conform to ASTM D6373 Performance Grade (PG) 82-22.

**Asphalt Binder PG Plus Test Requirements**

<b>Material Test</b>	<b>Requirement</b>	<b>Standard</b>
Elastic Recovery	[75%] minimum	ASTM D6084 <sup>1</sup>

<sup>1</sup> Follow procedure B on RTFO aged binder.

**401-2.4 Anti-stripping agent.** Any anti-stripping agent or additive (anti-strip) shall be heat stable and shall not change the asphalt binder grade beyond specifications. Anti-strip shall be an approved material of the [Virginia](#) Department of Transportation. ~~of the State in which the project is located.~~

**COMPOSITION**

**401-3.1 Composition of mixture(s).** The asphalt mix shall be composed of a mixture of aggregates, filler and anti-strip agent if required, and asphalt binder. The aggregate fractions shall be sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of the job mix formula (JMF).

**401-3.2 Job mix formula (JMF) laboratory.** The laboratory used to develop the JMF shall possess a current certificate of accreditation, listing D3666 from a national accrediting authority and all test methods required for developing the JMF; and be listed on the accrediting authority's website. A copy of the laboratory's current accreditation and accredited test methods shall be submitted to the Resident Project Representative (RPR) prior to start of construction.

**401-3.3 Job mix formula (JMF).** No asphalt mixture shall be placed until an acceptable mix design has been submitted to the RPR for review and accepted in writing. The RPR's review shall not relieve the Contractor of the responsibility to select and proportion the materials to comply with this section.

When the project requires asphalt mixtures of differing aggregate gradations and/or binders, a separate JMF shall be submitted for each mix. Add anti-stripping agent to meet tensile strength requirements.

The JMF shall be prepared by an accredited laboratory that meets the requirements of paragraph 401-3.2. The asphalt mixture shall be designed using procedures contained in Asphalt Institute MS-2 Mix Design Manual, 7th Edition. Samples shall be prepared and compacted using the gyratory compactor in accordance with ASTM D6925.

Should a change in sources of materials be made, a new JMF must be submitted to the RPR for review and accepted in writing before the new material is used. After the initial production JMF has been approved by the RPR and a new or modified JMF is required for whatever reason, the subsequent cost of the new or modified JMF, including a new control strip when required by the RPR, will be borne by the Contractor.

The RPR may request samples at any time for testing, prior to and during production, to verify the quality of the materials and to ensure conformance with the applicable specifications.

The JMF shall be submitted in writing by the Contractor at least [ 30 ] days prior to the start of paving operations. The JMF shall be developed within the same construction season using aggregates proposed for project use.

The JMF shall be dated, and stamped or sealed by the responsible professional Engineer of the laboratory and shall include the following items as a minimum:

- Manufacturer's Certificate of Analysis (COA) for the asphalt binder used in the JMF in accordance with paragraph 401-2.3. Certificate of asphalt performance grade is with modifier already added, if used and must indicate compliance with ASTM D6373. For plant modified asphalt binder, certified test report indicating grade certification of modified asphalt binder.
- Manufacturer's Certificate of Analysis (COA) for the anti-stripping agent if used in the JMF in accordance with paragraph 401-2.4.
- Certified material test reports for the course and fine aggregate and mineral filler in accordance with paragraphs 401-2.1.
- Percent passing each sieve size for individual gradation of each aggregate cold feed and/or hot bin; percent by weight of each cold feed and/or hot bin used; and the total combined gradation in the JMF.
- Specific Gravity and absorption of each coarse and fine aggregate.
- Percent natural sand.
- Percent fractured faces.
- Percent by weight of flat particles, elongated particles, and flat and elongated particles (and criteria).
- Percent of asphalt.
- Number of blows or gyrations
- Laboratory mixing and compaction temperatures.
- Supplier-recommended field mixing and compaction temperatures.

- Plot of the combined gradation on a 0.45 power gradation curve.
- Graphical plots of air voids, voids in the mineral aggregate (VMA), and unit weight versus asphalt content. To achieve minimum VMA during production, the mix design needs to account for material breakdown during production.
- Tensile Strength Ratio (TSR).
- Type and amount of Anti-strip agent when used.
- Asphalt Pavement Analyzer (APA) results.
- Date the JMF was developed. Mix designs that are not dated or which are from a prior construction season shall not be accepted.

**Table 1. Asphalt Design Criteria**

Test Property	Value	Test Method
Number of blows or gyrations	75	
Air voids (%)	3.5	ASTM D3203
Percent voids in mineral aggregate (VMA), minimum	See Table 2	ASTM D6995
Tensile Strength Ratio (TSR) <sup>1</sup>	not less than 80 at a saturation of 70-80%	ASTM D4867
Asphalt Pavement Analyzer (APA) <sup>2</sup>	Less than 10 mm @ 4000 passes	AASHTO T340 at 250 psi hose pressure at 64°C test temperature

<sup>1</sup> Test specimens for TSR shall be compacted at  $7 \pm 1.0$  % air voids. In areas subject to freeze-thaw, use freeze-thaw conditioning in lieu of moisture conditioning per ASTM D4867.

<sup>2</sup> AASHTO T340 at 100 psi hose pressure at 64°C test temperature may be used in the interim. If this method is used the required Value shall be less than 5 mm @ 8000 passes

The mineral aggregate shall be of such size that the percentage composition by weight, as determined by laboratory sieves, will conform to the gradation or gradations specified in Table 2 when tested in accordance with ASTM C136 and ASTM C117.

The gradations in Table 2 represent the limits that shall determine the suitability of aggregate for use from the sources of supply; be well graded from coarse to fine and shall not vary from the low limit on one sieve to the high limit on the adjacent sieve, or vice versa.



**Table 2. Aggregate - Asphalt Pavements**

Sieve Size	Percentage by Weight Passing Sieve
	Surface Course
1 inch (25.0 mm)	--
3/4 inch (19.0 mm)	100
1/2 inch (12.5 mm)	90-100
3/8 inch (9.5 mm)	72-88
No. 4 (4.75 mm)	53-73
No. 8 (2.36 mm)	38-60
No. 16 (1.18 mm)	26-48
No. 30 (600 µm)	18-38
No. 50 (300 µm)	11-27
No. 100 (150 µm)	6-18
No. 200 (75 µm)	3-6
<b>Minimum Voids in Mineral Aggregate (VMA)<sup>1</sup></b>	15.0
<b>Asphalt Percent:</b>	
Stone or gravel	5.0-7.5
<del>—Slag</del>	<del>6.5-9.5</del>
<b>Recommended Minimum Construction Lift Thickness</b>	2 inch

<sup>1</sup>To achieve minimum VMA during production, the mix design needs to account for material breakdown during production.

The aggregate gradations shown are based on aggregates of uniform specific gravity. The percentages passing the various sieves shall be corrected when aggregates of varying specific gravities are used, as indicated in the Asphalt Institute MS-2 Mix Design Manual, 7th Edition.

**401-3.4 Reclaimed asphalt pavement (RAP).** RAP shall not be used.

**401-3.5 Control Strip.** A control strip is not required.

## CONSTRUCTION METHODS

**401-4.1 Weather limitations.** The asphalt shall not be placed upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 4. The temperature requirements may be waived by the RPR, if requested; however, all other requirements including compaction shall be met.

**Table 4. Surface Temperature Limitations of Underlying Course**

Mat Thickness	Base Temperature (Minimum)	
	°F	°C
3 inches (7.5 cm) or greater	40 <sup>1</sup>	4
Greater than 2 inches (50 mm) but less than 3 inches (7.5 cm)	45	7

<sup>1</sup>The placement of the final wearing surface with a PG 82-22 shall be performed in ambient temperatures of 50°F and rising and the existing base temperature shall also be 50°F.

**401-4.2 Asphalt plant.** Plants used for the preparation of asphalt shall conform to the requirements of American Association of State Highway and Transportation Officials (AASHTO) M156 including the following items.

**a. Inspection of plant.** The RPR, or RPR's authorized representative, shall have access, at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant; verifying weights, proportions, and material properties; and checking the temperatures maintained in the preparation of the mixtures.

**b. Storage bins and surge bins.** The asphalt mixture stored in storage and/or surge bins shall meet the same requirements as asphalt mixture loaded directly into trucks. Asphalt mixture shall not be stored in storage and/or surge bins for a period greater than twelve (12) hours. If the RPR determines there is an excessive heat loss, segregation, or oxidation of the asphalt mixture due to temporary storage, temporary storage shall not be allowed.

**401-4.3 Aggregate stockpile management.** Aggregate stockpiles shall be constructed in a manner that prevents segregation and intermixing of deleterious materials. Aggregates from different sources shall be stockpiled, weighed and batched separately at the asphalt batch plant. Aggregates that have become segregated or mixed with earth or foreign material shall not be used.

A continuous supply of materials shall be provided to the work to ensure continuous placement.

**401-4.4 Hauling equipment.** Trucks used for hauling asphalt shall have tight, clean, and smooth metal beds. To prevent the asphalt from sticking to the truck beds, the truck beds shall be lightly coated with a minimum amount of paraffin oil, lime solution, or other material approved by the RPR. Petroleum products shall not be used for coating truck beds. Each truck shall have a suitable cover to protect the mixture from adverse weather. When necessary, to ensure that the mixture will be delivered to the site at the specified temperature, truck beds shall be insulated or heated and covers shall be securely fastened.

**401-4.4.1 Material transfer vehicle (MTV).** Material transfer vehicles used to transfer the material from the hauling equipment to the paver, shall use a self-propelled, material transfer vehicle with a swing conveyor that can deliver material to the paver without making contact with the paver. The MTV shall be able to move back and forth between the hauling equipment and the paver providing material transfer to the paver, while allowing the paver to operate at a constant speed. The Material Transfer Vehicle will have remixing and storage capability to prevent physical and thermal segregation.

**401-4.5 Asphalt pavers.** Asphalt pavers shall be self-propelled with an activated heated screed, capable of spreading and finishing courses of asphalt that will meet the specified thickness, smoothness, and grade. The paver shall have sufficient power to propel itself and the hauling equipment without adversely affecting the finished surface. The asphalt paver shall be equipped with a control system capable of automatically maintaining the specified screed grade and elevation.

If the spreading and finishing equipment in use leaves tracks or indented areas, or produces other blemishes in the pavement that are not satisfactorily corrected by the scheduled operations, the use of such equipment shall be discontinued.

The paver shall be capable of paving to a minimum width specified in paragraph 401-4.12.

**401-4.6 Rollers.** The number, type, and weight of rollers shall be sufficient to compact the asphalt to the required density while it is still in a workable condition without crushing of the aggregate, depressions or other damage to the pavement surface. Rollers shall be in good condition, clean, and capable of operating at slow speeds to avoid displacement of the asphalt. All rollers shall be specifically designed and suitable for compacting asphalt concrete and shall be properly used. Rollers that impair the stability of any layer of a pavement structure or underlying soils shall not be used.

**401-4.7 Density device.** The Contractor shall have on site a density gauge during all paving operations in order to assist in the determination of the optimum rolling pattern, type of roller and frequencies, as well as to monitor the effect of the rolling operations during production paving. The Contractor shall supply a qualified technician during all paving operations to calibrate the gauge and obtain accurate density readings for all new asphalt. These densities shall be supplied to the RPR upon request at any time during construction. No separate payment will be made for supplying the density gauge and technician.

**401-4.8 Preparation of asphalt binder.** The asphalt binder shall be heated in a manner that will avoid local overheating and provide a continuous supply of the asphalt binder to the mixer at a uniform temperature. The temperature of unmodified asphalt binder delivered to the mixer shall be sufficient to provide a suitable viscosity for adequate coating of the aggregate particles, but shall not exceed 325°F (160°C) when added to the aggregate. The temperature of modified asphalt binder shall be no more than 350°F (175°C) when added to the aggregate.

**401-4.9 Preparation of mineral aggregate.** The aggregate for the asphalt shall be heated and dried. The maximum temperature and rate of heating shall be such that no damage occurs to the aggregates. The temperature of the aggregate and mineral filler shall not exceed 350°F (175°C) when the asphalt binder is added. Particular care shall be taken that aggregates high in calcium or magnesium content are not damaged by overheating. The temperature shall not be lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.

**401-4.10 Preparation of Asphalt mixture.** The aggregates and the asphalt binder shall be weighed or metered and mixed in the amount specified by the JMF. The combined materials shall be mixed until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. Wet mixing time shall be the shortest time that will produce a satisfactory mixture, but not less than 25 seconds for batch plants. The wet mixing time for all plants shall be established by the Contractor, based on the procedure for determining the percentage of coated particles described in ASTM D2489, for each individual plant and for each type of aggregate used. The wet mixing time will be set to achieve 95% of coated particles. For continuous mix plants, the minimum mixing time shall be determined by dividing the weight of its contents at operating level by the weight of the mixture delivered per second by the mixer. The moisture content of all asphalt upon discharge shall not exceed 0.5%.

**401-4.11 Application of Prime and Tack Coat.** Immediately before placing the asphalt mixture, the underlying course shall be cleaned of all dust and debris.

~~A prime coat in accordance with Item P-602 shall be applied to aggregate base prior to placing the asphalt mixture.~~

A tack coat shall be applied in accordance with Item P-603 to all vertical and horizontal asphalt and concrete surfaces prior to placement of the first and each subsequent lift of asphalt mixture.

**401-4.12 Laydown plan, transporting, placing, and finishing.** Prior to the placement of the asphalt, the Contractor shall prepare a laydown plan with the sequence of paving lanes and width to minimize the

number of cold joints; the location of any temporary ramps; laydown temperature; and estimated time of completion for each portion of the work (milling, paving, rolling, cooling, etc.). The laydown plan and any modifications shall be approved by the RPR.

Deliveries shall be scheduled so that placing and compacting of asphalt is uniform with minimum stopping and starting of the paver. Hauling over freshly placed material shall not be permitted until the material has been compacted, as specified, and allowed to cool to approximately ambient temperature. The Contractor, at their expense, shall be responsible for repair of any damage to the pavement caused by hauling operations.

Contractor shall survey each lift of asphalt surface course and certify to RPR that every lot of each lift meets the grade tolerances of paragraph 401-6.2d before the next lift can be placed.

Edges of existing asphalt pavement abutting the new work shall be saw cut and the cut off material and laitance removed. Apply a tack coat in accordance with P-603 before new asphalt material is placed against it.

The speed of the paver shall be regulated to eliminate pulling and tearing of the asphalt mat. Placement of the asphalt mix shall begin along the centerline of a crowned section or on the high side of areas with a one way slope unless shown otherwise on the laydown plan as accepted by the RPR. The asphalt mix shall be placed in consecutive adjacent lanes having a minimum width of 10 feet except where edge lanes require less width to complete the area. Additional screed sections attached to widen the paver to meet the minimum lane width requirements must include additional auger sections to move the asphalt mixture uniformly along the screed extension.

The surface course paving plan shall identify longitudinal hot joints full width of the defined taxiway in the daily allotted timeframe. Contractor shall set the paving lane widths in a manner to address existing grade breaks. The plan for multiple layers shall identify the lane widths, tonnage amounts per lane, cooling timeframes, and appropriate cleanup.

The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least one foot (30 cm); however, the joint in the surface top course shall be at the centerline of crowned pavements. Transverse joints in one course shall be offset by at least 10 feet (3 m) from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 10 feet (3 m). On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the asphalt may be spread and luted by hand tools.

The RPR may at any time, reject any batch of asphalt, on the truck or placed in the mat, which is rendered unfit for use due to contamination, segregation, incomplete coating of aggregate, or overheated asphalt mixture. Such rejection may be based on only visual inspection or temperature measurements. In the event of such rejection, the Contractor may take a representative sample of the rejected material in the presence of the RPR, and if it can be demonstrated in the laboratory, in the presence of the RPR, that such material was erroneously rejected, payment will be made for the material at the contract unit price.

Areas of segregation in the surface course, as determined by the RPR, shall be removed and replaced at the Contractor's expense. The area shall be removed by saw cutting and milling a minimum of the construction lift thickness as specified in paragraph 401-3.3, Table 2 for the approved mix design. The area to be removed and replaced shall be a minimum width of the paver and a minimum of 10 feet (3 m) long. If an unusual amount of segregate or contaminated material is identified, all production paving shall be stopped until the cause can be identified and corrected. Removal of such areas may include the material produced within the lot.

**401-4.13 Compaction of asphalt mixture.** After placing, the asphalt mixture shall be thoroughly and uniformly compacted by self-propelled rollers. The surface shall be compacted as soon as possible when the asphalt has attained sufficient stability so that the rolling does not cause undue displacement, cracking

or shoving. The sequence of rolling operations and the type of rollers used shall be at the discretion of the Contractor. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any surface defects and/or displacement occurring as a result of the roller, or from any other cause, shall be corrected at the Contractor's expense.

Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until the surface is of uniform texture, true to grade and cross-section, and the required field density is obtained. To prevent adhesion of the asphalt to the roller, the wheels shall be equipped with a scraper and kept moistened with water as necessary.

In areas not accessible to the roller, the mixture shall be thoroughly compacted with approved power tampers.

Any asphalt that becomes loose and broken, mixed with dirt, contains check-cracking, or in any way defective shall be removed and replaced with fresh hot mixture and immediately compacted to conform to the surrounding area. This work shall be done at the Contractor's expense. Skin patching shall not be allowed.

**401-4.14 Joints.** The formation of all joints shall be made to ensure a continuous bond between the courses and obtain the required density. All joints shall have the same texture as other sections of the course and meet the requirements for smoothness and grade.

The roller shall not pass over the unprotected end of the freshly laid asphalt except when necessary to form a transverse joint. When necessary to form a transverse joint, it shall be made by means of placing a bulkhead or by tapering the course. The tapered edge shall be cut back to its full depth and width on a straight line to expose a vertical face prior to placing the adjacent lane. In both methods, all contact surfaces shall be coated with an asphalt tack coat before placing any fresh asphalt against the joint.

Longitudinal joints which have been left exposed for more than four (4) hours; the surface temperature has cooled to less than 175°F (80°C); or are irregular, damaged, uncompacted or otherwise defective shall be cut back with a cutting wheel or pavement saw a maximum of 3 inches (75 mm) to expose a clean, sound, uniform vertical surface for the full depth of the course. All cutback material and any laitance produced from cutting joints shall be removed from the project. Asphalt tack coat in accordance with P-603 shall be applied to the clean, dry joint prior to placing any additional fresh asphalt against the joint. The cost of this work shall be considered incidental to the cost of the asphalt.

**401-4.15 Saw-cut grooving.** Saw-cut grooving is not required.

**401-4.16 Diamond grinding.** Diamond grinding shall be completed prior to pavement grooving. Diamond grinding shall be accomplished by sawing with saw blades impregnated with industrial diamond abrasive.

Diamond grinding shall be performed with a machine designed specifically for diamond grinding capable of cutting a path at least 3 feet (0.9 m) wide. The saw blades shall be 1/8-inch (3-mm) wide with a sufficient number of blades to create grooves between 0.090 and 0.130 inches (2 and 3.5 mm) wide; and peaks and ridges approximately 1/32 inch (1 mm) higher than the bottom of the grinding cut. The actual number of blades will be determined by the Contractor and depend on the hardness of the aggregate. Equipment or grinding procedures that cause ravels, aggregate fractures, spalls or disturbance to the pavement will not be permitted. Contractor shall demonstrate to the RPR that the grinding equipment will produce satisfactory results prior to making corrections to surfaces. Grinding will be tapered in all directions to provide smooth transitions to areas not requiring grinding. The slurry resulting from the grinding operation shall be continuously removed and the pavement left in a clean condition. The Contractor shall apply a surface treatment per P-608 to all areas that have been subject to grinding.

**401-4.17 Nighttime paving requirements.** The Contractor shall provide adequate lighting during any nighttime construction. A lighting plan shall be submitted by the Contractor and approved by the RPR

prior to the start of any nighttime work. All work shall be in accordance with the approved CSPP and lighting plan.

### **CONTRACTOR QUALITY CONTROL (CQC)**

**401-5.1 General.** The Contractor shall develop a Contractor Quality Control Program (CQCP) in accordance with Item C-100. No partial payment will be made for materials without an approved CQCP.

**401-5.2 Contractor quality control (QC) facilities.** The Contractor shall provide or contract for testing facilities in accordance with Item C-100. The RPR shall be permitted unrestricted access to inspect the Contractor's QC facilities and witness QC activities. The RPR will advise the Contractor in writing of any noted deficiencies concerning the QC facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to be adversely affecting the test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are satisfactorily corrected.

**401-5.3 Contractor QC testing.** The Contractor shall perform all QC tests necessary to control the production and construction processes applicable to these specifications and as set forth in the approved CQCP. The testing program shall include, but not necessarily be limited to, tests for the control of asphalt content, aggregate gradation, temperatures, aggregate moisture, field compaction, and surface smoothness. A QC Testing Plan shall be developed as part of the CQCP.

**a. Asphalt content.** A minimum of two tests shall be performed per day in accordance with ASTM D6307 or ASTM D2172 for determination of asphalt content. When using ASTM D6307, the correction factor shall be determined as part of the first test performed at the beginning of plant production; and as part of every tenth test performed thereafter. The asphalt content for the day will be determined by averaging the test results.

**b. Gradation.** Aggregate gradations shall be determined a minimum of twice per day from mechanical analysis of extracted aggregate in accordance with ASTM D5444, ASTM C136, and ASTM C117.

**c. Moisture content of aggregate.** The moisture content of aggregate used for production shall be determined a minimum of once per day in accordance with ASTM C566.

**d. Moisture content of asphalt.** The moisture content shall be determined once per day in accordance with AASHTO T329 or ASTM D1461.

**e. Temperatures.** Temperatures shall be checked, at least four times per day, at necessary locations to determine the temperatures of the dryer, the asphalt binder in the storage tank, the asphalt at the plant, and the asphalt at the job site.

**f. In-place density monitoring.** The Contractor shall conduct any necessary testing to ensure that the specified density is being achieved. A nuclear gauge may be used to monitor the pavement density in accordance with ASTM D2950.

#### **g. Smoothness for Contractor Quality Control.**

The Contractor shall perform smoothness testing in transverse and longitudinal directions daily to verify that the construction processes are producing pavement with variances less than 1/4 inch in 12 feet, identifying areas that may pond water which could lead to hydroplaning of aircraft. If the smoothness criteria is not met, appropriate changes and corrections to the construction process shall be made by the Contractor before construction continues.

The Contractor may use a 12-foot (3.7 m) "straightedge, a rolling inclinometer meeting the requirements of ASTM E2133 or rolling external reference device that can simulate a 12-foot (3.7m)

straightedge approved by the RPR. Straight-edge testing shall start with one-half the length of the straightedge at the edge of pavement section being tested and then moved ahead one-half the length of the straightedge for each successive measurement. Testing shall be continuous across all joints. The surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between the two high points. If the rolling inclinometer or external reference device is used, the data may be evaluated using either the FAA profile program, ProFAA, or FHWA ProVal, using the 12-foot straightedge simulation function.

Smoothness readings shall not be made across grade changes or cross slope transitions. The transition between new and existing pavement shall be evaluated separately for conformance with the plans.

**(1) Transverse measurements.** Transverse measurements shall be taken for each day's production placed. Transverse measurements shall be taken perpendicular to the pavement centerline each 50 feet (15 m) or more often as determined by the RPR. The joint between lanes shall be tested separately to facilitate smoothness between lanes.

**(2) Longitudinal measurements.** Longitudinal measurements shall be taken for each day's production placed. Longitudinal tests shall be parallel to the centerline of paving; at the center of paving lanes when widths of paving lanes are less than 20 feet (6 m); and at the third points of paving lanes when widths of paving lanes are 20 ft (6 m) or greater. When placement abuts previously placed material the first measurement shall start with one half the length of the straight edge on the previously placed material.

Deviations on the final surface course in either the transverse or longitudinal direction that will trap water greater than 1/4 inch (6 mm) shall be corrected with diamond grinding per paragraph 401-4.16 or by removing and replacing the surface course to full depth. Grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. All areas in which diamond grinding has been performed shall be subject to the final pavement thickness tolerances specified in paragraph 401-6.1d(3). Areas that have been ground shall be sealed with a surface treatment in accordance with Item P-608. To avoid the surface treatment creating any conflict with runway or taxiway markings, it may be necessary to seal a larger area.

Control charts shall be kept to show area of each day's placement and the percentage of corrective grinding required. Corrections to production and placement shall be initiated when corrective grinding is required. If the Contractor's machines and/or methods produce significant areas that need corrective actions in excess of 10 percent of a day's production, production shall be stopped until corrective measures are implemented by the Contractor.

**h. Grade.** Grade shall be evaluated daily to allow adjustments to paving operations when grade measurements do not meet specifications. As a minimum, grade shall be evaluated prior to and after the placement of the first lift and after placement of the surface lift.

Measurements will be taken at appropriate gradelines (as a minimum at center and edges of paving lane) and longitudinal spacing as shown on cross-sections and plans. The final surface of the pavement will not vary from the gradeline elevations and cross-sections shown on the plans by more than 1/2 inch (12 mm) vertically and 0.1 feet (30 mm) laterally. The documentation will be provided by the Contractor to the RPR by the end of the following working day.

Areas with humps or depressions that exceed grade or smoothness criteria and that retain water on the surface must be ground off provided the course thickness after grinding is not more than 1/2 inch (12 mm) less than the thickness specified on the plans. Grinding shall be in accordance with paragraph 401-4.16.

The Contractor shall repair low areas or areas that cannot be corrected by grinding by removal of deficient areas to the depth of the final course plus ½ inch and replacing with new material. Skin patching is not allowed.

**401-5.4 Sampling.** When directed by the RPR, the Contractor shall sample and test any material that appears inconsistent with similar material being sampled, unless such material is voluntarily removed and replaced or deficiencies corrected by the Contractor. All sampling shall be in accordance with standard procedures specified. Samples shall be cut with a core drilling machine, portable saws shall not be an acceptable method of sampling material.

**401-5.5 Control charts.** The Contractor shall maintain linear control charts for both individual measurements and range (i.e. difference between highest and lowest measurements) for aggregate gradation, asphalt content, and VMA. The VMA for each day will be calculated and monitored by the QC laboratory.

Control charts shall be posted in a location satisfactory to the RPR and kept current. As a minimum, the control charts shall identify the project number, the contract item number, the test number, each test parameter, the Action and Suspension Limits applicable to each test parameter, and the Contractor's test results. The Contractor shall use the control charts as part of a process control system for identifying potential problems and assignable causes before they occur. If the Contractor's projected data during production indicates a problem and the Contractor is not taking satisfactory corrective action, the RPR may suspend production or acceptance of the material.

**a. Individual measurements.** Control charts for individual measurements shall be established to maintain process control within tolerance for aggregate gradation, asphalt content, and VMA. The control charts shall use the job mix formula target values as indicators of central tendency for the following test parameters with associated Action and Suspension Limits:

**Control Chart Limits for Individual Measurements**

Sieve	Action Limit	Suspension Limit
3/4 inch (19.0 mm)	±6%	±9%
1/2 inch (12.5 mm)	±6%	±9%
3/8 inch (9.5 mm)	±6%	±9%
No. 4 (4.75 mm)	±6%	±9%
No. 16 (1.18 mm)	±5%	±7.5%
No. 50 (300 µm)	±3%	±4.5%
No. 200 (75 µm)	±2%	±3%
<b>Asphalt Content</b>	±0.45%	±0.70%
<b>Minimum VMA</b>	-0.5%	-1.0%

**b. Range.** Control charts shall be established to control gradation process variability. The range shall be plotted as the difference between the two test results for each control parameter. The Suspension Limits specified below are based on a sample size of  $n = 2$ . Should the Contractor elect to perform more than two tests per lot, the Suspension Limits shall be adjusted by multiplying the Suspension Limit by 1.18 for  $n = 3$  and by 1.27 for  $n = 4$ .



**Control Chart Limits Based on Range**

<b>Sieve</b>	<b>Suspension Limit</b>
1/2 inch (12.5 mm)	11%
3/8 inch (9.5 mm)	11%
No. 4 (4.75 mm)	11%
No. 16 (1.18 mm)	9%
No. 50 (300 µm)	6%
No. 200 (75 µm)	3.5%
<b>Asphalt Content</b>	0.8%

**c. Corrective Action.** The CQCP shall indicate that appropriate action shall be taken when the process is believed to be out of tolerance. The Plan shall contain rules to gauge when a process is out of control and detail what action will be taken to bring the process into control. As a minimum, a process shall be deemed out of control and production stopped and corrective action taken, if:

- (1) One point falls outside the Suspension Limit line for individual measurements or range; or
- (2) Two points in a row fall outside the Action Limit line for individual measurements.

**401-5.6 QC reports.** The Contractor shall maintain records and shall submit reports of QC activities daily, in accordance with Item C-100.

**MATERIAL ACCEPTANCE**

**401-6.1 Acceptance sampling and testing.** Unless otherwise specified, all acceptance sampling and testing necessary to determine conformance with the requirements specified in this section will be performed by the RPR at no cost to the Contractor except that coring as required in this section shall be completed and paid for by the Contractor.

**a. Quality assurance (QA) testing laboratory.** The QA testing laboratory performing these acceptance tests will be accredited in accordance with ASTM D3666. The QA laboratory accreditation will be current and listed on the accrediting authority's website. All test methods required for acceptance sampling and testing will be listed on the lab accreditation.

**b. Lot size.** A standard lot will be equal to one day's production divided into approximately equal sublots of between 400 to 600 tons. When only one or two sublots are produced in a day's production, the sublots will be combined with the production lot from the previous or next day.

**As the total project size is less than 3,000 tons, acceptable material will be paid for by the ton placed per day.**

Where more than one plant is simultaneously producing asphalt for the job, the lot sizes will apply separately for each plant.

**c. Asphalt air voids.** Plant-produced asphalt will be tested for air voids on a subplot basis.

**(1) Sampling.** Material from each subplot shall be sampled in accordance with ASTM D3665. Samples shall be taken from material deposited into trucks at the plant or at the job site in accordance with ASTM D979. The sample of asphalt may be put in a covered metal tin and placed in an oven for not less than 30 minutes nor more than 60 minutes to maintain the material at or above the compaction temperature as specified in the JMF.

**(2) Testing.** Air voids will be determined for each subplot in accordance with ASTM D3203 for a set of three compacted specimens prepared in accordance with ASTM D6925.

**d. In-place asphalt mat and joint density.** Each subplot will be tested for in-place mat and joint density as a percentage of the theoretical maximum density (TMD).

**(1) Sampling.** The Contractor will cut minimum 5 inch (125 mm) diameter samples in accordance with ASTM D5361. The Contractor shall furnish all tools, labor, and materials for cleaning, and filling the cored pavement. Laitance produced by the coring operation shall be removed immediately after coring, and core holes shall be filled within one day after sampling in a manner acceptable to the RPR. Samples shall be cut with a core drilling machine, portable saws shall not be an acceptable method of sampling material.

**(2) Bond.** Each lift of asphalt shall be bonded to the underlying layer. If cores reveal that the surface is not bonded, additional cores shall be taken as directed by the RPR to determine the extent of unbonded areas. Unbonded areas shall be removed by milling and replaced at no additional cost as directed by the RPR.

**(3) Thickness.** Thickness of each lift of surface course will be evaluated by the RPR for compliance to the requirements shown on the plans after any necessary corrections for grade. Measurements of thickness will be made using the cores extracted for each subplot for density measurement. The maximum allowable deficiency at any point will not be more than 1/4 inch (6 mm) less than the thickness indicated for the lift. Average thickness of lift, or combined lifts, will not be less than the indicated thickness. Where the thickness tolerances are not met, the lot or subplot shall be corrected by the Contractor at his expense by removing the deficient area and replacing with new pavement. The Contractor, at his expense, may take additional cores as approved by the RPR to circumscribe the deficient area.

**(4) Mat density.** One core shall be taken from each subplot. Core locations will be determined by the RPR in accordance with ASTM D3665. Cores for mat density shall not be taken closer than one foot (30 cm) from a transverse or longitudinal joint. The bulk specific gravity of each cored sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of each subplot sample by the TMD for that subplot.

**(5) Joint density.** One core centered over the longitudinal joint shall be taken for each subplot that has a longitudinal joint. Core locations will be determined by the RPR in accordance with ASTM D3665. The bulk specific gravity of each core sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of each joint density sample by the average TMD for the lot. The TMD used to determine the joint density at joints formed between lots will be the lower of the average TMD values from the adjacent lots.

#### 401-6.2 Acceptance criteria.

**a. General.** Acceptance will be based on the implementation of the Contractor Quality Control Program (CQCP) and the following characteristics of the asphalt and completed pavements: air voids, mat density, joint density, grade.

**b. Air Voids and Mat density.** Acceptance of each lot of plant produced material for mat density and air voids will be based on the percentage of material within specification limits (PWL). If the PWL of the lot equals or exceeds 90%, the lot will be acceptable. Acceptance and payment will be determined in accordance with paragraph 401-8.1.

**c. Joint density.** Acceptance of each lot of plant produced asphalt for joint density will be based on the PWL. If the PWL of the lot is equal to or exceeds 90%, the lot will be considered acceptable. If the PWL is less than 90%, the Contractor shall evaluate the reason and act accordingly. If the PWL is less than 80%, the Contractor shall cease operations and until the reason for poor compaction has been determined. If the PWL is less than 71%, the pay factor for the lot used to complete the joint will be

reduced by five (5) percentage points. This lot pay factor reduction will be incorporated and evaluated in accordance with paragraph 401-8.1.

**d. Grade.** The final finished surface of the pavement shall be surveyed to verify that the grade elevations ~~and cross sections~~ shown on the plans do not deviate more than 1/2 inch (12 mm) vertically or 0.1 feet (30 mm) laterally.

~~Cross sections of the pavement shall be taken at a minimum 50 foot (15 m) longitudinal spacing, at all longitudinal grade breaks, and at start and end of each lane placed. Minimum cross section grade points shall include grade at centerline, and edge of taxiway pavement.~~

The survey and documentation shall be stamped and signed by a licensed surveyor. Payment for sublots that do not meet grade for over 25% of the sublot shall not be more than 95%.

**e. Profilograph roughness for QA Acceptance.** Not used.

**401-6.3 Percentage of material within specification limits (PWL).** The PWL will be determined in accordance with procedures specified in Item C-110. The specification tolerance limits (L) for lower and (U) for upper are contained in Table 5.

**Table 5. Acceptance Limits for Air Voids and Density**

Test Property	Pavements Specification Tolerance Limits	
	L	U
<b>Air Voids Total Mix (%)</b>	2.0	5.0
<b>Surface Course Mat Density (%)</b>	92.8	-
<b>Base Course Mat Density (%)</b>	92.0	-
<b>Joint density (%)</b>	90.5	--

**a. Outliers.** All individual tests for mat density and air voids will be checked for outliers (test criterion) in accordance with ASTM E178, at a significance level of 5%. Outliers will be discarded, and the PWL will be determined using the remaining test values. The criteria in Table 5 is based on production processes which have a variability with the following standard deviations: Surface Course Mat Density (%), 1.30; Base Course Mat Density (%), 1.55; Joint Density (%), 1.55.

The Contractor should note that (1) 90 PWL is achieved when consistently producing a surface course with an average mat density of at least 94.5% with 1.30% or less variability, (2) 90 PWL is achieved when consistently producing a base course with an average mat density of at least 94.0% with 1.55% or less variability, and (3) 90 PWL is achieved when consistently producing joints with an average joint density of at least 92.5% with 1.55% or less variability.

#### **401-6.4 Resampling pavement for mat density.**

**a. General.** Resampling of a lot of pavement will only be allowed for mat density, and then, only if the Contractor requests same, in writing, within 48 hours after receiving the written test results from the RPR. A retest will consist of all the sampling and testing procedures contained in paragraphs 401-6.1d and 401-6.2b. Only one resampling per lot will be permitted.

(1) A redefined PWL will be calculated for the resampled lot. The number of tests used to calculate the redefined PWL will include the initial tests made for that lot plus the retests.

(2) The cost for resampling and retesting shall be borne by the Contractor.

**b. Payment for resampled lots.** The redefined PWL for a resampled lot will be used to calculate the payment for that lot in accordance with Table 6.

**c. Outliers.** Check for outliers in accordance with ASTM E178, at a significance level of 5%.

## METHOD OF MEASUREMENT

**401-7.1 Measurement.** Asphalt shall be measured by the number of tons of asphalt used in the accepted work. Batch weights or truck scale weights will be used to determine the basis for the tonnage.

## BASIS OF PAYMENT

**401-8.1 Payment.** Payment for a lot of asphalt meeting all acceptance criteria as specified in paragraph 401-6.2 shall be made based on results of tests for mat density and air voids. Payment for acceptable lots shall be adjusted according to paragraph 401-8.1c for mat density and air voids; and paragraph 401-6.2c for joint density, subject to the limitation that:

**a.** The total project payment for plant mix asphalt pavement shall not exceed 100 percent of the product of the contract unit price and the total number of tons (kg) of asphalt used in the accepted work.

**b.** The price shall be compensation for furnishing all materials, for all preparation, mixing, and placing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

**c. Basis of adjusted payment.** The pay factor for each individual lot shall be calculated in accordance with Table 6. A pay factor shall be calculated for both mat density and air voids. The lot pay factor shall be the higher of the two values when calculations for both mat density and air voids are 100% or higher. The lot pay factor shall be the product of the two values when only one of the calculations for either mat density or air voids is 100% or higher. The lot pay factor shall be the lower of the two values when calculations for both mat density and air voids are less than 100%. If PWL for joint density is less than 71% then the lot pay factor shall be reduced by 5% but be no higher than 95%.

For each lot accepted, the adjusted contract unit price shall be the product of the lot pay factor for the lot and the contract unit price. Payment shall be subject to the total project payment limitation specified in paragraph 401-8.1a. Payment in excess of 100% for accepted lots of asphalt shall be used to offset payment for accepted lots of asphalt pavement that achieve a lot pay factor less than 100%.

Payment for sublots which do not meet grade in accordance with paragraph 401-6.2d after correction for over 25% of the subplot shall be reduced by 5%.

**Table 6. Price adjustment schedule<sup>1</sup>**

<b>Percentage of material within specification limits (PWL)</b>	<b>Lot pay factor (percent of contract unit price)</b>
96 – 100	106
90 – 95	PWL + 10
75 – 89	0.5 PWL + 55
55 – 74	1.4 PWL – 12
Below 55	Reject <sup>2</sup>

<sup>1</sup> Although it is theoretically possible to achieve a pay factor of 106% for each lot, actual payment above 100% shall be subject to the total project payment limitation specified in paragraph 401-8.1a.

<sup>2</sup> The lot shall be removed and replaced. However, the RPR may decide to allow the rejected lot to remain. In that case, if the RPR and Contractor agree in writing that the lot shall not be removed, it shall be paid for at 50% of the contract unit price and the total project payment shall be reduced by the amount withheld for the rejected lot.

**d. Profilograph Roughness.** Not used.

#### **401-8.1 Payment.**

Payment will be made under:

Item P-401-8.1              Asphalt Surface Course – per ton

#### **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C29	Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate
ASTM C88	Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C117	Standard Test Method for Materials Finer than 75-μm (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C127	Standard Test Method for Density, Relative Density (Specific Gravity) and Absorption of Coarse Aggregate
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C142	Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM C566	Standard Test Method for Total Evaporable Moisture Content of Aggregate by Drying

ASTM D75	Standard Practice for Sampling Aggregates
ASTM D242	Standard Specification for Mineral Filler for Bituminous Paving Mixtures
ASTM D946	Standard Specification for Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D979	Standard Practice for Sampling Asphalt Paving Mixtures
ASTM D1073	Standard Specification for Fine Aggregate for Asphalt Paving Mixtures
ASTM D1188	Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Coated Samples
ASTM D2172	Standard Test Method for Quantitative Extraction of Bitumen from Asphalt Paving Mixtures
ASTM D1461	Standard Test Method for Moisture or Volatile Distillates in Asphalt Paving Mixtures
ASTM D2041	Standard Test Method for Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D2419	Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate
ASTM D2489	Standard Practice for Estimating Degree of Particle Coating of Bituminous-Aggregate Mixtures
ASTM D2726	Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixtures
ASTM D2950	Standard Test Method for Density of Bituminous Concrete in Place by Nuclear Methods
ASTM D3203	Standard Test Method for Percent Air Voids in Compacted Dense and Open Bituminous Paving Mixtures
ASTM D3381	Standard Specification for Viscosity-Graded Asphalt Cement for Use in Pavement Construction
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D3666	Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4552	Standard Practice for Classifying Hot-Mix Recycling Agents
ASTM D4791	Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D4867	Standard Test Method for Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D5361	Standard Practice for Sampling Compacted Asphalt Mixtures for Laboratory Testing

ASTM D5444	Standard Test Method for Mechanical Size Analysis of Extracted Aggregate
ASTM D5821	Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D6084	Standard Test Method for Elastic Recovery of Bituminous Materials by Ductilometer
ASTM D6307	Standard Test Method for Asphalt Content of Hot Mix Asphalt by Ignition Method
ASTM D6373	Standard Specification for Performance Graded Asphalt Binder
ASTM D6752	Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Automatic Vacuum Sealing Method
ASTM D6925	Standard Test Method for Preparation and Determination of the Relative Density of Hot Mix Asphalt (HMA) Specimens by Means of the SuperPave Gyratory Compactor.
ASTM D6926	Standard Practice for Preparation of Bituminous Specimens Using Marshall Apparatus
ASTM D6927	Standard Test Method for Marshall Stability and Flow of Bituminous Mixtures
ASTM D6995	Standard Test Method for Determining Field VMA based on the Maximum Specific Gravity of the Mix (Gmm)
ASTM E11	Standard Specification for Woven Wire Test Sieve Cloth and Test Sieves
ASTM E178	Standard Practice for Dealing with Outlying Observations
ASTM E1274	Standard Test Method for Measuring Pavement Roughness Using a Profilograph
ASTM E950	Standard Test Method for Measuring the Longitudinal Profile of Traveled Surfaces with an Accelerometer Established Inertial Profiling Reference
ASTM E2133	Standard Test Method for Using a Rolling Inclinator to Measure Longitudinal and Transverse Profiles of a Traveled Surface
American Association of State Highway and Transportation Officials (AASHTO)	
AASHTO M156	Standard Specification for Requirements for Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures.
AASHTO T329	Standard Method of Test for Moisture Content of Hot Mix Asphalt (HMA) by Oven Method
AASHTO T324	Standard Method of Test for Hamburg Wheel-Track Testing of Compacted Asphalt Mixtures
AASHTO T 340	Standard Method of Test for Determining the Rutting Susceptibility of Hot Mix Asphalt (APA) Using the Asphalt Pavement Analyzer (APA)

## Asphalt Institute (AI)

## Asphalt Institute Handbook MS-26, Asphalt Binder

AC 150/5370-10H

Asphalt Institute MS-2 Mix Design Manual, 7th Edition

AI State Binder Specification Database

Federal Highway Administration (FHWA)

Long Term Pavement Performance Binder Program

Advisory Circulars (AC)

AC 150/5320-6 Airport Pavement Design and Evaluation

FAA Orders

5300.1 Modifications to Agency Airport Design, Construction, and Equipment Standards

Software

FAARFIELD

**END OF ITEM P-401**



Page Intentionally Blank

### Item P-403 Asphalt Mix Pavement Base Course

\*This specification has been edited to include VDOT criteria for materials and placement

#### DESCRIPTION

**403-1.1** This item shall consist of pavement courses composed of mineral aggregate and asphalt binder mixed in a central mixing plant and placed on a prepared course in accordance with these specifications and shall conform to the lines, grades, thicknesses, and typical cross-sections shown on the plans. Each course shall be constructed to the depth, typical section, and elevation required by the plans and shall be rolled, finished, and approved before the placement of the next course.

#### MATERIALS

**403-2.1 Aggregate.** Aggregates shall consist of crushed stone, crushed gravel, crushed slag, screenings, natural sand and mineral filler, as required. The aggregates should have no known history of detrimental pavement staining due to ferrous sulfides, such as pyrite. Coarse aggregate is the material retained on the No. 4 (4.75 mm) sieve. Fine aggregate is the material passing the No. 4 (4.75 mm) sieve.

**a. Coarse aggregate.** Coarse aggregate shall consist of sound, tough, durable particles, free from films of matter that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. Coarse aggregate material requirements are given in the table below.

**Coarse Aggregate Material Requirements**

	<u>Coarse Aggregate Properties</u>			<u>Fine Aggregate Properties</u>	
	<u>Coarse Aggregate Angularity (CAA)</u>				
<u>Mix Type</u>	<u>1 Fractured Face</u>	<u>2 Fractured Faces</u>	<u>F&amp;E % by Weight</u>	<u>SE</u>	<u>FAA</u>
<u>IM-19.0D</u>	<u>85% Min</u>	<u>80% Min</u>	<u>10% Max<sup>1</sup></u>	<u>45% Min</u>	<u>45% Min</u>
	<u>Max LA Abrasion Loss</u>				
	<u>Magnesium Sulphate 100 Rev.</u>	<u>Freeze and Thaw, 500 Rev.</u>			
<u>Grade A</u>	<u>9</u>	<u>40</u>			

	Deleterious Material				
	% by Weight	AASHTO Test Method		% by Weight	AASHTO Test Method
Coal and Lignite	0.25	T113		-	-
Clay Lumps	0.25	T112		0.25	T112
Material passing No. 200 sieve by washing	1.00 <sup>2</sup>	T11		5.0 <sup>3</sup>	T11 and T21
Shale, mica, coated grains, soft or flaky particles	-	-		1.0	T113
Organic Material	-	-		0.0	T21
<b>NOTES</b>					
1. Flat and Elongated: 10 Percent measured at 5:1 on maximum to minimum dimension.					
2. Coarse Deleterious: When the material passing the No. 200 sieve by washing is dust of fracture, the percentage of deleterious material may be increased to 1.50 percent.					
3. Fine Deleterious: In the case of stone sand, if the material passing the No. 200 sieve is dust of fracture, essentially free from clay or shale, the percentages shown for use in concrete subject to abrasion and in other concrete may be increased to 5.0 percent and 7.0 percent, respectively.					

**b. Fine aggregate.** Fine aggregate shall consist of clean, sound, tough, durable, angular shaped particles produced by crushing stone, slag, or gravel and shall be free from coatings of clay, silt, or other objectionable matter. Natural (non-manufactured) sand may be used to obtain the gradation of the aggregate blend or to improve the workability of the mix. Fine aggregate material requirements are listed in the table above Sharp-edged natural sand or sand prepared from stone, gravel, or combination thereof, complying with AASHTO M6. Soundness loss shall be a maximum of 15% per AASHTO T103 or 25% (for surface and intermediate courses). Fine aggregate angularity (FAA) shall be tested in accordance with AASHTO T 304 (Method A) and sand equivalent (SE) in accordance with AASHTO T 176.

**c. Sampling.** ASTM D75 shall be used in sampling coarse and fine aggregate, and ASTM C183 shall be used in sampling mineral filler.

**403-2.2 Mineral filler.** Mineral filler (baghouse fines) may be added in addition to material naturally present in the aggregate. Mineral filler shall meet the requirements of ASTM D242.

#### Mineral filler Requirements

Material Test	Requirement	Standard
Plasticity Index	4 maximum	ASTM D4318

**403-2.3 Asphalt binder.** Asphalt binder shall conform to ASTM D6373 Performance Grade (PG) 82-22 bituminous cement conforming to the requirements of AASHTO Provisional Specification MP-1.

A certificate of compliance from the manufacturer shall be included with the mix design submittal.

The supplier's certified test report with test data indicating grade certification for the asphalt binder shall be provided to the RPR for each load at the time of delivery to the mix plant. A certified test report with test data indicating grade certification for the asphalt binder shall also be provided to the RPR for any modification of the asphalt binder after delivery to the mix plant and before use in the HMA.

**403-2.4 Anti-stripping agent.** Any anti-stripping agent or additive (anti-strip) shall be heat stable and shall not change the asphalt binder grade beyond specifications. Anti-strip shall be an approved material of the Department of Transportation of the State in which the project is located.

**403-2.5 Bond Breaker.** Fabric shall meet the requirements of AASHTO M 288 Class I fabric with elongation not less than 50% at the specified strengths, and a weight not less than 14.5 oz/sy. A certificate of compliance (COC) shall be provided by the fabric manufacturer that the material may be used as a bond breaker.

## COMPOSITION

**403-3.1 Composition of mixture.** The asphalt plant mix shall be composed of a mixture of well-graded aggregate, filler and anti-strip agent if required, and asphalt binder. The several aggregate fractions shall be sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of the job mix formula (JMF).

**403-3.2 Job mix formula (JMF) laboratory.** The laboratory used to develop the JMF shall possess a current certificate of accreditation, listing D3666 from a national accrediting authority and all test methods required for developing the JMF, and listed on the accrediting authority's website. A copy of the laboratory's current accreditation and accredited test methods shall be submitted to the RPR prior to start of construction.

**403-3.3 Job mix formula (JMF).** No hot-mixed asphalt (HMA) for payment shall be produced until a JMF has been approved in writing by the RPR.

a. Provide the indicated hot mix bituminous concrete mix indicated on the drawings and in Tables below

1. Aggregate gradation shall be tested in accordance with AASHTO T27.

### ASPHALT CONCRETE MIXTURES – DESIGN RANGE PERCENTAGE By Weight Passing Square Mesh Sieves

Mix Type	1	3/4	1/2	3/8	No. 4	No. 8	No. 30	No. 200
IM-19.0D	100	90-100	90 Max	-	-	28-49		2-8

**MIX DESIGN CRITERIA**

	<b>VTM</b> (%)	<b>VFA</b> (%)	<b>VFA</b> (%) <b>Production</b>	<b>Min.</b> <b>VM</b> <b>A</b>	<b>Fines</b>	<b>Number of Gyations</b>		
<b>Mix Type</b>	(Note 1)	<b>Design</b>	(Note 2)	(%)	(Note 3)	<b>N Design</b>		
<b>IM-19.0D</b>	2.0 – 5.0	69-76	64-81	13	0.6-1.2	65		

Note 1: Asphalt content should be selected at the 4.0 percent Air Voids.

Note 2: During production of an approved job mix, the VFA shall be controlled within these limits.

Note 3: Fines-Asphalt Ratio is based on effective asphalt content.

b. The job-mix-formula (JMF) shall be submitted to the RPR for approval prior to construction of the test strip. In support of the JMF, the Contractor shall submit SUPERPAVE design test data for the following minimum list:

1. Aggregate sieve analysis.
2. Percent of aggregate component comprising the aggregate blend.
3. Aggregate gradation after stripping bituminous from the mix for sample preparation.
4. VTM, VMA, VFA, and F/A percentages.
5. Mix specific gravity to 3 decimal places.
6. Mix temperature for testing - 310°F to 320°F; compaction temperature for testing shall be 295°F to 300°F.
7. Field correction factor.
8. SUPERPAVE design data shall be plotted on graphs provided by the software of the test equipment manufacturer illustrating that the JMF requirements have been met.

c. The JMF shall establish a single percentage of aggregate passing each required sieve, a single percentage of asphalt material to be added to the aggregate, a temperature at which the mixture is to be produced, and a temperature at which the mixture is to be compacted for SUPERPAVE testing according to the requirements of AASHTO PP28-99. All formulas shall remain in effect until modified in writing by the RPR.

d. The Contractor shall have a VDOT certified Asphalt Mix Design Technician for designing and adjusting mixes as necessary. The Asphalt Mix Design Technician or Asphalt Plant Level II Technician may perform testing of asphalt mixes. The Asphalt Mix Design Technician shall be responsible for reviewing and approving the results of all testing. The Asphalt Mix Design Technician shall be available and have direct communication with the plant for making necessary adjustments in the asphalt concrete mixes at the mixing plant. The Asphalt Mix Design Technician and Asphalt Plant Level II Technician shall each be capable of conducting any tests necessary to put the plant into operation; however, the Asphalt Mix Design Technician shall be responsible for producing a mixture that complies with the requirements of these Specifications.

The mixture shall be designed and compacted at the N design gyrations specified in Table 3. For surface mixes, permeability test data shall be submitted in accordance with VTM 120 using either single point verification or the regression method for each surface mix having a different gradation. If the average of the permeability results from the single point verification method exceeds  $150 \times 10^{-5}$  cm/sec, or if the regression method predicts a permeability exceeding  $150 \times 10^{-5}$  cm/sec at 7.5% voids, the Contractor shall redesign the mixture to produce a permeability number less than  $150 \times 10^{-5}$  cm/sec. A minimum of one permeability samples will be taken and test run in the first lot, and every other lot thereafter, and results submitted to the RPR.

e. Type SM-12.5A asphalt concrete shall consist of crushed stone, crushed slag, or crushed gravel and fine aggregate, slag or stone screenings or a combination thereof combined with asphalt cement. No more than 5 percent of the aggregate retained on the No. 4 sieve and no more than 20 percent of the total aggregate may be polish susceptible.

f. The mixture shall produce a tensile strength ratio (TSR) value not less than 0.80 for the design and production tests. The TSR value shall be determined in accordance with AASHTO T283, including a freeze-thaw cycle, (4 inch specimens compacted with Marshall hammer or 3.5 x 6 inch specimens when compacted with a gyratory), except that the 16 hour curing time requirement and 72 to 96 hour storage period will be waived. Design tests shall use the same materials that are to be used in the production mix and shall be conducted in a VDOT approved laboratory.

**403-3.4 Reclaimed Asphalt Pavement (RAP).** Reclaimed asphalt pavement shall consist of reclaimed asphalt pavement (RAP), coarse aggregate, fine aggregate, mineral filler, and asphalt. Recycled asphalt shingles (RAS) shall not be allowed. The RAP shall be of a consistent gradation and asphalt content and properties. When RAP is fed into the plant, the maximum RAP chunk size shall not exceed 1-1/2 inches (38 mm). The reclaimed asphalt mix shall be designed using procedures contained in the Asphalt Institute MS-2 Mix Design Manual, 7th Edition. The percentage of asphalt in the RAP shall be established for the mixture design according to ASTM D2172 using the appropriate dust correction procedure. The JMF shall meet the requirements of paragraph 403-3.3. RAP should only be used for shoulder surface course mixes and for any intermediate courses. The use of RAP containing Coal Tar shall not be allowed. Coal Tar surface treatments must be removed prior to recycling underlying asphalt material. The amount of RAP shall be limited to 30 percent.

In addition to the requirements of paragraph 403-3.3, the JMF shall indicate the percent of reclaimed asphalt pavement and the percent and grade of new asphalt binder.

For the PG graded asphalt binder selected in paragraph 403-2.3, adjust as follows:

- a. For 0-20% RAP, there is no change in virgin asphalt binder content.
- b. For >20 to 30% RAP, select asphalt binder one grade softer, i.e., PG 82-22 would soften to PG 76-28.

**403-3.5 Control strip.** Full production shall not begin until an acceptable control strip has been constructed and accepted in writing by the RPR. The Contractor shall prepare and place a quantity of asphalt according to the JMF. The underlying grade or pavement structure upon which the control strip is to be constructed shall be the same as the remainder of the course represented by the control strip.

The Contractor will not be allowed to place the control strip until the Contractor quality control program (CQCP), showing conformance with the requirements of paragraph 403-5.1, has been accepted, in writing, by the RPR.

The control strip will consist of at least 250 tons (227 metric tons) or 1/2 subplot, whichever is greater. The control strip shall be placed in two lanes of the same width and depth to be used in production with a longitudinal cold joint. The cold joint must be cut back in accordance with paragraph 403-4.13 using the same procedure that will be used during production. The cold joint for the control strip will be an exposed

construction joint at least four (4) hours old or when the mat has cooled to less than 160°F (71°C). The equipment used in construction of the control strip shall be the same type, configuration and weight to be used on the project.

The control strip shall be evaluated for acceptance as a single lot in accordance with the acceptance criteria in paragraph 403-6.1 and 403-6.2.

The control strip will be considered acceptable by the RPR if the gradation, asphalt content, and VMA are within the action limits specified in paragraph 403-5.5a; and Mat density greater than or equal to 94%, air voids 3.5% +/- 1%, and joint density greater than or equal to 92%.

If the control strip is unacceptable, necessary adjustments to the JMF, plant operation, placing procedures, and/or rolling procedures shall be made and another control strip shall be placed. Unacceptable control strips shall be removed at the Contractor's expense.

The control strip will be considered one lot for payment based upon the average of a minimum of 3 samples (no sublots required for control strip). Payment will only be made for an acceptable control strip in accordance with paragraph 403-8.1.

## CONSTRUCTION METHODS

**403-4.1 Weather limitations.** The asphalt shall not be placed upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 4. The temperature requirements may be waived by the RPR, if requested; however, all other requirements including compaction shall be met.

**Table 4. Surface Temperature Limitations of Underlying Course**

Mat Thickness	Base Temperature (Minimum)	
	Degrees F	Degrees C
3 inches (7.5 cm) or greater	40	4
Greater than 2 inches (50 mm) but less than 3 inches (7.5 cm)	45	7

**403-4.2 Asphalt plant.** Plants used for the preparation of asphalt shall conform to the requirements of American Association of State Highway and Transportation Officials (AASHTO) M156 including the following items:

**a. Inspection of plant.** The RPR, or RPR's authorized representative, shall have access, at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant: verifying weights, proportions, and material properties; and checking the temperatures maintained in the preparation of the mixtures.

**b. Storage bins and surge bins.** The asphalt mixture stored in storage and/or surge bins shall meet the same requirements as asphalt mixture loaded directly into trucks. Asphalt mixture shall not be stored in storage and/or surge bins for a period greater than twelve (12) hours. If the RPR determines there is an excessive heat loss, segregation or oxidation of the asphalt mixture due to temporary storage, temporary storage shall not be allowed.

**403-4.3 Aggregate stockpile management.** Aggregate stockpiles shall be constructed in such a manner that prevents segregation and intermixing of deleterious materials. Aggregates from different sources shall be stockpiled, weighed and batched separately at the concrete batch plant. Aggregates that have become segregated or mixed with earth or foreign material shall not be used.

A continuous supply of materials shall be provided to the work to ensure continuous placement.

**403-4.4 Hauling equipment.** Trucks used for hauling asphalt shall have tight, clean, and smooth metal beds. To prevent the asphalt from sticking to the truck beds, the truck beds shall be lightly coated with a minimum amount of paraffin oil, lime solution, or other material approved by the RPR. Petroleum products shall not be used for coating truck beds. Each truck shall have a suitable cover to protect the mixture from adverse weather. When necessary, to ensure that the mixture will be delivered to the site at the specified temperature, truck beds shall be insulated or heated and covers shall be securely fastened.

**403-4.4.1 Material transfer vehicle (MTV).** Material transfer Vehicles shall be required due to the improvement in smoothness and decrease in both physical and thermal segregation. To transfer the material from the hauling equipment to the paver, use a self-propelled, material transfer vehicle with a swing conveyor that can deliver material to the paver without making contact with the paver. The MTV shall be able to move back and forth between the hauling equipment and the paver providing material transfer to the paver, while allowing the paver to operate at a constant speed. The Material Transfer Vehicle will have remixing and storage capability to prevent physical and thermal segregation.

**403-4.5 Asphalt pavers.** Asphalt pavers shall be self-propelled with an activated heated screed, capable of spreading and finishing courses of asphalt that will meet the specified thickness, smoothness, and grade. The paver shall have sufficient power to propel itself and the hauling equipment without adversely affecting the finished surface. The asphalt paver shall be equipped with a control system capable of automatically maintaining the specified screed grade and elevation.

If the spreading and finishing equipment in use leaves tracks or indented areas, or produces other blemishes in the pavement that are not satisfactorily corrected by the scheduled operations, the use of such equipment shall be discontinued.

The paver shall be capable of paving to a minimum width specified in paragraph 401-4.11.

**403-4.6 Rollers.** The number, type, and weight of rollers shall be sufficient to compact the asphalt to the required density while it is still in a workable condition without crushing of the aggregate, depressions or other damage to the pavement surface. Rollers shall be in good condition, capable of operating at slow speeds to avoid displacement of the asphalt. All rollers shall be specifically designed and suitable for compacting asphalt concrete and shall be properly used. Rollers that impair the stability of any layer of a pavement structure or underlying soils shall not be used.

**403-4.6.1 Density device.** The Contractor shall have on site a density gauge during all paving operations in order to assist in the determination of the optimum rolling pattern, type of roller and frequencies, as well as to monitor the effect of the rolling operations during production paving. The Contractor shall also supply a qualified technician during all paving operations to calibrate the density gauge and obtain accurate density readings for all new asphalt. These densities shall be supplied to the RPR upon request at any time during construction. No separate payment will be made for supplying the density gauge and technician.

**403-4.7 Preparation of asphalt binder.** The asphalt binder shall be heated in a manner that will avoid local overheating and provide a continuous supply of the asphalt material to the mixer at a uniform temperature. The temperature of the unmodified asphalt binder delivered to the mixer shall be sufficient to provide a suitable viscosity for adequate coating of the aggregate particles, but shall not exceed 325°F (160°C) when added to the aggregate. The temperature of modified asphalt binder shall be no more than 350°F (175°C) when added to the aggregate.

**403-4.8 Preparation of mineral aggregate.** The aggregate for the asphalt shall be heated and dried. The maximum temperature and rate of heating shall be such that no damage occurs to the aggregates. The temperature of the aggregate and mineral filler shall not exceed 350°F (175°C) when the asphalt binder is added. Particular care shall be taken that aggregates high in calcium or magnesium content are not



damaged by overheating. The temperature shall not be lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.

**403-4.9 Preparation of asphalt mixture.** The aggregates and the asphalt binder shall be weighed or metered and introduced into the mixer in the amount specified by the JMF. The combined materials shall be mixed until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. Wet mixing time shall be the shortest time that will produce a satisfactory mixture, but not less than 25 seconds for batch plants. The wet mixing time for all plants shall be established by the Contractor, based on the procedure for determining the percentage of coated particles described in ASTM D2489, for each individual plant and for each type of aggregate used. The wet mixing time will be set to achieve 95% of coated particles. For continuous mix plants, the minimum mixing time shall be determined by dividing the weight of its contents at operating level by the weight of the mixture delivered per second by the mixer. The moisture content of all asphalt upon discharge shall not exceed 0.5%.

**403-4.10 Application of Prime and Tack Coat.** Immediately before placing the asphalt mixture, the underlying course shall be cleaned of all dust and debris.

A prime coat in accordance with Item P-602 shall be applied to aggregate base prior to placing the asphalt mixture.

A tack coat shall be applied in accordance with Item P-603 to all vertical and horizontal asphalt and concrete surfaces prior to placement of the first and each subsequent lift of asphalt mixture.

**403-4.11 Laydown plan, transporting, placing, and finishing.** Prior to the placement of the asphalt, the Contractor shall prepare a laydown plan with the sequence of paving lanes and width to minimize the number of cold joints; the location of any temporary ramps; laydown temperature; and estimated time of completion for each portion of the work (milling, paving, rolling, cooling, etc.). The laydown plan and any modifications shall be approved by the RPR.

Deliveries shall be scheduled so that placing and compacting of asphalt is uniform with minimum stopping and starting of the paver. Hauling over freshly placed material shall not be permitted until the material has been compacted, as specified, and allowed to cool to approximately ambient temperature. The Contractor, at their expense, shall be responsible for repair of any damage to the pavement caused by hauling operations.

Contractor shall survey each lift of asphalt surface course and certify to RPR that every lot of each lift meets the grade tolerances of paragraph 401-6.2e before the next lift can be placed.

Edges of existing asphalt pavement abutting the new work shall be saw cut and the cut off material and laitance removed. Apply a tack coat in accordance with P-603 before new asphalt material is placed against it.

The speed of the paver shall be regulated to eliminate pulling and tearing of the asphalt mat. Placement of the asphalt mix shall begin along the centerline of a crowned section or on the high side of areas with a one way slope unless shown otherwise on the laydown plan as accepted by the RPR. The asphalt mix shall be placed in consecutive adjacent lanes having a minimum width of 15 feet except where edge lanes require less width to complete the area. Additional screed sections attached to widen the paver to meet the minimum lane width requirements must include additional auger sections to move the asphalt mixture uniformly along the screed extension.

The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least 1 foot (30 cm); however, the joint in the surface top course shall be at the centerline of crowned pavements. Transverse joints in one course shall be offset by at least 10 feet (3 m) from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 10 feet (3 m). On

areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the asphalt may be spread and luted by hand tools.

The RPR may at any time, reject any batch of asphalt, on the truck or placed in the mat, which is rendered unfit for use due to contamination, segregation, incomplete coating of aggregate, or overheated asphalt mixture. Such rejection may be based on only visual inspection or temperature measurements. In the event of such rejection, the Contractor may take a representative sample of the rejected material in the presence of the RPR, and if it can be demonstrated in the laboratory, in the presence of the RPR, that such material was erroneously rejected, payment will be made for the material at the contract unit price.

Areas of segregation in the surface course, as determined by the RPR, shall be removed and replaced at the Contractor's expense. The area shall be removed by saw cutting and milling a minimum of the construction lift thickness as specified in paragraph 401-3.3, Table 2 for the approved mix design. The area to be removed and replaced shall be a minimum width of the paver and a minimum of 10 feet (3 m) long.

**403-4.12 Compaction of asphalt mixture.** After placing, the asphalt mixture shall be thoroughly and uniformly compacted by self-propelled rollers. The surface shall be compacted as soon as possible when the asphalt has attained sufficient stability so that the rolling does not cause undue displacement, cracking or shoving. The sequence of rolling operations and the type of rollers used shall be at the discretion of the Contractor. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any surface defects and/or displacement occurring as a result of the roller, or from any other cause, shall be corrected at the Contractor's expense.

Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until the surface is of uniform texture, true to grade and cross-section, and the required field density is obtained. To prevent adhesion of the asphalt to the roller, the wheels shall be equipped with a scraper and kept moistened with water as necessary.

In areas not accessible to the roller, the mixture shall be thoroughly compacted with approved power tampers.

Any asphalt that becomes loose and broken, mixed with dirt, contains check-cracking, or in any way defective shall be removed and replaced with fresh hot mixture and immediately compacted to conform to the surrounding area. This work shall be done at the Contractor's expense. Skin patching shall not be allowed.

**403-4.13 Joints.** The formation of all joints shall be made in such a manner as to ensure a continuous bond between the courses and obtain the required density. All joints shall have the same texture as other sections of the course and meet the requirements for smoothness and grade.

The roller shall not pass over the unprotected end of the freshly laid asphalt except when necessary to form a transverse joint. When necessary to form a transverse joint, it shall be made by means of placing a bulkhead or by tapering the course. The tapered edge shall be cut back to its full depth and width on a straight line to expose a vertical face prior to placing the adjacent lane. In both methods, all contact surfaces shall be coated with an asphalt tack coat before placing any fresh asphalt against the joint.

Longitudinal joints which have been left exposed for more than four (4) hours; the surface temperature has cooled to less than 175°F (80°C); or are irregular, damaged, uncompacted or otherwise defective shall be cut back with a cutting wheel or pavement saw a maximum of 3 inches (75 mm) to expose a clean, sound, uniform vertical surface for the full depth of the course. All cutback material and any laitance produced from cutting joints shall be removed from the project. An asphalt tack coat or other product approved by the RPR shall be applied to the clean, dry joint prior to placing any additional fresh asphalt against the joint. The cost of this work shall be considered incidental to the cost of the asphalt.

**403-4.14 Saw-cut grooving.** Saw-cut grooving is not required.

**403-4.15 Diamond grinding.** Diamond grinding shall be completed prior to pavement grooving. Diamond grinding shall be accomplished by sawing with saw blades impregnated with industrial diamond abrasive.

Diamond grinding shall be performed with a machine designed specifically for diamond grinding capable of cutting a path at least 3 feet (0.9 m) wide. The saw blades shall be 1/8-inch (3-mm) wide with a minimum of 55 to 60 blades per 12 inches (300 mm) of cutting head width; grooves between 0.090 and 0.130 inches (2 and 3.5 mm) wide; and peaks and ridges approximately 1/32 inch (1 mm) higher than the bottom of the grinding cut. The actual number of blades will be determined by the Contractor and depend on the hardness of the aggregate. Equipment or grinding procedures that causes ravels, aggregate fractures, spalls or disturbance to the pavement will not be permitted.

Grinding will be tapered in all directions to provide smooth transitions to areas not requiring grinding. The slurry resulting from the grinding operation shall be continuously removed and the pavement left in a clean condition. The Contractor shall apply a surface treatment per P-608 to all areas that have been subject to grinding.

**403-4.16 Nighttime Paving Requirements.** The Contractor shall provide adequate lighting during any nighttime construction. A lighting plan shall be submitted by the Contractor and approved by the RPR prior to the start of any nighttime work. All work shall be in accordance with the approved CSPP and lighting plan.

### **CONTRACTOR QUALITY CONTROL (CQC)**

**403-5.1 General.** The Contractor shall develop a CQCP in accordance with Item C-100. No partial payment will be made for materials that are subject to specific QC requirements without an approved CQCP.

**403-5.2 Contractor quality control (QC) facilities.** The Contractor shall provide or contract for testing facilities in accordance with Item C-100. The RPR shall be permitted unrestricted access to inspect the Contractor's QC facilities and witness QC activities. The RPR will advise the Contractor in writing of any noted deficiencies concerning the QC facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to be adversely affecting the test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are satisfactorily corrected.

**403-5.3 Quality Control (QC) testing.** The Contractor shall perform all QC tests necessary to control the production and construction processes applicable to these specifications and as set forth in the approved CQCP. The testing program shall include, but not necessarily be limited to, tests for the control of asphalt content, aggregate gradation, temperatures, aggregate moisture, field compaction, and surface smoothness. A QC Testing Plan shall be developed as part of the CQCP.

**a. Asphalt content.** A minimum of two tests shall be performed per day in accordance with ASTM D6307 or ASTM D2172 for determination of asphalt content. When using ASTM D6307, the correction factor shall be determined as part of the first test performed at the beginning of plant production; and as part of every tenth test performed thereafter. The asphalt content for the day will be determined by averaging the test results.

**b. Gradation.** Aggregate gradations shall be determined a minimum of twice per lot from mechanical analysis of extracted aggregate in accordance with ASTM D5444 and ASTM C136, and ASTM C117.

**c. Moisture content of aggregate.** The moisture content of aggregate used for production shall be determined a minimum of once per lot in accordance with ASTM C566.

**d. Moisture content of asphalt.** The moisture content of the asphalt shall be determined once per lot in accordance with AASHTO T329 or ASTM D1461.

**e. Temperatures.** Temperatures shall be checked, at least four times per lot, at necessary locations to determine the temperatures of the dryer, the asphalt binder in the storage tank, the asphalt at the plant, and the asphalt at the job site.

**f. In-place density monitoring.** The Contractor shall conduct any necessary testing to ensure that the specified density is being achieved. A nuclear gauge may be used to monitor the pavement density in accordance with ASTM D2950.

**g. Smoothness for Contractor Quality Control.**

The Contractor shall perform smoothness testing in transverse and longitudinal directions daily to verify that the construction processes are producing pavement with variances less than ¼ inch in 12 feet, identifying areas that may pond water which could lead to hydroplaning of aircraft. If the smoothness criteria is not met, appropriate changes and corrections to the construction process shall be made by the Contractor before construction continues.

The Contractor may use a 12-foot (3.7 m) “straightedge, a rolling inclinometer meeting the requirements of ASTM E2133 or rolling external reference device that can simulate a 12-foot (3.7m) straightedge approved by the RPR. Straight-edge testing shall start with one-half the length of the straightedge at the edge of pavement section being tested and then moved ahead one-half the length of the straightedge for each successive measurement. Testing shall be continuous across all joints. The surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between the two high points. If the rolling inclinometer or external reference device is used, the data may be evaluated using the FAA profile program, ProFAA, using the 12-foot straightedge simulation function.

Smoothness readings shall not be made across grade changes or cross slope transitions. The transition between new and existing pavement and between the start and stop of lanes place shall be evaluated separately for conformance with the plans.

**(1) Transverse measurements.** Transverse measurements shall be taken for each day’s production placed. Transverse measurements will be taken perpendicular to the pavement centerline each 50 feet (15 m) or more often as determined by the RPR. The joint between lanes shall be tested separately to facilitate smoothness between lanes.

**(2) Longitudinal measurements.** Longitudinal measurements shall be taken for each day’s production placed. Longitudinal tests will be parallel to the centerline of paving; at the center of paving lanes when widths of paving lanes are less than 20 feet (6 m); and at the third points of paving lanes when widths of paving lanes are 20 ft (6 m) or greater. When placement abuts previously placed material the first measurement shall start with one half the length of the straight edge on the previously placed material.

Deviations on the final surface course in either the transverse or longitudinal direction that will trap water greater than 1/4 inch (6 mm) shall be corrected with diamond grinding per paragraph 403-4.15 or by removing and replacing the surface course to full depth. Grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. All areas in which diamond grinding has been performed shall be subject to the final pavement thickness tolerances specified in paragraph 401-6.1d(3). Areas that have been ground shall be sealed with a surface treatment in accordance with Item P-608. To avoid the surface treatment creating any conflict with runway or taxiway markings, it may be necessary to seal a larger area.

Control charts shall be kept to show area of each day’s placement and the percentage of corrective grinding required. Corrections to production and placement shall be initiated when corrective

grinding is required. If the Contractor's machines and/or methods produce significant areas that need corrective actions in excess of 10 percent of a day's production, production shall be stopped until corrective measures are implemented by the Contractor.

**h. Grade.** Grade shall be evaluated daily to allow adjustments to paving operations when grade measurements do not meet specifications. As a minimum, grade shall be evaluated prior to the placement of the first lift and then prior to and after placement of the surface lift.

Measurements will be taken at appropriate gradelines (as a minimum at center and edges of paving lane) and longitudinal spacing as shown on cross-sections and plans. The final surface of the pavement will not vary from the gradeline elevations and cross-sections shown on the plans by more than 1/2 inch (12 mm) vertically. The documentation will be provided by the Contractor to the RPR within 24 hours.

Areas with humps or depressions that exceed grade or smoothness criteria and that retain water on the surface must be ground off provided the course thickness after grinding is not more than 1/2 inch (12 mm) less than the thickness specified on the plans. Grinding shall be in accordance with paragraph 403-4.15.

The Contractor shall repair low areas or areas that cannot be corrected by grinding by removal of deficient areas to the depth of the final course plus 1/2 inch and replacing with new material. Skin patching is not allowed.

**403-5.4 Sampling.** When directed by the RPR, the Contractor shall sample and test any material that appears inconsistent with similar material being sampled, unless such material is voluntarily removed and replaced or deficiencies corrected by the Contractor. All sampling shall be in accordance with standard procedures specified. Samples shall be cut with a core drilling machine, portable saws shall not be an acceptable method of sampling material.

**403-5.5 Control charts.** The Contractor shall maintain linear control charts both for individual measurements and range (i.e., difference between highest and lowest measurements) for aggregate gradation, asphalt content, and VMA. The VMA for each day shall be calculated and monitored by the QC laboratory.

Control charts shall be posted in a location satisfactory to the RPR and kept current. As a minimum, the control charts shall identify the project number, the contract item number, the test number, each test parameter, the Action and Suspension Limits applicable to each test parameter, and the Contractor's test results. The Contractor shall use the control charts as part of a process control system for identifying potential problems and assignable causes before they occur. If the Contractor's projected data during production indicates a problem and the Contractor is not taking satisfactory corrective action, the RPR may suspend production or acceptance of the material.

**a. Individual measurements.** Control charts for individual measurements shall be established to maintain process control within tolerance for aggregate gradation, asphalt content, and VMA. The control charts shall use the JMF target values as indicators of central tendency for the following test parameters with associated Action and Suspension Limits:

**Control Chart Limits for Individual Measurements**

Sieve	Action Limit	Suspension Limit
3/4 inch (19.0 mm)	±6%	±9%
1/2 inch (12.5 mm)	±6%	±9%
3/8 inch (9.5 mm)	±6%	±9%
No. 4 (4.75 mm)	±6%	±9%
No. 16 (1.18 mm)	±5%	±7.5%
No. 50 (300 µm)	±3%	±4.5%
No. 200 (75 µm)	±2%	±3%
Asphalt Content	±0.45%	±0.70%
Minimum VMA	-0.5%	-1.0%

**b. Range.** Control charts for range shall be established to control process variability for the test parameters and Suspension Limits listed below. The range shall be computed for each lot as the difference between the two test results for each control parameter. The Suspension Limits specified below are based on a sample size of  $n = 2$ . Should the Contractor elect to perform more than two tests per lot, the Suspension Limits shall be adjusted by multiplying the Suspension Limit by 1.18 for  $n = 3$  and by 1.27 for  $n = 4$ .

**Control Chart Limits Based on Range**  
( $n = 2$ )

Sieve	Suspension Limit
1/2 inch (12.5 mm)	11%
3/8 inch (9.5 mm)	11%
No. 4 (4.75 mm)	11%
No. 16 (1.18 mm)	9%
No. 50 (300 µm)	6%
No. 200 (75 µm)	3.5%
Asphalt Content	0.8%

**c. Corrective action.** The CQCP shall indicate that appropriate action shall be taken when the process is believed to be out of tolerance. The Plan shall contain sets of rules to gauge when a process is out of control and detail what action will be taken to bring the process into control. As a minimum, a process shall be deemed out of control and production stopped and corrective action taken, if:

- (1) One point falls outside the Suspension Limit line for individual measurements or range; or
- (2) Two points in a row fall outside the Action Limit line for individual measurements.

**403-5.6 Quality control (QC) reports.** The Contractor shall maintain records and shall submit reports of QC activities daily, in accordance with the CQCP described in Item C-100.

**MATERIAL ACCEPTANCE**

**403-6.1. Quality Assurance Acceptance sampling and testing.** Unless otherwise specified, all acceptance sampling and testing necessary to determine conformance with the requirements specified in

this section will be performed by the RPR at no cost to the Contractor except that coring as required in this section shall be completed and paid for by the Contractor.

**a. Quality Assurance (QA) testing laboratory.** The QA testing laboratory performing these acceptance tests will be accredited in accordance with ASTM D3666. The QA laboratory accreditation will be current and listed on the accrediting authority's website. All test methods required for acceptance sampling and testing will be listed on the lab accreditation.

**b. Lot Size.** A standard lot will be equal to one day's production divided into approximately equal sublots of between 400 to 600 tons. When only one or two sublots are produced in a day's production, the sublots will be combined with the production lot from the previous or next day.

Where more than one plant is simultaneously producing asphalt for the job, the lot sizes will apply separately for each plant.

**c. Asphalt air voids.** Plant-produced asphalt will be tested for air voids on a subplot basis.

**(1) Sampling.** Material from each subplot shall be sampled in accordance with ASTM D3665. Samples shall be taken from material deposited into trucks at the plant or at the job site in accordance with ASTM D979. The sample of asphalt may be put in a covered metal tin and placed in an oven for not less than 30 minutes nor more than 60 minutes to maintain the material at or above the compaction temperature as specified in the JMF.

**(2) Testing.** Air voids will be determined for each subplot in accordance with ASTM D3203 for a set of three compacted specimens prepared in accordance with ASTM D6925.

**d. In-place asphalt mat and joint density.** Each subplot will be tested for in-place mat and joint density as a percentage of the theoretical maximum density (TMD).

**(1) Sampling.** The Contractor will cut minimum 5 inches (125 mm) diameter samples in accordance with ASTM D5361. The Contractor shall furnish all tools, labor, and materials for cleaning, and filling the cored pavement. Laitance produced by the coring operation shall be removed immediately after coring, and core holes shall be filled within one day after sampling in a manner acceptable to the RPR.

**(2) Bond.** Each lift of asphalt shall be bonded to the underlying layer. If cores reveal that the surface is not bonded, additional cores shall be taken as directed by the RPR to determine the extent of unbonded areas. Unbonded areas shall be removed by milling and replaced at no additional cost as directed by the RPR.

**(3) Thickness.** Thickness of each lift of surface course will be evaluated by the RPR for compliance to the requirements shown on the plans after any necessary corrections for grade. Measurements of thickness will be made using the cores extracted for each subplot for density measurement. The maximum allowable deficiency at any point will not be more than 1/4 inch (6 mm) less than the thickness indicated for the lift. Average thickness of lift, or combined lifts, will not be less than the indicated thickness. Where the thickness tolerances are not met, the lot or subplot shall be corrected by the Contractor at his expense by removing the deficient area and replacing with new pavement. The Contractor, at his expense, may take additional cores as approved by the RPR to circumscribe the deficient area.

**(4) Mat density.** One core shall be taken from each subplot. Core locations will be determined by the RPR in accordance with ASTM D3665. Cores for mat density shall not be taken closer than one foot (30 cm) from a transverse or longitudinal joint. The bulk specific gravity of each cored sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of each subplot sample by the TMD for that subplot.

**(5) Joint density.** One core centered over the longitudinal joint shall be taken for each subplot which contains a longitudinal joint. Core locations will be determined by the RPR in accordance with

ASTM D3665. The bulk specific gravity of each core sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of each joint density sample by the average TMD for the lot. The TMD used to determine the joint density at joints formed between lots will be the lower of the average TMD values from the adjacent lots.

#### 403-6.2 Acceptance criteria.

**a. General.** Acceptance will be based on the implementation of the Contractor Quality Control Program (CQCP) and the following characteristics of the asphalt and completed pavements: air voids, mat density, joint density, grade.

**b. Air voids.** Acceptance of each lot of plant produced material for air voids will be based upon the average air void from the sublots. If the average air voids of the lot are equal to or greater than 2% and equal to or less than 5%, then the lot will be acceptable. If the average is below 2% or greater than 5%, the lot shall be removed and replaced at the Contractor's expense.

**c. Mat density.** Acceptance of each lot of plant produced material for mat density will be based on the average of all of the densities taken from the sublots. If the average mat density of the lot so established equals or exceeds 94%, the lot will be acceptable. If the average mat density of the lot is below 94%, the lot shall be removed and replaced at the Contractor's expense.

**d. Joint density.** Acceptance of each lot of plant produced asphalt for joint density will be based on the average of all of the joint densities taken from the sublots. If the average joint density of the lot so established equals or exceeds 92%, the lot will be acceptable. If the average joint density of the lot is less than 92%, the Contractor shall stop production and evaluate the method of compacting joints. Production may resume once the reason for poor compaction has been determined and appropriate measures have been taken to ensure proper compaction.

**e. Grade.** The final finished surface of the pavement of the completed project shall be surveyed to verify that the grade elevations and cross-sections shown on the plans do not deviate more than 1/2 inch (12 mm) vertically.

Cross-sections of the pavement shall be taken at the grid shown in the pavement spot elevation plans and at all grade breaks. ~~a minimum [ 50-foot (15-m) ] longitudinal spacing and at all longitudinal grade breaks. Minimum cross section grade points shall include grade at centerline, [ ± 10 feet of centerline ], and edge of [ runway ] [ taxiway ] pavement.~~

The survey and documentation shall be stamped and signed by a licensed surveyor. Payment for sublots that do not meet grade for over 25% of the subplot shall not be more than 95%.

#### 403-6.3 Resampling Pavement for Mat Density.

**a. General.** Resampling of a lot of pavement will only be allowed for mat density and then, only if the Contractor requests same in writing, within 48 hours after receiving the written test results from the RPR. A retest will consist of all the sampling and testing procedures contained in paragraphs 403-6.1. Only one resampling per lot will be permitted.

(1) A redefined mat density will be calculated for the resampled lot. The number of tests used to calculate the redefined mat density will include the initial tests made for that lot plus the retests.

(2) The cost for resampling and retesting shall be borne by the Contractor.

**b. Payment for resampled lots.** The redefined mat density for a resampled lot will be used to evaluate the acceptance of that lot in accordance with paragraph 403-6.2.

**c. Outliers.** Check for outliers in accordance with ASTM E178, at a significance level of 5%. Outliers will be discarded and density determined using the remaining test values.



**403-6.4 Leveling course.** The leveling course is the first variable thickness lift placed to correct surface irregularities prior to placement of subsequent courses. The leveling course shall meet the aggregate gradation in Table 2, paragraph 403-3.3. The leveling course shall meet the requirements of paragraph 403-3.3, 403-6.1b for air voids, but shall not be subject to the density requirements of paragraph 403-6.1c. The leveling course shall be compacted with the same effort used to achieve density of the control strip. The leveling course shall not exceed the lift thickness associated with each gradation in Table 2, paragraph 403-3.3.

## METHOD OF MEASUREMENT

**403-7.1 Measurement.** Plant mix asphalt mix pavement shall be measured by the number of tons of asphalt pavement used in the accepted work. Recorded batch weights or truck scale weights will be used to determine the basis for the tonnage.

## BASIS OF PAYMENT

**403-8.1 Payment.** Payment for a lot of asphalt mixture meeting all acceptance criteria as specified in paragraph 403-6.2 shall be made at the contract unit price per ton for asphalt. The price shall be compensation for furnishing all materials, for all preparation, mixing, and placing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-403-8.1	IM-19.0D Asphalt Base Course, Beneath Concrete Pavement – per ton
----------------	---

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### ASTM International (ASTM)

ASTM C29	Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate
ASTM C88	Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C117	Standard Test Method for Materials Finer than 75- $\mu$ m (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C127	Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C142	Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM C183	Standard Practice for Sampling and the Amount of Testing of Hydraulic Cement

ASTM C566	Standard Test Method for Total Evaporable Moisture Content of Aggregate by Drying
ASTM D75	Standard Practice for Sampling Aggregates
ASTM D242	Standard Specification for Mineral Filler for Bituminous Paving Mixtures
ASTM D946	Standard Specification for Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D979	Standard Practice for Sampling Bituminous Paving Mixtures
ASTM D1073	Standard Specification for Fine Aggregate for Bituminous Paving Mixtures
ASTM D1074	Standard Test Method for Compressive Strength of Bituminous Mixtures
ASTM D1461	Standard Test Method for Moisture or Volatile Distillates in Bituminous Paving Mixtures
ASTM D2041	Standard Test Method for Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D2172	Standard Test Method for Quantitative Extraction of Bitumen from Bituminous Paving Mixtures
ASTM D2419	Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate
ASTM D2489	Standard Practice for Estimating Degree of Particle Coating of Bituminous-Aggregate Mixtures
ASTM D2726	Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixtures
ASTM D2950	Standard Test Method for Density of Bituminous Concrete in Place by Nuclear Methods
ASTM D3203	Standard Test Method for Percent Air Voids in Compacted Dense and Open Bituminous Paving Mixtures
ASTM D3381	Standard Specification for Viscosity-Graded Asphalt Cement for Use in Pavement Construction
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D3666	Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D4125	Standard Test Methods for Asphalt Content of Bituminous mixtures by the Nuclear Method
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4552	Standard Practice for Classifying Hot-Mix Recycling Agents
ASTM D4791	Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate

ASTM D4867	Standard Test Method for Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D5444	Standard Test Method for Mechanical Size Analysis of Extracted Aggregate
ASTM D5581	Standard Test Method for Resistance to Plastic Flow of Bituminous Mixtures Using Marshall Apparatus (6 inch-Diameter Specimen)
ASTM D5821	Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D6307	Standard Test Method for Asphalt Content of Hot-Mix Asphalt by Ignition Method
ASTM D6373	Standard Specification for Performance Graded Asphalt Binder
ASTM D6752	Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Automatic Vacuum Sealing Method
ASTM D6925	Standard Test Method for Preparation and Determination of the Relative Density of Hot Mix Asphalt (HMA) Specimens by Means of the SuperPave Gyratory Compactor
ASTM D6926	Standard Practice for Preparation of Bituminous Specimens Using Marshall Apparatus
ASTM D6927	Standard Test Method for Marshall Stability and Flow of Bituminous Mixtures
ASTM D6995	Standard Test Method for Determining Field VMA based on the Maximum Specific Gravity of the Mix (Gmm)
ASTM E11	Standard Specification for Woven Wire Test Sieve Cloth and Test Sieves
ASTM E178	Standard Practice for Dealing with Outlying Observations
ASTM E2133	Standard Test Method for Using a Rolling Inclinator to Measure Longitudinal and Transverse Profiles of a Traveled Surface
American Association of State Highway and Transportation Officials (AASHTO)	
AASHTO M156	Standard Specification for Requirements for Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures
AASHTO T329	Standard Method of Test for Moisture Content of Hot Mix Asphalt (HMA) by Oven Method
AASHTO T 340	Standard Method of Test for Determining the Rutting Susceptibility of Hot Mix Asphalt (APA) Using the Asphalt Pavement Analyzer (APA)
Asphalt Institute (AI)	
MS-2	Mix Design Manual, 7th Edition
MS-26	Asphalt Binder Handbook AI State Binder Specification Database

AC 150/5370-10H

FAA Orders

5300.1

Modifications to Agency Airport Design, Construction, and Equipment  
Standards

Federal Highway Administration (FHWA)

Long Term Pavement Performance Binder program

Software

FAARFIELD

**END OF ITEM P-403**

Page Intentionally Blank

## Item P-501 Cement Concrete Pavement

### DESCRIPTION

**501-1.1** This work shall consist of pavement composed of cement concrete with reinforcement constructed on a prepared underlying surface in accordance with these specifications and shall conform to the lines, grades, thickness, and typical cross-sections shown on the plans. The terms cement concrete, hydraulic cement concrete, and concrete are interchangeable in this specification.

### MATERIALS

#### 501-2.1 Aggregates.

**a. Reactivity.** Fine and Coarse aggregates to be used in PCC on this project shall be tested and evaluated by the Contractor for alkali-aggregate reactivity in accordance with both ASTM C1260 and ASTM C1567. Tests must be representative of aggregate sources which will be providing material for production. ASTM C1260 and ASTM C1567 tests may be run concurrently.

(1) Coarse aggregate and fine aggregate shall be tested separately in accordance with ASTM C1260, however, the length of test shall be extended to 28 days (30 days from casting). Tests must have been completed within 6 months of the date of the concrete mix submittal.

(2) The combined coarse and fine aggregate shall be tested in accordance with ASTM C1567, modified for combined aggregates, using the proposed mixture design proportions of aggregates, cementitious materials, and/or specific reactivity reducing chemicals. If the expansion does not exceed 0.10% at 28 days, the proposed combined materials will be accepted. If the expansion is greater than 0.10% at 28 days, the aggregates will not be accepted unless adjustments to the combined materials mixture can reduce the expansion to less than 0.10% at 28 days, or new aggregates shall be evaluated and tested.

(3) If lithium nitrate is proposed for use with or without supplementary cementitious materials, the aggregates shall be tested in accordance with Corps of Engineers (COE) Concrete Research Division (CRD) C662 in lieu of ASTM C1567. If lithium nitrate admixture is used, it shall be nominal 30%  $\pm$  0.5% weight lithium nitrate in water. If the expansion does not exceed 0.10% at 28 days, the proposed combined materials will be accepted. If the expansion is greater than 0.10% at 28 days, the aggregates will not be accepted unless adjustments to the combined materials mixture can reduce the expansion to less than 0.10% at 28 days, or new aggregates shall be evaluated and tested.

**b. Fine aggregate.** Grading of the fine aggregate, as delivered to the mixer, shall conform to the requirements of ASTM C33 and the parameters identified in the fine aggregate material requirements below. Fine aggregate material requirements and deleterious limits are shown in the table below.

Fine Aggregate Material Requirements		
Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate	Loss after 5 cycles: 10% maximum using Sodium sulfate - or - 15% maximum using magnesium sulfate	ASTM C88
Sand Equivalent	45 minimum	ASTM D2419
Fineness Modulus (FM)	$2.50 \leq FM \leq 3.40$	ASTM C136
Limits for Deleterious Substances in Fine Aggregate for Concrete		
Clay lumps and friable particles	1.0% maximum	ASTM C142
Coal and lignite	0.5% using a medium with a density of Sp. Gr. of 2.0	ASTM C123
Total Deleterious Material	1.0% maximum	

**c. Coarse aggregate.** The maximum size coarse aggregate shall be 1-1/2 inch. Maximum nominal size is defined as one sieve size larger than the first sieve to retain more than 10 percent of the material.

Aggregates delivered to the mixer shall be clean, hard, uncoated aggregates consisting of crushed stone, crushed or uncrushed gravel, air-cooled iron blast furnace slag, crushed recycled concrete pavement, or a combination. The aggregates shall have no known history of detrimental pavement staining. Steel blast furnace slag shall not be permitted. Coarse aggregate material requirements and deleterious limits are shown in the table below; washing may be required to meet aggregate requirements.

#### Coarse Aggregate Material Requirements

Material Test	Requirement	Standard
Resistance to Degradation	Loss: 40% maximum	ASTM C131
Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate	Loss after 5 cycles: 12% maximum using Sodium sulfate - or - 18% maximum using magnesium sulfate	ASTM C88
Flat, Elongated, or Flat and Elongated Particles	8% maximum, by weight, of flat, elongated, or flat and elongated particles at 5:1 for any size group coarser than 3/8 (9.5 mm) sieve <sup>1</sup>	ASTM D4791
Bulk density of slag <sup>2</sup>	Weigh not less than 70 pounds per cubic foot (1.12 Mg/cubic meter)	ASTM C29
D-cracking (Freeze-Thaw) <sup>3</sup>	Durability factor $\geq 95$	ASTM C666

<sup>1</sup> A flat particle is one having a ratio of width to thickness greater than five (5); an elongated particle is one having a ratio of length to width greater than five (5).

<sup>2</sup> Only required if slag is specified.

<sup>3</sup> Coarse aggregate may only be accepted from sources that have a 20-year service history for the same gradation to be supplied with no history of D-Cracking. Aggregates that do not have a 20-year record of service free from major repairs (less than 5% of slabs replaced) in similar conditions without D-cracking shall not be used unless the material currently being produced has a durability factor greater than or equal to 95 per ASTM C666. The Contractor shall submit a current certification and test results to verify the aggregate acceptability. Test results will only be accepted from a State Department of Transportation (DOT) materials laboratory or an accredited laboratory. Certification and test results which are not dated or which are over one (1) year old or which are for different gradations will not be accepted.

The amount of deleterious material in the coarse aggregate shall not exceed the following limits:

#### Limits for Deleterious Substances in Coarse Aggregate

Deleterious material	ASTM	Percentage by Mass
Clay Lumps and friable particles	ASTM C142	1.0
Material finer than No. 200 sieve (75 µm)	ASTM C117	1.0 <sup>1</sup>
Lightweight particles	ASTM C123 using a medium with a density of Sp. Gr. of 2.0	0.5
Chert <sup>2</sup> (less than 2.40 Sp Gr.)	ASTM C123 using a medium with a density of Sp. Gr. of 2.40)	0.1 <sup>3</sup>

<sup>1</sup> The limit for material finer than 75-µm is allowed to be increased to 1.5% for crushed aggregates consisting of dust of fracture that is essentially free from clay or shale. Test results supporting acceptance of increasing limit to 1.5% with statement indicating material is dust of fracture must be submitted with Concrete mix. Acceptable techniques to characterizing these fines include methylene blue adsorption or X-ray diffraction analysis.

<sup>2</sup> Chert and aggregates with less than 2.4 specific gravity.

<sup>3</sup> ~~The limit for chert may be increased to 1.0 percent by mass in areas not subject to severe freeze and thaw.~~

**d. Combined aggregate gradation.** This specification is targeted for a combined aggregate gradation developed following the guidance presented in United States Air Force Engineering Technical Letter (ETL) 97-5: Proportioning Concrete Mixtures with Graded Aggregates for Rigid Airfield Pavements. Base the aggregate grading upon a combination of all the aggregates (coarse and fine) to be used for the mixture proportioning. Three aggregate sizes may be required to achieve an optimized combined gradation that will produce a workable concrete mixture for its intended use. Use aggregate gradations that produce concrete mixtures with well-graded or optimized aggregate combinations. The Contractor shall submit complete mixture information necessary to calculate the volumetric components of the mixture. The combined aggregate grading shall meet the following requirements:

(1) The materials selected and the proportions used shall be such that when the Coarseness Factor (CF) and the Workability Factor (WF) are plotted on a diagram as described in paragraph 501-2.1d(4) below, the point thus determined shall fall within the parallelogram described therein.

(2) The CF shall be determined from the following equation:

$$CF = \frac{(\text{cumulative percent retained on the } 3/8 \text{ in. (9.5 mm) sieve})(100)}{(\text{cumulative percent retained on the No. 8 (2.36 mm) sieve})}$$

(3) The WF is defined as the percent passing the No. 8 (2.36 mm) sieve based on the combined gradation. However, WF shall be adjusted, upwards only, by 2.5 percentage points for each 94 pounds (42 kg) of cementitious material per cubic meter yard greater than 564 pounds per cubic yard (335 kg per cubic meter).

(4) A diagram shall be plotted using a rectangular scale with WF on the Y-axis with units from 20 (bottom) to 45 (top), and with CF on the X-axis with units from 80 (left side) to 30 (right side). On this diagram a parallelogram shall be plotted with corners at the following coordinates (CF-75, WF-28), (CF-75, WF-40), (CF-45, WF-32.5), and (CF-45, WF-44.5). If the point determined by the intersection of the computed CF and WF does not fall within the above parallelogram, the grading of each size of aggregate used and the proportions selected shall be changed as necessary. The point determined by the plotting of the CF and WF may be adjusted during production  $\pm 3$  WF and  $\pm 5$  CF. Adjustments to gradation may not take the point outside of the parallelogram.



**e. Contractors combined aggregate gradation.** The Contractor shall submit their combined aggregate gradation using the following format:

**Contractor's Combined Aggregate Gradation**

<b>Sieve Size</b>	<b>Contractor's Concrete mix Gradation (Percent passing by weight)</b>
2 inch (50 mm)	*
1-1/2 inch (37.5 mm)	*
1 inch (25.0 mm)	*
3/4 inch (19.0 mm)	*
1/2 inch (12.5 mm)	*
3/8 inch (9.5 mm)	*
No. 4 (4.75 mm)	*
No. 8 (2.36 mm)	*
No. 16 (1.18 mm)	*
No. 30 (600 µm)	*
No. 50 (300 µm)	*
No. 100 (150 µm)	*

**501-2.2 Cement.** Cement shall conform to the requirements of ASTM C150 Type I or II; or ASTM C595 Type IP, IS, or IL; or ASTM C1157 Type GU, MH, or LH

**501-2.3 Cementitious materials.**

**a. Fly ash.** Fly ash shall meet the requirements of ASTM C618, with the exception of loss of ignition, where the maximum shall be less than 6%. Fly ash shall have a Calcium Oxide (CaO) content of less than 15% and a total alkali content less than 3% per ASTM C311. The Contractor shall furnish the previous three most recent, consecutive ASTM C618 reports for each source of fly ash proposed in the concrete mix, and shall furnish each additional report as they become available during the project. The reports can be used for acceptance or the material may be tested independently by the Resident Project Representative (RPR).

**b. Slag cement (ground granulated blast furnace (GGBF)).** Slag cement shall conform to ASTM C989, Grade 100 or Grade 120. Slag cement shall be used only at a rate between 25% and 55% of the total cementitious material by mass.

**c. Raw or calcined natural pozzolan.** Natural pozzolan shall be raw or calcined and conform to ASTM C618, Class N, including the optional requirements for uniformity and effectiveness in controlling Alkali-Silica reaction and shall have a loss on ignition not exceeding 6%. Class N pozzolan for use in mitigating Alkali-Silica Reactivity shall have a total available alkali content less than 3%.

**501-2.4 Joint seal.** The joint seal for the joints in the concrete pavement shall meet the requirements of Item P-604 and Item P-605 and shall be of the type specified in the plans.

**501-2.5 Isolation joint filler.** Premolded joint filler for isolation joints shall conform to the requirements of ASTM D1751 or ASTM D1752 and shall be where shown on the plans. The filler for each joint shall be furnished in a single piece for the full depth and width required for the joint, unless otherwise specified by the RPR. When the use of more than one piece is required for a joint, the abutting ends shall be

fastened securely and held accurately to shape by stapling or other positive fastening means satisfactory to the RPR.

**501-2.6 Steel reinforcement.** Reinforcing shall consist of welded wire fabric conforming to the requirements of ASTM A1064 Grade 70 or deformed and plain bars conforming to the requirements of ASTM A615 Grade 60.

**501-2.7 Dowel and tie bars.** Dowel bars shall be plain steel bars conforming to ASTM A615 and shall be free from burring or other deformation restricting slippage in the concrete.

**a. Dowel Bars.** Before delivery to the construction site each dowel bar shall be epoxy coated per ASTM A1078, Type 1, with a coating thickness after curing greater than 10 mils. Patched ends are not required for Type 1 coated dowels. The dowels shall be coated with a bond-breaker recommended by the manufacturer. Dowel sleeves or inserts are not permitted. Grout retention rings shall be fully circular metal or plastic devices capable of supporting the dowel until the grout hardens.

**b. Tie Bars.** Tie bars shall be deformed steel bars and conform to the requirements of ASTM A615. Tie bars designated as Grade 60 in ASTM A615 or ASTM A706 shall be used for construction requiring bent bars.

**501-2.8 Water.** Water used in mixing or curing shall be potable. If water is taken from other sources considered non-potable, it shall meet the requirements of ASTM C1602.

**501-2.9 Material for curing concrete.** Curing materials shall conform to one of the following specifications:

**a. Liquid membrane-forming compounds for curing concrete** shall conform to the requirements of ASTM C309, Type 2, Class A, or Class B.

**b. White polyethylene film for curing concrete** shall conform to the requirements of ASTM C171.

**c. White burlap-polyethylene sheeting for curing concrete** shall conform to the requirements of ASTM C171.

**d. Waterproof paper for curing concrete** shall conform to the requirements of ASTM C171.

**501-2.10 Admixtures.** Admixtures shall conform to the following specifications:

**a. Air-entraining admixtures.** Air-entraining admixtures shall meet the requirements of ASTM C260 and shall consistently entrain the air content in the specified ranges under field conditions. The air-entraining agent and any water reducer admixture shall be compatible.

**b. Water-reducing admixtures.** Water-reducing admixture shall meet the requirements of ASTM C494, Type A, B, or D.

**c. Other admixtures.** The use of set retarding and set-accelerating admixtures shall be approved by the RPR prior to developing the concrete mix. Retarding admixtures shall meet the requirements of ASTM C494, Type A, B, or D and set-accelerating admixtures shall meet the requirements of ASTM C494, Type C. Calcium chloride and admixtures containing calcium chloride shall not be used.

**d. Lithium Nitrate.** The lithium admixture shall be a nominal 30% aqueous solution of Lithium Nitrate, with a density of 10 pounds/gallon (1.2 kg/L), and shall have the approximate chemical form as shown below:

### Lithium Admixture

Constituent	Limit (Percent by Mass)
LiNO <sub>3</sub> (Lithium Nitrate)	30 ±0.5
SO <sub>4</sub> (Sulfate Ion)	0.1 (max)
Cl (Chloride Ion)	0.2 (max)
Na (Sodium Ion)	0.1 (max)
K (Potassium Ion)	0.1 (max)

The lithium nitrate admixture dispensing and mixing operations shall be verified and certified by the lithium manufacturer's representative.

**501-2.11 Epoxy-resin.** All epoxy-resin materials shall be two-component materials conforming to the requirements of ASTM C881, Class as appropriate for each application temperature to be encountered, except that in addition, the materials shall meet the following requirements:

- a. Material for use for embedding dowels and anchor bolts shall be Type IV, Grade 3.
- b. Material for use as patching materials for complete filling of spalls and other voids and for use in preparing epoxy resin mortar shall be Type III, Grade as approved.
- c. Material for use for injecting cracks shall be Type IV, Grade 1.
- d. Material for bonding freshly mixed Portland cement concrete or mortar or freshly mixed epoxy resin concrete or mortar to hardened concrete shall be Type V, Grade as approved.

**501-2.12 Bond Breaker.** Fabric shall meet the requirements of AASHTO M 288 Class I fabric with elongation not less than 50% at the specified strengths, with a weight not less than 14.5 oz/sy. A certificate of compliance (COC) shall be provided by the fabric manufacturer that the material may be used as a bond breaker.

### CONCRETE MIX

**501-3.1. General.** No concrete shall be placed until an acceptable concrete mix has been submitted to the RPR for review and the RPR has taken appropriate action. The RPR's review shall not relieve the Contractor of the responsibility to select and proportion the materials to comply with this section.

**501-3.2 Concrete Mix Laboratory.** The laboratory used to develop the concrete mix shall be accredited in accordance with ASTM C1077. The laboratory accreditation must be current and listed on the accrediting authority's website. All test methods required for developing the concrete mix must be included in the lab accreditation. A copy of the laboratory's current accreditation and accredited test methods shall be submitted to the RPR prior to start of construction.

**501-3.3 Concrete Mix Proportions.** Develop the mix using the procedures contained in Portland Cement Association (PCA) publication, "Design and Control of Concrete Mixtures." Concrete shall be proportioned to achieve a 28-day flexural strength that meets or exceeds the acceptance criteria contained in paragraph 501-6.6 for a flexural strength of 650 psi per ASTM C78.

The minimum cementitious material shall be adequate to ensure a workable, durable mix. The minimum cementitious material (cement plus fly ash, or slag cement) shall be 517 pounds per cubic yard. The ratio of water to cementitious material, including free surface moisture on the aggregates but not including moisture absorbed by the aggregates shall be between 0.38 – 0.45 by weight.

Flexural strength test specimens shall be prepared in accordance with ASTM C192 and tested in accordance with ASTM C78. At the start of the project, the Contractor shall determine an allowable slump as determined by ASTM C143 not to exceed 2 inches (50 mm) for slip-form placement. For fixed-form placement, the slump shall not exceed 3 inches (75 mm). For hand placement, the slump shall not exceed 4 inches (100 mm).

The results of the concrete mix shall include a statement giving the maximum nominal coarse aggregate size and the weights and volumes of each ingredient proportioned on a one cubic yard (meter) basis. Aggregate quantities shall be based on the mass in a saturated surface dry condition.

If a change in source(s) is made, or admixtures added or deleted from the mix, a new concrete mix must be submitted to the RPR for approval.

The RPR may request samples at any time for testing, prior to and during production, to verify the quality of the materials and to ensure conformance with the applicable specifications.

**501-3.4 Concrete Mix submittal.** The concrete mix shall be submitted to the RPR at least 30 days prior to the start of operations. The submitted concrete mix shall not be more than 180 days old and must use the materials to be used for production for the project. Production shall not begin until the concrete mix is approved in writing by the RPR.

Each of the submitted concrete mixes (i.e., slip form, side form machine finish and side form hand finish) shall be stamped or sealed by the responsible professional Engineer of the laboratory and shall include the following items and quantities as a minimum:

- Certified material test reports for aggregate in accordance with paragraph 501-2.1. Certified reports must include all tests required; reporting each test, test method, test result, and requirement specified (criteria).
- Combined aggregate gradations and analysis; and including plots of the fine aggregate fineness modulus.
- Reactivity Test Results.
- Coarse aggregate quality test results, including deleterious materials.
- Fine aggregate quality test results, including deleterious materials.
- Mill certificates for cement and supplemental cementitious materials.
- Certified test results for all admixtures, including Lithium Nitrate if applicable.
- Specified flexural strength, slump, and air content.
- Recommended proportions/volumes for proposed mixture and trial water-cementitious materials ratio, including actual slump and air content.
- Flexural and compressive strength summaries and plots, including all individual beam and cylinder breaks.
- Correlation ratios for acceptance testing and Contractor QC testing, when applicable.
- Historical record of test results documenting production standard deviation, when applicable.

#### **501-3.5 Cementitious materials.**

**a. Fly ash.** When fly ash is used as a partial replacement for cement, the replacement rate shall be determined from laboratory trial mixes, and shall be between 20 and 30% by weight of the total cementitious material. If fly ash is used in conjunction with slag cement the maximum replacement rate shall not exceed 10% by weight of total cementitious material.

**b. Slag cement (ground granulated blast furnace (GGBF)).** Slag cement may be used. The slag cement, or slag cement plus fly ash if both are used, may constitute between 25 to 55% of the total cementitious material by weight.

**c. Raw or calcined natural pozzolan.** Natural pozzolan may be used in the concrete mix. When pozzolan is used as a partial replacement for cement, the replacement rate shall be determined from laboratory trial mixes, and shall be between 20 and 30% by weight of the total cementitious material. If pozzolan is used in conjunction with slag cement the maximum replacement rate shall not exceed 10% by weight of total cementitious material.

### 501-3.6 Admixtures.

**a. Air-entraining admixtures.** Air-entraining admixture are to be added in such a manner that will ensure uniform distribution of the agent throughout the batch. The air content of freshly mixed air-entrained concrete shall be based upon trial mixes with the materials to be used in the work adjusted to produce concrete of the required plasticity and workability. The percentage of air in the mix shall be 5.5%. Air content shall be determined by testing in accordance with ASTM C231 for gravel and stone coarse aggregate and ASTM C173 for slag and other highly porous coarse aggregate.

**b. Water-reducing admixtures.** Water-reducing admixtures shall be added to the mix in the manner recommended by the manufacturer and in the amount necessary to comply with the specification requirements. Tests shall be conducted with the materials to be used in the work, in accordance with ASTM C494.

**c. Other admixtures.** Set controlling, and other approved admixtures shall be added to the mix in the manner recommended by the manufacturer and in the amount necessary to comply with the specification requirements. Tests shall be conducted with the materials to be used in the work, in accordance with ASTM C494.

**d. Lithium nitrate.** Lithium nitrate shall be added to the mix in the manner recommended by the manufacturer and in the amount necessary to comply with the specification requirements in accordance with paragraph 501-2.10d.

## CONSTRUCTION METHODS

**501-4.1 Control Strip.** The control strip(s) shall be to the next planned joint after the initial 250 feet (75 m) of each type of pavement construction (slip-form pilot lane, slip-form fill-in lane, or fixed form). The Contractor shall demonstrate, in the presence of the RPR, that the materials, concrete mix, equipment, construction processes, and quality control processes meet the requirements of the specifications. The concrete mixture shall be extruded from the paver meeting the edge slump tolerance and with little or no finishing. Pilot, fill-in, and fixed-form control strips will be accepted separately. Minor adjustments to the mix design may be required to place an acceptable control strip. The production mix will be the adjusted mix design used to place the acceptable control strip. Upon acceptance of the control strip by the RPR, the Contractor must use the same equipment, materials, and construction methods for the remainder of concrete paving. Any adjustments to processes or materials must be approved in advance by the RPR. Acceptable control strips will meet edge slump tolerance and surface acceptable with little or no finishing, air content within action limits, strength equal or greater than requirements of P501-3.3. The control strip will be considered one lot for payment (no sublots required for control strip). Payment will only be made for an acceptable control strip in accordance with paragraph 501-8.1 using a lot pay factor equal to 100.

**501-4.2 Equipment.** The Contractor is responsible for the proper operation and maintenance of all equipment necessary for handling materials and performing all parts of the work to meet this specification.

**a. Plant and equipment.** The plant and mixing equipment shall conform to the requirements of ASTM C94 and/or ASTM C685. **The Contractor shall conduct uniformity tests using the proposed concrete mix in the presence of the RPR and provide test results for acceptance prior to the control strip.** Each truck mixer **used for the delivery of concrete for hand placement** shall have attached in a prominent place a manufacturer's nameplate showing the capacity of the drum in terms of volume of mixed concrete and the speed of rotation of the mixing drum or blades. The truck mixers shall be examined daily for changes in condition due to accumulation of hard concrete or mortar or wear of blades. The pickup and throwover blades shall be replaced when they have worn down 3/4 inch (19 mm) or more. The Contractor shall have a copy of the manufacturer's design on hand showing dimensions and arrangement of blades in reference to original height and depth.

Equipment for transferring and spreading concrete from the transporting equipment to the paving lane in front of the finishing equipment shall be provided. The equipment shall be specially manufactured, self-propelled transfer equipment which will accept the concrete outside the paving lane and will spread it evenly across the paving lane in front of the paver and strike off the surface evenly to a depth which permits the paver to operate efficiently.

**b. Finishing equipment.**

**(1) Slip-form.** The standard method of constructing concrete pavements shall be with an approved slip-form paving equipment designed and operated to spread, consolidate, screed, and finish the freshly placed concrete in one complete pass of the machine so that the end result is a dense and homogeneous pavement which is achieved with a minimum of hand finishing. The paver-finisher shall be a heavy duty, self-propelled machine designed specifically for paving and finishing high quality concrete pavements.

**(2) Fixed-form.** **Alternatively, the concrete pavement can be placed with slip-form paving equipment using fixed forms.** ~~On projects requiring less than 10,000 cubic yards (7650 cubic meters) of concrete pavement or irregular areas at locations inaccessible to slip-form paving equipment.~~ **On irregular areas,** concrete pavement may be placed with **roller screed or vibratory screed equipped with internal vibrators** specifically designed for placement and finishing using stationary side forms. Methods and equipment shall be reviewed and accepted by the RPR. Hand screeding and float finishing may only be used on small irregular areas as allowed by the RPR.

**c. Vibrators.** Vibrator shall be the internal type. The rate of vibration of each vibrating unit shall be sufficient to consolidate the pavement without segregation or voids. The number, spacing, and frequency shall be as necessary to provide a dense and homogeneous pavement and meet the recommendations of American Concrete Institute (ACI) 309R, Guide for Consolidation of Concrete. Adequate power to operate all vibrators shall be available on the paver. The vibrators shall be automatically controlled so that they shall be stopped as forward motion ceases. The Contractor shall provide an electronic or mechanical means to monitor vibrator status. The checks on vibrator status shall occur a minimum of two times per day or when requested by the RPR.

Hand held vibrators may only be used in irregular areas and shall meet the recommendations of ACI 309R, Guide for Consolidation of Concrete.

**d. Concrete saws.** The Contractor shall provide sawing equipment adequate in number of units and power to complete the sawing to the required dimensions. The Contractor shall provide at least one standby saw in good working order and a supply of saw blades at the site of the work at all times during sawing operations.

**e. Fixed forms.** Straight side fixed forms shall be made of steel and shall be furnished in sections not less than 10 feet (3 m) in length. Forms shall be provided with adequate devices for secure settings so that when in place they will withstand, without visible spring or settlement, the impact and vibration of the consolidating and finishing equipment. Forms with battered top surfaces and bent, twisted or broken

forms shall not be used. Built-up forms shall not be used, except as approved by the RPR. The top face of the form shall not vary from a true plane more than 1/8 inch (3 mm) in 10 feet (3 m), and the upstanding leg shall not vary more than 1/4 inch (6 mm). The forms shall contain provisions for locking the ends of abutting sections together tightly for secure setting. Wood forms may be used under special conditions, when approved by the RPR. The forms shall extend the full depth of the pavement section.

**501-4.3 Form setting.** Forms shall be set to line and grade as shown on the plans, sufficiently in advance of the concrete placement, to ensure continuous paving operation. Forms shall be set to withstand, without visible spring or settlement, the impact and vibration of the consolidating and finishing equipment. Forms shall be cleaned and oiled prior to the concrete placement.

**501-4.4 Base surface preparation prior to placement.** Any damage to the prepared base, subbase, and subgrade shall be corrected full depth by the Contractor prior to concrete placement. The underlying surface shall be entirely free of frost when concrete is placed. The prepared grade shall be moistened with water, without saturating, immediately ahead of concrete placement to prevent rapid loss of moisture from concrete. Bond breaker shall be applied in accordance with 501-2.12.

**501-4.5 Handling, measuring, and batching material.** Aggregate stockpiles shall be constructed and managed in such a manner that prevents segregation and intermixing of deleterious materials. Aggregates from different sources shall be stockpiled, weighed and batched separately at the concrete batch plant. Aggregates that have become segregated or mixed with earth or foreign material shall not be used. All aggregates produced or handled by hydraulic methods, and washed aggregates, shall be stockpiled or binned for draining at least 12 hours before being batched. Store and maintain all aggregates at a uniform moisture content prior to use. A continuous supply of materials shall be provided to the work to ensure continuous placement.

**501-4.6 Mixing concrete.** The concrete may be mixed at the work site, in a central mix plant or in truck mixers. The mixer shall be of an approved type and capacity. Mixing time shall be measured from the time all materials are placed into the drum until the drum is emptied into the truck. All concrete shall be mixed and delivered to the site in accordance with the requirements of ASTM C94 or ASTM C685.

Mixed concrete from the central mixing plant shall be transported in truck mixers, truck agitators, or non-agitating trucks. The elapsed time from the addition of cementitious material to the mix until the concrete is discharged from the truck should not exceed 30 minutes when the concrete is hauled in non-agitating trucks, nor 90 minutes when the concrete is hauled in truck mixers or truck agitators. In no case shall the temperature of the concrete when placed exceed 90°F (32°C). Retempering concrete by adding water or by other means will not be permitted. With transit mixers additional water may be added to the batch materials and additional mixing performed to increase the slump to meet the specified requirements provided the addition of water is performed within 45 minutes after the initial mixing operations and provided the water/cementitious ratio specified is not exceeded.

**501-4.7 Weather Limitations on mixing and placing.** No concrete shall be mixed, placed, or finished when the natural light is insufficient, unless an adequate and approved artificial lighting system is operated.

**a. Cold weather.** Unless authorized in writing by the RPR, mixing and concreting operations shall be discontinued when a descending air temperature in the shade and away from artificial heat reaches 40°F (4°C) and shall not be resumed until an ascending air temperature in the shade and away from artificial heat reaches 35°F (2°C).

The aggregate shall be free of ice, snow, and frozen lumps before entering the mixer. The temperature of the mixed concrete shall not be less than 50°F (10°C) at the time of placement. Concrete shall not be placed on frozen material nor shall frozen aggregates be used in the concrete.

When concreting is authorized during cold weather, water and/or the aggregates may be heated to not more than 150°F (66°C). The apparatus used shall heat the mass uniformly and shall be arranged to preclude the possible occurrence of overheated areas which might be detrimental to the materials.

Curing during cold weather shall be in accordance with paragraph 501-4.13d.

**b. Hot weather.** During periods of hot weather when the maximum daily air temperature exceeds 85°F (30°C), the following precautions shall be taken.

The forms and/or the underlying surface shall be sprinkled with water immediately before placing the concrete. The concrete shall be placed at the coolest temperature practicable, and in no case shall the temperature of the concrete when placed exceed 90°F (32°C). The aggregates and/or mixing water shall be cooled as necessary to maintain the concrete temperature at or not more than the specified maximum.

The concrete placement shall be protected from exceeding an evaporation rate of 0.2 psf (0.98 kg/m<sup>2</sup> per hour) per hour. When conditions are such that problems with plastic cracking can be expected, and particularly if any plastic cracking begins to occur, the Contractor shall immediately take such additional measures as necessary to protect the concrete surface. If the Contractor's measures are not effective in preventing plastic cracking, paving operations shall be immediately stopped.

Curing during hot weather shall be in accordance with paragraph 501-4.13e.

**c. Temperature management program.** Prior to the start of paving operation for each day of paving, the Contractor shall provide the RPR with a Temperature Management Program for the concrete to be placed to assure that uncontrolled cracking is avoided. (Federal Highway Administration HIPERPAV 3 is one example of a temperature management program.) As a minimum, the program shall address the following items:

- (1) Anticipated tensile strains in the fresh concrete as related to heating and cooling of the concrete material.
- (2) Anticipated weather conditions such as ambient temperatures, wind velocity, and relative humidity; and anticipated evaporation rate using Figure 19-9, PCA, Design and Control of Concrete Mixtures.
- (3) Anticipated timing of initial sawing of joint.
- (4) Anticipated number and type of saws to be used.

**d. Rain.** The Contractor shall have available materials for the protection of the concrete during inclement weather. Such protective materials shall consist of rolled polyethylene sheeting at least 4 mils (0.1 mm) thick of sufficient length and width to cover the plastic concrete slab and any edges. The sheeting may be mounted on either the paver or a separate movable bridge from which it can be unrolled without dragging over the plastic concrete surface. When rain appears imminent, all paving operations shall stop and all available personnel shall begin covering the surface of the unhardened concrete with the protective covering.

**501-4.8 Concrete Placement.** At any point in concrete conveyance, the free vertical drop of the concrete from one point to another or to the underlying surface shall not exceed 3 feet (1 m). The finished concrete product must be dense and homogeneous, without segregation and conforming to the standards in this specification. Backhoes and grading equipment shall not be used to distribute the concrete in front of the paver. Front end loaders will not be used. All concrete shall be consolidated without voids or segregation, including under and around all load-transfer devices, joint assembly units, and other features embedded in the pavement. Hauling equipment or other mechanical equipment can be permitted on adjoining previously constructed pavement when the concrete strength reaches a flexural strength of 550 psi (3.8 MPa), based on the average of four field cured specimens per 2,000 cubic yards (1,530 cubic meters) of concrete placed. The Contractor must determine that the above minimum strengths are



adequate to protect the pavement from overloads due to the construction equipment proposed for the project.

The Contractor shall have available materials for the protection of the concrete during cold, hot and/or inclement weather in accordance with paragraph 501-4.7.

**a. Slip-form construction.** The concrete shall be distributed uniformly into final position by a self-propelled slip-form paver without delay. The alignment and elevation of the paver shall be regulated from outside reference lines established for this purpose. The paver shall vibrate the concrete for the full width and depth of the strip of pavement being placed and the vibration shall be adequate to provide a consistency of concrete that will stand normal to the surface with sharp well-defined edges. The sliding forms shall be rigidly held together laterally to prevent spreading of the forms. The plastic concrete shall be effectively consolidated by internal vibration with transverse vibrating units for the full width of the pavement and/or a series of equally placed longitudinal vibrating units. The space from the outer edge of the pavement to longitudinal unit shall not exceed 9 inches (23 cm) for slipform and at the end of the dowels for the fill-in lanes. The spacing of internal units shall be uniform and shall not exceed 18 inches (0.5 m).

The term internal vibration means vibrating units located within the specified thickness of pavement section.

The rate of vibration of each vibrating unit shall be sufficient to consolidate the pavement without segregation, voids, or vibrator trails and the amplitude of vibration shall be sufficient to be perceptible on the surface of the concrete along the entire length of the vibrating unit and for a distance of at least one foot (30 cm). The frequency of vibration or amplitude should be adjusted proportionately with the rate of travel to result in a uniform density and air content. The paving machine shall be equipped with a tachometer or other suitable device for measuring and indicating the actual frequency of vibrations.

The concrete shall be held at a uniform consistency. The slip-form paver shall be operated with as nearly a continuous forward movement as possible and all operations of mixing, delivering, and spreading concrete shall be coordinated to provide uniform progress with stopping and starting of the paver held to a minimum. If for any reason, it is necessary to stop the forward movement of the paver, the vibratory and tamping elements shall also be stopped immediately. No tractive force shall be applied to the machine, except that which is controlled from the machine.

When concrete is being placed adjacent to an existing pavement, that part of the equipment which is supported on the existing pavement shall be equipped with protective pads on crawler tracks or rubber-tired wheels on which the bearing surface is offset to run a sufficient distance from the edge of the pavement to avoid breaking the pavement edge.

Not more than 15% of the total free edge of each 500-foot (150 m) segment of pavement, or fraction thereof, shall have an edge slump exceeding 1/4 inch (6 mm), and none of the free edge of the pavement shall have an edge slump exceeding 3/8 inch (9 mm). (The total free edge of 500 feet (150 m) of pavement will be considered the cumulative total linear measurement of pavement edge originally constructed as nonadjacent to any existing pavement; that is, 500 feet (150 m) of paving lane originally constructed as a separate lane will have 1,000 feet (300 m) of free edge, 500 feet (150 m) of fill-in lane will have no free edge, etc.). The area affected by the downward movement of the concrete along the pavement edge shall be limited to not more than 18 inches (0.5 m) from the edge.

When excessive edge slump cannot be corrected before the concrete has hardened, the area with excessive edge slump will be removed the full width of the slip form lane and replaced at the expense of the Contractor as directed by the RPR.

**b. Fixed-form construction.** Forms shall be drilled in advance of being placed to line and grade to accommodate tie bars / dowel bars where these are specified. **Dowel bars in forms shall be positively fixed to meet alignment tolerances and facilitate removal of forms.**

Immediately in advance of placing concrete and after all subbase operations are completed, side forms shall be trued and maintained to the required line and grade for a distance sufficient to prevent delay in placing.

Side forms shall remain in place at least 12 hours after the concrete has been placed, and in all cases until the edge of the pavement no longer requires the protection of the forms. Curing compound shall be applied to the concrete immediately after the forms have been removed.

Side forms shall be thoroughly cleaned and coated with a release agent each time they are used and before concrete is placed against them.

Concrete shall be spread, screed, shaped and consolidated by one or more self-propelled machines. These machines shall uniformly distribute and consolidate concrete without segregation so that the completed pavement will conform to the required cross-section with a minimum of handwork.

The number and capacity of machines furnished shall be adequate to perform the work required at a rate equal to that of concrete delivery. The equipment must be specifically designed for placement and finishing using stationary side forms. Methods and equipment shall be reviewed and accepted by the RPR.

Concrete for the full paving width shall be effectively consolidated by internal vibrators. The rate of vibration of each vibrating unit shall be sufficient to consolidate the pavement without segregation, voids, or leaving vibrator trails.

Power to vibrators shall be connected so that vibration ceases when forward or backward motion of the machine is stopped.

**c. Consolidation.** Concrete shall be consolidated with the specified type of lane-spanning, gang-mounted, mechanical, immersion type vibrating equipment mounted in front of the paver, supplemented, in rare instances as specified, by hand-operated vibrators. The vibrators shall be inserted into the concrete to a depth that will provide the best full-depth consolidation but not closer to the underlying material than 2 inches (50 mm). Vibrators shall not be used to transport or spread the concrete. For each paving train, at least one additional vibrator spud, or sufficient parts for rapid replacement and repair of vibrators shall be maintained at the paving site at all times. Any evidence of inadequate consolidation (honeycomb along the edges, large air pockets, or any other evidence) or over-consolidation (vibrator trails, segregation, or any other evidence) shall require the immediate stopping of the paving operation and adjustment of the equipment or procedures as approved by the RPR.

If a lack of consolidation of the hardened concrete is suspected by the RPR, referee testing may be required. Referee testing of hardened concrete will be performed by the RPR by cutting cores from the finished pavement after a minimum of 24 hours curing. The RPR shall visually examine the cores for evidence of lack of consolidation. Density determinations will be made by the RPR based on the water content of the core as taken. ASTM C642 shall be used for the determination of core density in the saturated-surface dry condition. When required, referee cores will be taken at the minimum rate of one for each 500 cubic yards (382 m<sup>3</sup>) of pavement, or fraction. The Contractor shall be responsible for all referee testing cost if they fail to meet the required density.

The average density of the cores shall be at least 97% of the original concrete mix density, with no cores having a density of less than 96% of the original concrete mix density. Failure to meet the referee tests will be considered evidence that the minimum requirements for vibration are inadequate for the job conditions. Additional vibrating units or other means of increasing the effect of vibration shall be employed so that the density of the hardened concrete conforms to the above requirements.

**501-4.9 Strike-off of concrete and placement of reinforcement.** Following the placing of the concrete, it shall be struck off to conform to the cross-section shown on the plans and to an elevation that when the concrete is properly consolidated and finished, the surface of the pavement shall be at the elevation shown on the plans. When reinforced concrete pavement is placed in two layers, the bottom layer shall be struck off to such length and depth that the sheet of reinforcing steel fabric or bar mat may be laid full length on the concrete in its final position without further manipulation. The reinforcement shall then be placed directly upon the concrete, after which the top layer of the concrete shall be placed, struck off, and screed. If any portion of the bottom layer of concrete has been placed more than 30 minutes without being covered with the top layer or if initial set has taken place, it shall be removed and replaced with freshly mixed concrete at the Contractor's expense. When reinforced concrete is placed in one layer, the reinforcement may be positioned in advance of concrete placement or it may be placed in plastic concrete by mechanical or vibratory means after spreading.

Reinforcing steel, at the time concrete is placed, shall be free of mud, oil, or other organic matter that may adversely affect or reduce bond. Reinforcing steel with rust, mill scale or a combination of both will be considered satisfactory, provided the minimum dimensions, weight, and tensile properties of a hand wire-brushed test specimen are not less than the applicable ASTM specification requirements.

**501-4.10 Joints.** Joints shall be constructed as shown on the plans and in accordance with these requirements. All joints shall be constructed with their faces perpendicular to the surface of the pavement and finished or edged as shown on the plans. Joints shall not vary more than 1/2-inch (12 mm) from their designated position and shall be true to line with not more than 1/4-inch (6 mm) variation in 10 feet (3 m). The surface across the joints shall be tested with a 12-foot (3 m) straightedge as the joints are finished and any irregularities in excess of 1/4 inch (6 mm) shall be corrected before the concrete has hardened. All joints shall be so prepared, finished, or cut to provide a groove of uniform width and depth as shown on the plans.

**a. Construction.** Longitudinal construction joints shall be slip-formed or formed against side forms as shown in the plans.

Transverse construction joints shall be installed at the end of each day's placing operations and at any other points within a paving lane when concrete placement is interrupted for more than 30 minutes or it appears that the concrete will obtain its initial set before fresh concrete arrives. The installation of the joint shall be located at a planned contraction or expansion joint. If placing of the concrete is stopped, the Contractor shall remove the excess concrete back to the previous planned joint.

**b. Contraction.** Contraction joints shall be installed at the locations and spacing as shown on the plans. Contraction joints shall be installed to the dimensions required by forming a groove or cleft in the top of the slab while the concrete is still plastic or by sawing a groove into the concrete surface after the concrete has hardened. When the groove is formed in plastic concrete the sides of the grooves shall be finished even and smooth with an edging tool. If an insert material is used, the installation and edge finish shall be according to the manufacturer's instructions. The groove shall be finished or cut clean so that spalling will be avoided at intersections with other joints. Grooving or sawing shall produce a slot at least 1/8 inch (3 mm) wide and to the depth shown on the plans.

**c. Isolation (expansion).** Isolation joints shall be installed as shown on the plans. The premolded filler of the thickness as shown on the plans, shall extend for the full depth and width of the slab at the joint. The filler shall be fastened uniformly along the hardened joint face with no buckling or debris between the filler and the concrete interface, including a temporary filler **or oiled soiled metal cap** for the sealant reservoir at the top of the slab. The edges of the joint shall be finished and tooled while the concrete is still plastic

**d. Dowels and Tie Bars for Joints**

**(1) Tie bars.** Tie bars shall consist of deformed bars installed in joints as shown on the plans. Tie bars shall be placed at right angles to the centerline of the concrete slab and shall be spaced at intervals shown on the plans. They shall be held in position parallel to the pavement surface and in the middle of the slab depth and within the tolerances in paragraph 501-4.10(f.). When tie bars extend into an unpaved lane, they may be bent against the form at longitudinal construction joints, unless threaded bolt or other assembled tie bars are specified. Tie bars shall not be painted, greased, or enclosed in sleeves. When slip-form operations call for tie bars, two-piece hook bolts can be installed.

**(2) Dowel bars.** Dowel bars shall be placed across joints in the proper horizontal and vertical alignment as shown on the plans. The dowels shall be coated with a bond-breaker or other lubricant recommended by the manufacturer and approved by the RPR. Dowels bars at longitudinal construction joints shall be bonded in drilled holes.

**(3) Placing dowels and tie bars.** Horizontal spacing of dowels shall be within a tolerance of  $\pm 3/4$  inch (19 mm). The vertical location on the face of the slab shall be within a tolerance of  $\pm 1/2$  inch (12 mm). The method used to install dowels shall ensure that the horizontal and vertical alignment will not be greater than  $1/4$  inch per foot (6 mm per 0.3 m), except for those across the crown or other grade change joints. Dowels across crowns and other joints at grade changes shall be measured to a level surface. Horizontal alignment shall be checked perpendicular to the joint edge. The portion of each dowel intended to move within the concrete or expansion cap shall be wiped clean and coated with a thin, even film of lubricating oil or light grease before the concrete is placed. Dowels shall be installed as specified in the following subparagraphs.

**(a) Contraction joints.** Dowels and tie bars in longitudinal and transverse contraction joints within the paving lane shall be held securely in place by means of rigid metal frames or basket assemblies of an approved type. The basket assemblies shall be held securely in the proper location by means of suitable pins or anchors. Do not cut or crimp the dowel basket tie wires.

At the Contractor's option, dowels and tie bars in contraction joints may be installed by insertion into the plastic concrete using approved equipment and procedures per the paver manufacturer's design. Approval of installation methods will be based on the results of the control strip showing that the dowels and tie bars are installed within specified tolerances as verified by cores or non-destructive rebar location devices approved by the RPR.

**(b) Construction joints.** Install dowels and tie bars by the cast-in-place or the drill-and-dowel method. Installation by removing and replacing in preformed holes will not be permitted. Dowels and tie bars shall be prepared and placed across joints where indicated, correctly aligned, and securely held in the proper horizontal and vertical position during placing and finishing operations, by means of devices fastened to the forms.

**(c) Joints in hardened concrete.** Install dowels in hardened concrete by bonding the dowels into holes drilled into the concrete. The concrete shall have cured for seven (7) days or reached a minimum flexural strength of 450 psi (3.1 MPa) before drilling begins. Holes  $1/8$  inch (3 mm) greater in diameter than the dowels shall be drilled into the hardened concrete using rotary-core drills. Rotary-percussion drills may be used, provided that excessive spalling does not occur. Spalling beyond the limits of the grout retention ring will require modification of the equipment and operation. Depth of dowel hole shall be within a tolerance of  $\pm 1/2$  inch (12 mm) of the dimension shown on the drawings. On completion of the drilling operation, the dowel hole shall be blown out with oil-free, compressed air. Dowels shall be bonded in the drilled holes using epoxy resin. Epoxy resin shall be injected at the back of the hole before installing the dowel and extruded to the collar during insertion of the dowel so as to completely fill the void around the dowel. Application by buttering the dowel will not be permitted. The dowels shall be held in alignment at the collar of the hole by means of a suitable metal or plastic grout retention ring fitted around the dowel.

**e. Sawing of joints.** Sawing shall commence, without regard to day or night, as soon as the concrete has hardened sufficiently to permit cutting without chipping, spalling, or tearing and before uncontrolled shrinkage cracking of the pavement occurs and shall continue without interruption until all joints have been sawn. All slurry and debris produced in the sawing of joints shall be removed by vacuuming and washing. Curing compound or system shall be reapplied in the initial saw-cut and maintained for the remaining cure period.

Joints shall be cut in locations as shown on the plans. The initial joint cut shall be a minimum 1/8 inch (3 mm) wide and to the depth shown on the plans. Prior to placement of joint sealant or seals, the top of the joint shall be widened by sawing as shown on the plans.

**501-4.11 Finishing.** Finishing operations shall be a continuing part of placing operations starting immediately behind the strike-off of the paver. Initial finishing shall be provided by the transverse screed or extrusion plate. The sequence of operations shall be transverse finishing, longitudinal machine floating if used, straightedge finishing, edging of joints, and then texturing. Finishing shall be by the machine method. The hand method shall be used only on isolated areas of odd slab widths or shapes and in the event of a breakdown of the mechanical finishing equipment. Supplemental hand finishing for machine finished pavement shall be kept to an absolute minimum. Any machine finishing operation which requires appreciable hand finishing, other than a moderate amount of straightedge finishing, shall be immediately stopped and proper adjustments made or the equipment replaced. Equipment, mixture, and/or procedures which produce more than 1/4 inch (6 mm) of mortar-rich surface shall be immediately modified as necessary to eliminate this condition or operations shall cease. Compensation shall be made for surging behind the screeds or extrusion plate and settlement during hardening and care shall be taken to ensure that paving and finishing machines are properly adjusted so that the finished surface of the concrete (not just the cutting edges of the screeds) will be at the required line and grade. Finishing equipment and tools shall be maintained clean and in an approved condition. At no time shall water be added to the surface of the slab with the finishing equipment or tools, or in any other way. Fog (mist) sprays or other surface applied finishing aids specified to prevent plastic shrinkage cracking, approved by the RPR, may be used in accordance with the manufacturers requirements.

**a. Machine finishing with slipform pavers.** The slipform paver shall be operated so that only a very minimum of additional finishing work is required to produce pavement surfaces and edges meeting the specified tolerances. Any equipment or procedure that fails to meet these specified requirements shall immediately be replaced or modified as necessary. A self-propelled non-rotating pipe float may be used while the concrete is still plastic, to remove minor irregularities and score marks. Only one pass of the pipe float shall be allowed. Equipment, mixture, and/or procedures which produce more than 1/4 inch (6 mm) of mortar-rich surface shall be immediately modified as necessary to eliminate this condition or operations shall cease. Remove excessive slurry from the surface with a cutting straightedge and wipe off the edge. Any slurry which does run down the vertical edges shall be immediately removed by hand, using stiff brushes or scrapers. No slurry, concrete or concrete mortar shall be used to build up along the edges of the pavement to compensate for excessive edge slump, either while the concrete is plastic or after it hardens.

**b. Machine finishing with fixed forms.** The machine shall be designed to straddle the forms and shall be operated to screed and consolidate the concrete. Machines that cause displacement of the forms shall be replaced. The machine shall make only one pass over each area of pavement. If the equipment and procedures do not produce a surface of uniform texture, true to grade, in one pass, the operation shall be immediately stopped and the equipment, mixture, and procedures adjusted as necessary.

**c. Other types of finishing equipment.** Clary screeds, other rotating tube floats, or bridge deck finishers are not allowed on mainline paving, but may be allowed on irregular or odd-shaped slabs, and near buildings or trench drains, subject to the RPR's approval.

Bridge deck finishers shall have a minimum operating weight of 7500 pounds (3400 kg) and shall have a transversely operating carriage containing a knock-down auger and a minimum of two immersion vibrators. Vibrating screeds or pans shall be used only for isolated slabs where hand finishing is permitted as specified, and only where specifically approved.

**d. Hand finishing.** Hand finishing methods will not be permitted, except under the following conditions: (1) in the event of breakdown of the mechanical equipment, hand methods may be used to finish the concrete already deposited on the grade and (2) in areas of narrow widths or of irregular dimensions where operation of the mechanical equipment is impractical.

**e. Straightedge testing and surface correction.** After the pavement has been struck off and while the concrete is still plastic, it shall be tested for trueness with a 12-foot (3.7-m) finishing straightedge swung from handles capable of spanning at least one-half the width of the slab. The straightedge shall be held in contact with the surface in successive positions parallel to the centerline and the whole area gone over from one side of the slab to the other, as necessary. Advancing shall be in successive stages of not more than one-half the length of the straightedge. Any excess water and laitance in excess of 1/8 inch (3 mm) thick shall be removed from the surface of the pavement and wasted. Any depressions shall be immediately filled with freshly mixed concrete, struck off, consolidated, and refinished. High areas shall be cut down and refinished. Special attention shall be given to assure that the surface across joints meets the smoothness requirements. Straightedge testing and surface corrections shall continue until the entire surface is found to be free from observable departures from the straightedge and until the slab conforms to the required grade and cross-section. The use of long-handled wood floats shall be confined to a minimum; they may be used only in emergencies and in areas not accessible to finishing equipment.

**501-4.12 Surface texture.** The surface of the pavement shall be finished as designated below for all newly constructed concrete pavements. It is important that the texturing equipment not tear or unduly roughen the pavement surface during the operation. The texture shall be uniform in appearance and approximately 1/16 inch (2 mm) in depth. Any imperfections resulting from the texturing operation shall be corrected to the satisfaction of the RPR.

**a. Brush or broom finish.** Shall be applied when the water sheen has practically disappeared. The equipment shall operate transversely across the pavement surface.

**b. Burlap drag finish.** Burlap, at least 15 ounces per square yard (555 grams per square meter), will typically produce acceptable texture. To obtain a textured surface, the transverse threads of the burlap shall be removed approximately one foot (30 cm) from the trailing edge. A heavy buildup of grout on the burlap threads produces the desired wide sweeping longitudinal striations on the pavement surface.

**c. Artificial turf finish.** Not used.

**501-4.13 Curing.** Immediately after finishing operations are completed and bleed water is gone from the surface, all exposed surfaces of the newly placed concrete shall be cured for a 7-day cure period in accordance with one of the methods below. Failure to provide sufficient cover material of whatever kind the Contractor may elect to use, or lack of water to adequately take care of both curing and other requirements, shall be cause for immediate suspension of concreting operations. The concrete shall not be left exposed for more than 1/2 hour during the curing period.

When a two-saw-cut method is used to construct the contraction joint, the curing compound shall be applied to the saw-cut immediately after the initial cut has been made. The sealant reservoir shall not be sawed until after the curing period has been completed. When the one cut method is used to construct the contraction joint, the joint shall be cured with wet rope, wet rags, or wet blankets. The rags, ropes, or blankets shall be kept moist for the duration of the curing period.

**a. Impervious membrane method.** Curing with liquid membrane compounds should not occur until bleed and surface moisture has evaporated. All exposed surfaces of the pavement shall be sprayed

uniformly with white pigmented curing compound immediately after the finishing of the surface and before the set of the concrete has taken place. The curing compound shall not be applied during rainfall. Curing compound shall be applied by mechanical sprayers under pressure at the rate of one gallon (4 liters) to not more than 150 square feet (14 sq m). The spraying equipment shall be of the fully atomizing type equipped with a tank agitator. At the time of use, the compound shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. During application, the compound shall be stirred continuously by mechanical means. Hand spraying of odd widths or shapes and concrete surfaces exposed by the removal of forms will be permitted. When hand spraying is approved by the RPR, a double application rate shall be used to ensure coverage. Should the film become damaged from any cause, including sawing operations, within the required curing period, the damaged portions shall be repaired immediately with additional compound or other approved means. Upon removal of side forms, the sides of the exposed slabs shall be protected immediately to provide a curing treatment equal to that provided for the surface.

**b. White burlap-polyethylene sheets.** The surface of the pavement shall be entirely covered with the sheeting. The sheeting used shall be such length (or width) that it will extend at least twice the thickness of the pavement beyond the edges of the slab. The sheeting shall be placed so that the entire surface and both edges of the slab are completely covered. The sheeting shall be placed and weighted to remain in contact with the surface covered, and the covering shall be maintained fully saturated and in position for seven (7) days after the concrete has been placed.

**c. Water method.** The entire area shall be covered with burlap or other water absorbing material. The material shall be of sufficient thickness to retain water for adequate curing without excessive runoff. The material shall be kept wet at all times and maintained for seven (7) days. When the forms are stripped, the vertical walls shall also be kept moist. It shall be the responsibility of the Contractor to prevent ponding of the curing water on the subbase.

**d. Concrete protection for cold weather.** Maintain the concrete at a temperature of at least 50°F (10°C) for a period of 72 hours after placing and at a temperature above freezing for the remainder of the 7-day curing period. The Contractor shall be responsible for the quality and strength of the concrete placed during cold weather; and any concrete damaged shall be removed and replaced at the Contractor's expense.

**e. Concrete protection for hot weather.** Concrete should be continuous moisture cured for the entire curing period and shall commence as soon as the surfaces are finished and continue for at least 24 hours. However, if moisture curing is not practical beyond 24 hours, the concrete surface shall be protected from drying with application of a liquid membrane-forming curing compound while the surfaces are still damp. Other curing methods may be approved by the RPR.

**501-4.14 Removing forms.** Unless otherwise specified, forms shall not be removed from freshly placed concrete until it has hardened sufficiently to permit removal without chipping, spalling, or tearing. After the forms have been removed, the sides of the slab shall be cured in accordance with paragraph 501-4.13.

If honeycombed areas are evident when the forms are removed, materials, placement, and consolidation methods must be reviewed and appropriate adjustments made to assure adequate consolidation at the edges of future concrete placements. Honeycombed areas that extend into the slab less than approximately 1 inch (25 mm), shall be repaired with an approved grout, as directed by the RPR. Honeycombed areas that extend into the slab greater than a depth of 1 inch (25 mm) shall be considered as defective work and shall be removed and replaced in accordance with paragraph 501-4.19.

**501-4.15 Saw-cut grooving.** ~~Not Required. If shown on the plans, grooved surfaces shall be provided in accordance with the requirements of Item P-621.~~

**501-4.16 Sealing joints.** The joints in the pavement shall be sealed in accordance with Item P-604 and P-605.

**501-4.17 Protection of pavement.** The Contractor shall protect the pavement and its appurtenances against both public traffic and traffic caused by the Contractor's employees and agents until accepted by the RPR. This shall include watchmen to direct traffic and the erection and maintenance of warning signs, lights, pavement bridges, crossovers, and protection of unsealed joints from intrusion of foreign material, etc. Any damage to the pavement occurring prior to final acceptance shall be repaired or the pavement replaced at the Contractor's expense.

Aggregates, rubble, or other similar construction materials shall not be placed on airfield pavements. Traffic shall be excluded from the new pavement by erecting and maintaining barricades and signs until the concrete is at least seven (7) days old, or for a longer period if directed by the RPR.

In paving intermediate lanes between newly paved pilot lanes, operation of the hauling and paving equipment will be permitted on the new pavement after the pavement has been cured for seven (7) days, the joints are protected, the concrete has attained a minimum field cured flexural strength of 450 psi (3100 kPa), and the slab edge is protected.

All new and existing pavement carrying construction traffic or equipment shall be kept clean and spillage of concrete and other materials shall be cleaned up immediately.

Damaged pavements shall be removed and replaced at the Contractor's expense. Slabs shall be removed to the full depth, width, and length of the slab.

**501-4.18 Opening to construction traffic.** The pavement shall not be opened to traffic until test specimens molded and cured in accordance with ASTM C31 have attained a flexural strength of 450 pounds per square inch (3100 kPa) when tested in accordance with ASTM C78. If such tests are not conducted, the pavement shall not be opened to traffic until 14 days after the concrete was placed. Prior to opening the pavement to construction traffic, all joints shall either be sealed or protected from damage to the joint edge and intrusion of foreign materials into the joint. As a minimum, backer rod or tape may be used to protect the joints from foreign matter intrusion.

**501-4.19 Repair, removal, or replacement of slabs.** New pavement slabs that are broken or contain cracks or are otherwise defective or unacceptable as defined by acceptance criteria in paragraph 501-6.6 shall be removed and replaced or repaired, as directed by the RPR, at the Contractor's expense. Spalls along joints shall be repaired as specified. Removal of partial slabs is not permitted. Removal and replacement shall be full depth, shall be full width of the slab, and the limit of removal shall be normal to the paving lane and to each original transverse joint. The RPR will determine whether cracks extend full depth of the pavement and may require cores to be drilled on the crack to determine depth of cracking. Such cores shall have a diameter of 2 inches (50 mm) to 4 inches (100 mm), shall be drilled by the Contractor and shall be filled by the Contractor with a well consolidated concrete mixture bonded to the walls of the hole with a bonding agent, using approved procedures. Drilling of cores and refilling holes shall be at no expense to the Owner. Repair of cracks as described in this section shall not be allowed if in the opinion of the RPR the overall condition of the pavement indicates that such repair is unlikely to achieve an acceptable and durable finished pavement. No repair of cracks shall be allowed in any panel that demonstrates segregated aggregate with an absence of coarse aggregate in the upper 1/8 inch (3 mm) of the pavement surface.

**a. Shrinkage cracks.** Shrinkage cracks which do not exceed one-third of the pavement depth shall be cleaned and either high molecular weight methacrylate (HMWM) applied; or epoxy resin (Type IV, Grade 1) pressure injected using procedures recommended by the manufacturer and approved by the RPR. Sandblasting of the surface may be required following the application of HMWM to restore skid resistance. Care shall be taken to ensure that the crack is not widened during epoxy resin injection. All epoxy resin injection shall take place in the presence of the RPR. Shrinkage cracks which exceed one-third the pavement depth shall be treated as full depth cracks in accordance with paragraphs 501-4.19b and 501-19c.



**b. Slabs with cracks through interior areas.** Interior area is defined as that area more than 6 inches (150 mm) from either adjacent original transverse joint. The full slab shall be removed and replaced at no cost to the Owner, when there are any full depth cracks, or cracks greater than one-third the pavement depth, that extend into the interior area.

**c. Cracks close to and parallel to joints.** All full-depth cracks within 6 inches (150 mm) either side of the joint and essentially parallel to the original joints, shall be treated as follows.

**(1) Full depth cracks and original joint not cracked.** The full-depth crack shall be treated as the new joint and the original joint filled with an epoxy resin.

**i. Full-depth crack.** The joint sealant reservoir for the crack shall be formed by sawing to a depth of 3/4 inches (19 mm),  $\pm 1/16$  inch (2 mm), and to a width of 5/8 inch (16 mm),  $\pm 1/8$  inch (3 mm). The crack shall be sawed with equipment specially designed to follow random cracks. Any equipment or procedure which causes raveling or spalling along the crack shall be modified or replaced to prevent raveling or spalling. The joint shall be sealed with sealant in accordance with P-605 or as directed by the RPR.

**ii. Original joint.** If the original joint sealant reservoir has been sawed out, the reservoir and as much of the lower saw cut as possible shall be filled with epoxy resin, Type IV, Grade 2, thoroughly tooled into the void using approved procedures.

If only the original narrow saw cut has been made, it shall be cleaned and pressure injected with epoxy resin, Type IV, Grade 1, using approved procedures.

Where a parallel crack goes part way across paving lane and then intersects and follows the original joint which is cracked only for the remainder of the width, it shall be treated as specified above for a parallel crack, and the cracked original joint shall be prepared and sealed as originally designed.

**(2) Full depth cracks and original joint cracked.** If there is any place in the lane width where a parallel crack and a cracked portion of the original joint overlap, the entire slab containing the crack shall be removed and replaced.

**d. Removal and replacement of full slabs.** Make a full depth cut perpendicular to the slab surface along all edges of the slab with a concrete saw cutting any dowels or tie-bars. **If the edges of the slabs are spalled, cut the edge of the slab at least one to six inches into the concrete pavement at the direction of the RPR.** Remove damaged slab protecting adjacent pavement from damage. Damage to adjacent slabs may result in removal of additional slabs as directed by the RPR at the Contractor's expense.

The underlying material shall be repaired, re-compacted and shaped to grade.

Dowels of the size and spacing specified for other joints in similar pavement on the project shall be installed along all four (4) edges of the new slab in accordance with paragraph 501-4.10d.

Placement of concrete shall be as specified for original construction. The joints around the new slab shall be prepared and sealed as specified for original construction.

**e. Spalls along joints.**

**(1)** Spalls less than one inch wide and less than the depth of the joint sealant reservoir, shall be filled with joint sealant material.

**(2)** Spalls larger than one inch and/or deeper than the joint reservoir, but less than 1/2 the slab depth, and less than 25% of the length of the adjacent joint shall be repaired as follows:

**i.** Make a vertical saw cut at least one inch (25 mm) outside the spalled area and to a depth of at least 2 inches (50 mm). Saw cuts shall be straight lines forming rectangular areas surrounding the spalled area.

**ii.** Remove unsound concrete and at least 1/2 inch (12 mm) of visually sound concrete between the saw cut and the joint or crack with a light chipping hammer.

iii. Clean cavity with high-pressure water jets supplemented with compressed air as needed to remove all loose material.

iv. Apply a prime coat of epoxy resin, Type III, Grade I, to the dry, cleaned surface of all sides and bottom of the cavity, except any joint face.

v. Fill the cavity with low slump concrete or mortar or with epoxy resin concrete or mortar.

vi. An insert or other bond-breaking medium shall be used to prevent bond at all joint faces.

vii. A reservoir for the joint sealant shall be sawed to the dimensions required for other joints, or as required to be routed for cracks. The reservoir shall be thoroughly cleaned and sealed with the sealer specified for the joints.

(3) Spalls deeper than 1/2 of the slab depth or spalls longer than 25% of the adjacent joint require replacement of the entire slab.

**f. Diamond grinding of Concrete surfaces.** Diamond grinding shall be completed prior to pavement grooving. Diamond grinding of the hardened concrete should not be performed until the concrete is at least 14 days old and has achieved full minimum strength. Equipment that causes ravels, aggregate fractures, spalls or disturbance to the joints will not be permitted. The depth of diamond grinding shall not exceed 1/2 inch (13 mm) and all areas in which diamond grinding has been performed will be subject to the final pavement thickness tolerances specified.

Diamond grinding shall be performed with a machine specifically designed for diamond grinding capable of cutting a path at least 3 feet (0.9 m) wide. The saw blades shall be 1/8-inch (3-mm) wide with sufficient number of flush cut blades that create grooves between 0.090 and 0.130 inches (2 and 3.5 mm) wide; and peaks and ridges approximately 1/32 inch (1 mm) higher than the bottom of the grinding cut. The Contractor shall determine the number and type of blades based on the hardness of the aggregate. Contractor shall demonstrate to the RPR that the grinding equipment will produce satisfactory results prior to making corrections to surfaces.

Grinding will be tapered in all directions to provide smooth transitions to areas not requiring grinding. The slurry resulting from the grinding operation shall be continuously removed and the pavement left in a clean condition. All grinding shall be at the expense of the Contractor.

## **CONTRACTOR QUALITY CONTROL (CQC)**

**501-5.1 Quality control program.** The Contractor shall develop a Quality Control Program in accordance with Item C-100. No partial payment will be made for materials that are subject to specific quality control requirements without an approved quality control program.

**501-5.2 Contractor Quality Control (CQC).** [ The Contractor shall provide or contract for testing facilities in accordance with Item C-100. The RPR shall be permitted unrestricted access to inspect the Contractor's QC facilities and witness QC activities. The RPR will advise the Contractor in writing of any noted deficiencies concerning the QC facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to be adversely affecting the test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are satisfactorily corrected.

**501-5.3 Contractor QC testing.** The Contractor shall perform all QC tests necessary to control the production and construction processes applicable to this specification and as set forth in the CQCP. The testing program shall include, but not necessarily be limited to, tests for aggregate gradation, aggregate moisture content, slump, and air content. A QC Testing Plan shall be developed and approved by the RPR as part of the CQCP.

The RPR may at any time, notwithstanding previous plant acceptance, reject and require the Contractor to dispose of any batch of concrete mixture which is rendered unfit for use due to contamination, segregation, or improper slump. Such rejection may be based on only visual inspection. In the event of such rejection, the Contractor may take a representative sample of the rejected material in the presence of the RPR, and if it can be demonstrated in the laboratory, in the presence of the RPR, that such material was erroneously rejected, payment will be made for the material at the contract unit price.

**a. Fine aggregate.**

**(1) Gradation.** A sieve analysis shall be made at least twice daily in accordance with ASTM C136 from randomly sampled material taken from the discharge gate of storage bins or from the conveyor belt.

**(2) Moisture content.** If an electric moisture meter is used, at least two direct measurements of moisture content shall be made per week to check the calibration. If direct measurements are made in lieu of using an electric meter, two tests shall be made per day. Tests shall be made in accordance with ASTM C70 or ASTM C566.

**(3) Deleterious substances.** Fine aggregate as delivered to the mixer shall be tested for deleterious substances in fine aggregate for concrete as specified in paragraph 501-2.1b, prior to production of the control strip, and a minimum of every 30-days during production or more frequently as necessary to control deleterious substances.

**b. Coarse Aggregate.**

**(1) Gradation.** A sieve analysis shall be made at least twice daily for each size of aggregate. Tests shall be made in accordance with ASTM C136 from randomly sampled material taken from the discharge gate of storage bins or from the conveyor belt.

**(2) Moisture content.** If an electric moisture meter is used, at least two direct measurements of moisture content shall be made per week to check the calibration. If direct measurements are made in lieu of using an electric meter, two tests shall be made per day. Tests shall be made in accordance with ASTM C566.

**(3) Deleterious substances.** Coarse aggregate as delivered to the mixer shall be tested for deleterious substances in coarse aggregate for concrete as specified in paragraph 501-2.1c, prior to production of the control strip, and a minimum of every 30-days during production or more frequently as necessary to control deleterious substances.

**c. Slump.** One test shall be made for each subplot. Slump tests shall be performed in accordance with ASTM C143 from material randomly sampled from material discharged from trucks at the paving site. Material samples shall be taken in accordance with ASTM C172.

**d. Air content.** One test shall be made for each subplot. Air content tests shall be performed in accordance with ASTM C231 for gravel and stone coarse aggregate and ASTM C173 for slag or other porous coarse aggregate, from material randomly sampled from trucks at the paving site. Material samples shall be taken in accordance with ASTM C172.

**e. Unit weight and Yield.** One test shall be made for each subplot. Unit weight and yield tests shall be in accordance with ASTM C138. The samples shall be taken in accordance with ASTM C172 and at the same time as the air content tests.

**f. Temperatures.** Temperatures shall be checked at least four times per lot at the job site in accordance with ASTM C1064.

**g. Smoothness for Contractor Quality Control.**

The Contractor shall perform smoothness testing in transverse and longitudinal directions daily to verify that the construction processes are producing pavement with variances less than ¼ inch in 12 feet,

identifying areas that may pond water which could lead to hydroplaning of aircraft. If the smoothness criteria is not met, appropriate changes and corrections to the construction process shall be made by the Contractor before construction continues.

The Contractor may use a 12-foot (3.7 m) “straightedge, a rolling inclinometer meeting the requirements of ASTM E2133 or rolling external reference device that can simulate a 12-foot (3.7m) straightedge approved by the RPR. Straight-edge testing shall start with one-half the length of the straightedge at the edge of pavement section being tested and then moved ahead one-half the length of the straightedge for each successive measurement. Testing shall be continuous across all joints. The surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between the two high points. If the rolling inclinometer or external reference device is used, the data may be evaluated using either the FAA profile program, ProFAA, or FHWA profile program ProVal, using the 12-foot straightedge simulation function.

Smoothness readings shall not be made across grade changes or cross slope transitions. The transition between new and existing pavement shall be evaluated separately for conformance with the plans.

**(1) Transverse measurements.** Transverse measurements shall be taken for each day’s production placed. Transverse measurements shall be taken perpendicular to the pavement centerline each 50 feet (15 m) or more often as determined by the RPR. The joint between lanes shall be tested separately to facilitate smoothness between lanes.

**(2) Longitudinal measurements.** Longitudinal measurements shall be taken for each day’s production placed. Longitudinal tests shall be parallel to the centerline of paving; at the center of paving lanes when widths of paving lanes are less than 20 feet (6 m); and at the third points of paving lanes when widths of paving lanes are 20 ft (6 m) or greater. When placement abuts previously placed material the first measurement shall start with one half the length of the straight edge on the previously placed material.

Deviations on the final surface course in either the transverse or longitudinal direction that will trap water greater than 1/4 inch (6 mm) shall be corrected with diamond grinding per paragraph 501-4.19f or by removing and replacing the surface course to full depth. Grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. All areas in which diamond grinding has been performed shall be subject to the final pavement thickness tolerances specified in paragraph 501-6.6.

Control charts shall be kept to show area of each day’s placement and the percentage of corrective grinding required. Corrections to production and placement shall be initiated when corrective grinding is required. If the Contractor’s machines and/or methods produce significant areas that need corrective actions in excess of 10 percent of a day’s production, production shall be stopped until corrective measures are implemented by the Contractor.

**h. Grade.** Grade will be evaluated prior to and after placement of the concrete surface.

Measurements will be taken at appropriate gradelines (as a minimum at center and edges of paving lane) and longitudinal spacing as shown on cross-sections and plans. The final surface of the pavement will not vary from the gradeline elevations and cross-sections shown on the plans by more than 1/2 inch (12 mm) vertically. The documentation will be provided by the Contractor to the RPR within 48 hours.

Areas with humps or depression that that exceed grade or smoothness and that retain water on the surface must be ground off provided the course thickness after grinding is not more than 1/2 inch (12 mm) less than the thickness specified on the plans. If these areas cannot be corrected with grinding then the slabs that are retaining water must be removed and replaced in accordance with paragraph 501-4.19d. Grinding shall be in accordance with paragraph 501-4.19f. All corrections will be at the Contractors expense.

**501-5.4 Control charts.** The Contractor shall maintain linear control charts for fine and coarse aggregate gradation, slump, and air content. The Contractor shall also maintain a control chart plotting the coarseness factor/workability factor from the combined gradations in accordance with paragraph 501-2.1d.

Control charts shall be posted in a location satisfactory to the RPR and shall be kept up to date at all times. As a minimum, the control charts shall identify the project number, the contract item number, the test number, each test parameter, the Action and suspension Limits, or Specification limits, applicable to each test parameter, and the Contractor's test results. The Contractor shall use the control charts as part of a process control system for identifying potential problems and assignable causes before they occur. If the Contractor's projected data during production indicates a potential problem and the Contractor is not taking satisfactory corrective action, the RPR may halt production or acceptance of the material.

**a. Fine and coarse aggregate gradation.** The Contractor shall record the running average of the last five gradation tests for each control sieve on linear control charts. Superimposed on the control charts shall be the action and suspension limits. Gradation tests shall be performed by the Contractor per ASTM C136. The Contractor shall take at least two samples per lot to check the final gradation. Sampling shall be per ASTM D75 from the flowing aggregate stream or conveyor belt.

**b. Slump and air content.** The Contractor shall maintain linear control charts both for individual measurements and range (that is, difference between highest and lowest measurements) for slump and air content in accordance with the following Action and Suspension Limits.

**c. Combined gradation.** The Contractor shall maintain a control chart plotting the coarseness factor and workability factor on a chart in accordance with paragraph 501-2.1d.

**Control Chart Limits<sup>1</sup>**

Control Parameter	Individual Measurements	
	Action Limit	Suspension Limit
Gradation <sup>2</sup>	*3	*3
Coarseness Factor (CF)	±3.5	±5
Workability Factor (WF)	±2	±3
Slump	+0.5 to -1 inch (+13 to -25 mm)	+1 to -1.5 inch (+25 to -38 mm)
Air Content	±1.5%	±2.0%

<sup>1</sup> Control charts shall developed and maintained for each control parameter indicated.

<sup>2</sup> Control charts shall be developed and maintained for each sieve size.

<sup>3</sup> Action and suspension limits shall be determined by the Contractor.

**501-5.5 Corrective action at Suspension Limit.** The CQCP shall indicate that appropriate action shall be taken when the process is believed to be out of control. The CQCP shall detail what action will be taken to bring the process into control and shall contain sets of rules to gauge when a process is out of control. As a minimum, a process shall be deemed out of control and corrective action taken if any one of the following conditions exists.

- a. Fine and coarse aggregate gradation.** When two consecutive averages of five tests are outside of the suspension limits, immediate steps, including a halt to production, shall be taken to correct the grading.

- b. Coarseness and Workability factor. When the CF or WF reaches the applicable suspension limits, the Contractor, immediate steps, including a halt to production, shall be taken to correct the CF and WF.

c. Fine and coarse aggregate moisture content. Whenever the moisture content of the fine or coarse aggregate changes by more than 0.5%, the scale settings for the aggregate batcher and water batcher shall be adjusted.

- d. Slump. The Contractor shall halt production and make appropriate adjustments whenever:

- (1) one point falls outside the Suspension Limit line for individual measurements

OR

- (2) two points in a row fall outside the Action Limit line for individual measurements.

d. Air content. The Contractor shall halt production and adjust the amount of air-entraining admixture whenever:

- (1) one point falls outside the Suspension Limit line for individual measurements

OR

- (2) two points in a row fall outside the Action Limit line for individual measurements.

## MATERIAL ACCEPTANCE

**501-6.1 Quality Assurance (QA) Acceptance sampling and testing.** All acceptance sampling and testing necessary to determine conformance with the requirements specified in this section, ~~with the exception of coring for thickness determination~~, will be performed by the RPR. The Contractor shall provide adequate facilities for the initial curing of beams. The Contractor shall bear the cost of providing initial curing facilities and coring and filling operations, per paragraph 501-6.5b(1).

The samples will be transported while in the molds. The curing, except for the initial cure period, will be accomplished using the immersion in saturated lime water method. During the 24 hours after molding, the temperature immediately adjacent to the specimens must be maintained in the range of 60° to 80°F (16° to 27°C), and loss of moisture from the specimens must be prevented. The specimens may be stored in tightly constructed wooden boxes, damp sand pits, temporary buildings at construction sites, under wet burlap in favorable weather, or in heavyweight closed plastic bags, or using other suitable methods, provided the temperature and moisture loss requirements are met.

**501-6.2 Quality Assurance (QA) testing laboratory.** Quality assurance testing organizations performing these acceptance tests will be accredited in accordance with ASTM C1077. The quality assurance laboratory accreditation must be current and listed on the accrediting authority's website. All test methods required for acceptance sampling and testing must be listed on the lab accreditation. A copy of the laboratory's current accreditation and accredited test methods will be submitted to the RPR prior to start of construction.

**501-6.3 Lot size.** Concrete will be accepted for strength and thickness on a lot basis. A lot will consist of a day's production not to exceed 4,250 square yards. Each lot will be divided into approximately equal sublots with individual sublots between 400 to 600 cubic yards. Where three sublots are produced, they will constitute a lot. Where one or two sublots are produced, they will be incorporated into the previous or next lot. Where more than one plant is simultaneously producing concrete for the job, the lot sizes will apply separately for each plant.

**501-6.4 Partial lots.** When operational conditions cause a lot to be terminated before the specified number of tests have been made for the lot or for overages or minor placements to be considered as partial lots, the following procedure will be used to adjust the lot size and the number of tests for the lot.

Where three sublots have been produced, they will constitute a lot. Where one or two sublots have been produced, they will be incorporated into the next lot or the previous lot and the total number of sublots will be used in the acceptance criteria calculation, that is,  $n=5$  or  $n=6$ .

### **501-6.5 Acceptance Sampling and Testing.**

#### **a. Strength.**

**(1) Sampling.** One sample will be taken for each subplot from the concrete delivered to the job site. Sampling locations will be determined by the RPR in accordance with random sampling procedures contained in ASTM D3665. The concrete will be sampled in accordance with ASTM C172.

**(2) Test Specimens.** The RPR will be responsible for the casting, initial curing, transportation, and curing of specimens in accordance with ASTM C31. Two (2) specimens will be made from each sample and slump, air content, unit weight, and temperature tests will be conducted for each set of strength specimens. Within 24 to 48 hours, the samples will be transported from the field to the laboratory while in the molds. Samples will be cured in saturated lime water.

The strength of each specimen will be determined in accordance with ASTM C78. The strength for each subplot will be computed by averaging the results of the two test specimens representing that subplot.

**(3) Acceptance.** Acceptance of pavement for strength will be determined by the RPR in accordance with paragraph 501-6.6b(1). All individual strength tests within a lot will be checked for outliers in accordance with ASTM E178, at a significance level of 5%. Outliers will be discarded and the remaining test values will be used to determine acceptance in accordance with paragraph 501-6.5b.

#### **b. Pavement thickness.**

**(1) Sampling.** One core will be taken by the Contractor for each subplot in the presence of the RPR. Sampling locations will be determined by the RPR in accordance with random sampling procedures contained in ASTM D3665. Areas, such as thickened edges, with planned variable thickness, will be excluded from sample locations.

Cores shall be a minimum 4 inch (100 mm) in diameter neatly cut with a core drill. The Contractor will furnish all tools, labor, and materials for cutting samples and filling the cored hole. Core holes will be filled by the Contractor with a non-shrink grout approved by the RPR within one day after sampling.

**(2) Testing.** The thickness of the cores will be determined by the RPR by the average caliper measurement in accordance with ASTM C174. Each core shall be photographed and the photograph included with the test report.

**(3) Acceptance.** Acceptance of pavement for thickness will be determined by the RPR in accordance with paragraph 501-6.6.

### **501-6.6 Acceptance criteria.**

**a. General.** Acceptance will be based on the following characteristics of the completed pavement discussed in paragraph 501-6.5b:

- (1) Strength**
- (2) Thickness**
- (3) Grade**
- (4) Profilograph smoothness**
- (5) Adjustments for repairs**

Acceptance for strength, thickness, and grade, will be based on the criteria contained in accordance with paragraph 501-6.6b(1), 501-6.6b(2), and 501-6.6b(3), respectively. Acceptance for profilograph smoothness will be based on the criteria contained in paragraph 501-6.6b(4).

Production quality must achieve 90 PWL or higher to receive full payment.

Strength and thickness will be evaluated for acceptance on a lot basis using the method of estimating PWL. Production quality must achieve 90 PWL or higher to receive full pavement. The PWL will be determined in accordance with procedures specified in Item C-110.

The lower specification tolerance limit (L) for strength and thickness will be:

**Lower Specification Tolerance Limit (L)**

<b>Strength</b>	$0.93 \times \text{strength specified in paragraph 501-3.3}$
<b>Thickness</b>	Lot Plan Thickness in inches, - 0.50 in

**b. Acceptance criteria.**

**(1) Strength.** If the PWL of the lot equals or exceeds 90%, the lot will be acceptable. Acceptance and payment for the lot will be determined in accordance with paragraph 501-8.1.

**(2) Thickness.** If the PWL of the lot equals or exceeds 90%, the lot will be acceptable. Acceptance and payment for the lot will be determined in accordance with paragraph 501-8.1.

**(3) Grade.** The final finished surface of the pavement of the completed project will not vary from the gradeline elevations and cross-sections shown on the plans by more than 1/2 inch (12 mm) vertically. The documentation, stamped and signed by a licensed surveyor shall be in accordance with paragraph 501-5.3h. Payment for sublots that do not meet grade for over 25% of the subplot shall be reduced by 5% and not be more than 95%.

**(4) Profilograph roughness for QA Acceptance.** The final profilograph shall be the full length of the project to facilitate testing of roughness between lots. The Contractor, in the presence of the RPR shall perform a profilograph roughness test on the completed project with a profilograph meeting the requirements of ASTM E1274 or a Class I inertial profiler meeting ASTM E950. Data and results shall be provided within 48 hrs of profilograph roughness tests.

The pavement shall have an average profile index less than 15 inches per mile per 1/10 mile. The equipment shall utilize electronic recording and automatic computerized reduction of data to indicate “must grind” bumps and the Profile Index for the pavement using a 0.2-inch (5 mm) blanking band. The bump template must span one inch (25 mm) with an offset of 0.4 inches (10 mm). The profilograph must be calibrated prior to use and operated by a factory or State DOT approved, trained operator. Profilograms shall be recorded on a longitudinal scale of one inch (25 mm) equals 25 feet (7.5 m) and a vertical scale of one inch (25 mm) equals one inch (25 mm). Profilograph shall be performed one foot right and left of project centerline and 15 feet (4.5 m) right and left of project centerline. Any areas that indicate “must grind” shall be corrected with diamond grinding per paragraph 501-4.19f or by removing and replacing full depth of surface course, as directed by the RPR. Where corrections are necessary, a second profilograph run shall be performed to verify that the corrections produced an average profile index of 15 inches per mile per 1/10 mile or less.

**(5) Adjustments for repair.** Sublots with spall repairs, crack repairs, or partial panel replacement, will be limited to no more than 95% payment.

**(6) Adjustment for grinding.** For sublots with grinding over 25% of a subplot, payment will be reduced 5%.



## METHOD OF MEASUREMENT

**501-7.1** Concrete pavement shall be measured by the number of square yards of plain or reinforced pavement as specified in-place, completed and accepted.

**501-7.2** Concrete transition slabs shall be measured per linear foot concrete transition slab as specified in-place, completed and accepted.

**501-7.3** Concrete pavement blockouts for utility structures and/or fixtures shall be considered incidental to the installation of the structure and/or fixture and no separate measurements shall be made.

## BASIS OF PAYMENT

**501-8.1 Payment.** Payment for concrete pavement meeting all acceptance criteria as specified in paragraph 501-6.6. Acceptance Criteria shall be based on results of strength, smoothness, and thickness tests. Payment for acceptable lots of concrete pavement shall be adjusted in accordance with paragraph 501-8.1a for strength and thickness; 501-8.1b for repairs; 501-8.1c for grinding; and 501-8.1d for smoothness, subject to the limitation that:

The total project payment for concrete pavement shall not exceed 100 percent of the product of the contract unit price and the total number of square yards of concrete pavement used in the accepted work (See Note 1 under the Price Adjustment Schedule table below).

Payment shall be full compensation for all labor, materials, tools, equipment, and incidentals required to complete the work as specified herein and on the drawings. Thickened edges and slabs, where shown on the plans, shall be included as incidental to the P-501-8.1 pay item or P-501-8.2 pay item where thickened edges and slabs are for plain or reinforced concrete pavement. Reinforced and non-reinforced isolated slabs, where shown on the plans, shall be included as incidental to the P-501-8.4 pay item where isolated slabs require plain or reinforced concrete pavement.

**a. Basis of adjusted payment.** The pay factor for each individual lot shall be calculated in accordance with the Price Adjustment Schedule table below. A pay factor shall be calculated for both strength and thickness. The lot pay factor shall be the higher of the two values when calculations for both strength and thickness are 100% or higher. The lot pay factor shall be the product of the two values when only one of the calculations for either strength or thickness is 100% or higher. The lot pay factor shall be the lower of the two values when calculations for both strength and thickness are less than 100%.

**Price Adjustment Schedule<sup>1</sup>**

Percentage of Materials Within Specification Limits (PWL)	Lot Pay Factor (Percent of Contract Unit Price)
96 – 100	106
90 – 95	PWL + 10
75 – 90	0.5 PWL + 55
55 – 74	1.4 PWL – 12
Below 55	Reject <sup>2</sup>

<sup>1</sup> Although it is theoretically possible to achieve a pay factor of 106% for each lot, actual payment in excess of 100% shall be subject to the total project payment limitation specified in paragraph 501-8.1.

<sup>2</sup> The lot shall be removed and replaced unless, after receipt of FAA concurrence, the Owner and Contractor agree in writing that the lot will remain; the lot paid at 50% of the contract unit price; and the total project payment limitation reduced by the amount withheld for that lot.

For each lot accepted, the adjusted contract unit price shall be the product of the lot pay factor for the lot and the contract unit price. Payment shall be subject to the total project payment limitation specified in paragraph 501-8.1. Payment in excess of 100% for accepted lots of concrete pavement shall be used to offset payment for accepted lots of concrete pavement that achieve a lot pay factor less than 100%; except for rejected lots which remain in place and/or sublots with adjustments for repairs.

**b. Adjusted payment for repairs.** The PWL lot pay factor shall be reduced by 5% and be no higher than 95% for sublots which contain repairs in accordance with paragraph 501-4.19 on more than 20% of the slabs within the subplot. Payment factors greater than 100 percent for the strength and thickness cannot be used to offset adjustments for repairs.

**c. Adjusted payment for grinding.** The PWL lot pay factor shall be reduced by 5% and be no higher than 95% for sublots with grinding over 25% of a subplot.

**d. Profilograph Roughness.** The Contractor will receive full payment when the profilograph average profile index is in accordance with paragraph 501-6.6b(4). When the final average profile index for the entire length of pavement does not exceed 15 inches per mile per 1/10 mile, payment will be made at the contract unit price for the completed pavement.

**e. Payment.**

Payment shall be made under:

Item P-501-8.1	Cement Concrete Pavement, 13.5 inch Depth – per square yard
Item P-501-8.2	Reinforced Cement Concrete Pavement, 13.5 inch Depth – per square yard
Item P-501-8.3	Isolated Concrete Slab Replacement, Variable Depth – per square yard
Item P-501-8.4	Concrete Transition Slabs – per linear foot

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM A184	Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A615	Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A704	Standard Specification for Welded Steel Plain Bar or Rod Mats for Concrete Reinforcement
ASTM A706	Standard Specification for Low-Alloy Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM A775	Standard Specification for Epoxy-Coated Steel Reinforcing Bars
ASTM A884	Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement
ASTM A934	Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars

ASTM A996	Standard Specification for Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement
ASTM A1035	Standard Specification for Deformed and Plain, Low-Carbon, Chromium, Steel Bars for Concrete Reinforcement
ASTM A1064	Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM A1078	Standard Specification for Epoxy-Coated Steel Dowels for Concrete Pavement
ASTM C29	Standard Test Method for Bulk Density (“Unit Weight”) and Voids in Aggregate
ASTM C31	Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33	Standard Specification for Concrete Aggregates
ASTM C39	Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C70	Standard Test Method for Surface Moisture in Fine Aggregate
ASTM C78	Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C88	Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C94	Standard Specification for Ready-Mixed Concrete
ASTM C114	Standard Test Methods for Chemical Analysis of Hydraulic Cement
ASTM C117	Standard Test Method for Materials Finer than 75- $\mu$ m (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C123	Standard Test Method for Lightweight Particles in Aggregate
ASTM C136	Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C138	Standard Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete
ASTM C142	Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM C143	Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150	Standard Specification for Portland Cement
ASTM C171	Standard Specification for Sheet Materials for Curing Concrete
ASTM C172	Standard Practice for Sampling Freshly Mixed Concrete

ASTM C173	Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method
ASTM C174	Standard Test Method for Measuring Thickness of Concrete Elements Using Drilled Concrete Cores
ASTM C227	Standard Test Method for Potential Alkali Reactivity of Cement-Aggregate Combinations (Mortar-Bar Method)
ASTM C231	Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260	Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C295	Standard Guide for Petrographic Examination of Aggregates for Concrete
ASTM C309	Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C311	Standard Test Methods for Sampling and Testing Fly Ash or Natural Pozzolans for Use in Portland Cement Concrete
ASTM C494	Standard Specification for Chemical Admixtures for Concrete
ASTM C566	Standard Test Method for Total Evaporable Moisture Content of Aggregates by Drying
ASTM C595	Standard Specification for Blended Hydraulic Cements
ASTM C618	Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C642	Standard Test Method for Density, Absorption, and Voids in Hardened Concrete
ASTM C666	Standard Test Method for Resistance of Concrete to Rapid Freezing and Thawing
ASTM C685	Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing
ASTM C881	Standard Specification for Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C989	Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1017	Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C1064	Test Method for Temperature of Freshly Mixed Hydraulic-Cement Concrete
ASTM C1077	Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1157	Standard Performance Specification for Hydraulic Cement
ASTM C1260	Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)

ASTM C1365	Standard Test Method for Determination of the Proportion of Phases in Portland Cement and Portland-Cement Clinker Using X-Ray Powder Diffraction Analysis
ASTM C1567	Standard Test Method for Determining the Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C1602	Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete
ASTM D75	Standard Practice for Sampling Aggregates
ASTM D1751	Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D1752	Standard Specification for Preformed Sponge Rubber and Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction
ASTM D2419	Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D4791	Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM E178	Standard Practice for Dealing with Outlying Observations
ASTM E1274	Standard Test Method for Measuring Pavement Roughness Using a Profilograph
ASTM E2133	Standard Test Method for Using a Rolling Inclinator to Measure Longitudinal and Transverse Profiles of a Traveled Surface
American Concrete Institute (ACI)	
ACI 305R	Guide to Hot Weather Concreting
ACI 306R	Guide to Cold Weather Concreting
ACI 309R	Guide for Consolidation of Concrete
Advisory Circulars (AC)	
AC 150/5320-6	Airport Pavement Design and Evaluation
Federal Highway Administration (FHWA)	
HIPERPAV 3, version 3.2	
Portland Concrete Association (PCA)	
PCA	Design and Control of Concrete Mixtures, 16 <sup>th</sup> Edition
U.S. Army Corps of Engineers (USACE) Concrete Research Division (CRD)	
CRD C662	Determining the Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials, Lithium Nitrate Admixture and Aggregate (Accelerated Mortar-Bar Method)

United States Air Force Engineering Technical Letter (ETL)

ETL 97-5

Proportioning Concrete Mixtures with Graded Aggregates for Rigid  
Airfield Pavements

**END ITEM P-501**

Page Intentionally Blank

## Item P-603 Emulsified Asphalt Tack Coat

### DESCRIPTION

**603-1.1** This item shall consist of preparing and treating an asphalt or concrete surface with asphalt material in accordance with these specifications and in reasonably close conformity to the lines shown on the plans.

### MATERIALS

**603-2.1 Asphalt materials.** The asphalt material shall be an emulsified asphalt as specified in ASTM D3628 as an asphalt application for tack coat appropriate to local conditions. The emulsified asphalt shall not be diluted. The Contractor shall provide a copy of the manufacturer's Certificate of Analysis (COA) for the asphalt material to the Resident Project Representative (RPR) before the asphalt material is applied for review and acceptance. The furnishing of COA for the asphalt material shall not be interpreted as a basis for final acceptance. The manufacturer's COA may be subject to verification by testing the material delivered for use on the project.

The Contractor shall use an approved emulsified asphalt material shown on VDOT's Approved List 50.1A. CMS-2 conforming to Section 210 of VDOT specifications may be used during the winter months.

**Table 1 Bituminous Material**

Type and Grade	Specification
CQS-1h CRS-1h CSS-1h	Section 210 Virginia Department of Transportation 2016 Road and Bridge Specifications
Non-Tracking Tack	

### CONSTRUCTION METHODS

**603-3.1 Weather limitations.** The tack coat shall be applied only when the existing surface is dry and the atmospheric temperature is 50°F (10°C) or above; the temperature has not been below 35°F (2°C) for the 12 hours prior to application; and when the weather is not foggy or rainy. The temperature requirements may be waived when directed by the RPR.

**603-3.2 Equipment.** The Contractor shall provide equipment for heating and applying the emulsified asphalt material. The emulsion shall be applied with a manufacturer-approved computer rate-controlled asphalt distributor. The equipment shall be in good working order and contain no contaminants or diluents in the tank. Spray bar tips must be clean, free of burrs, and of a size to maintain an even distribution of the emulsion. Any type of tip or pressure source is suitable that will maintain predetermined flow rates and constant pressure during the application process with application speeds under eight (8) miles per hour (13 km per hour) or seven (700) feet per minute (213 m per minute).



The equipment will be tested under pressure for leaks and to ensure proper set-up before use to verify truck set-up (via a test-shot area), including but not limited to, nozzle tip size appropriate for application, spray-bar height and pressure and pump speed, evidence of triple-overlap spray pattern, lack of leaks, and any other factors relevant to ensure the truck is in good working order before use.

The distributor truck shall be equipped with a minimum 12-foot (3.7-m) spreader spray bar with individual nozzle control with computer-controlled application rates. The distributor truck shall have an easily accessible thermometer that constantly monitors the temperature of the emulsion, and have an operable mechanical tank gauge that can be used to cross-check the computer accuracy. If the distributor is not equipped with an operable quick shutoff valve, the prime operations shall be started and stopped on building paper.

The distributor truck shall be equipped to effectively heat and mix the material to the required temperature prior to application as required. Heating and mixing shall be done in accordance with the manufacturer's recommendations. Do not overheat or over mix the material.

The distributor shall be equipped with a hand sprayer.

Asphalt distributors must be calibrated annually in accordance with ASTM D2995. The Contractor must furnish a current calibration certification for the asphalt distributor truck from any State or other agency as approved by the RPR.

A power broom and/or power blower suitable for cleaning the surfaces to which the asphalt tack coat is to be applied shall be provided.

**603-3.3 Application of emulsified asphalt material.** The emulsified asphalt shall not be diluted. Immediately before applying the emulsified asphalt tack coat, the full width of surface to be treated shall be swept with a power broom and/or power blower to remove all loose dirt and other objectionable material.

The emulsified asphalt material shall be uniformly applied with an asphalt distributor at the rates appropriate for the conditions and surface specified in the table below. The type of asphalt material and application rate shall be approved by the RPR prior to application.

**Emulsified Asphalt**

Surface Type	Residual Rate, gal/SY (L/square meter)	Emulsion Application Bar Rate, gal/SY (L/square meter)
New asphalt	0.02-0.05 (0.09-0.23)	0.03-0.07 (0.13-0.32)
Existing asphalt	0.04-0.07 (0.18-0.32)	0.06-0.11 (0.27-0.50)
Milled Surface	0.04-0.08 (0.18-0.36)	0.06-0.12 (0.27-0.54)
Concrete	0.03-0.05 (0.13-0.23)	0.05-0.08 (0.23-0.36)

After application of the tack coat, the surface shall be allowed to cure without being disturbed for the period of time necessary to permit drying and setting of the tack coat. This period shall be determined by the RPR. The Contractor shall protect the tack coat and maintain the surface until the next course has been placed. When the tack coat has been disturbed by the Contractor, tack coat shall be reapplied at the Contractor's expense.

**603-3.4 Freight and waybills** The Contractor shall submit waybills and delivery tickets, during progress of the work. Before the final statement is allowed, file with the RPR certified waybills and certified delivery tickets for all emulsified asphalt materials used in the construction of the pavement covered by the contract. Do not remove emulsified asphalt material from storage until the initial outage and

temperature measurements have been taken. The delivery or storage units will not be released until the final outage has been taken.

### **METHOD OF MEASUREMENT**

**603-4.1** The emulsified asphalt material for tack coat shall be measured by the gallon. Volume shall be corrected to the volume at 60°F (16°C) in accordance with ASTM D1250. The emulsified asphalt material paid for will be the measured quantities used in the accepted work, provided that the measured quantities are not 10% over the specified application rate. Any amount of emulsified asphalt material more than 10% over the specified application rate for each application will be deducted from the measured quantities, except for irregular areas where hand spraying of the emulsified asphalt material is necessary. Water added to emulsified asphalt will not be measured for payment.

### **BASIS OF PAYMENT**

**603.5-1** Payment shall be made at the contract unit price per gallon of emulsified asphalt material. This price shall be full compensation for furnishing all materials, for all preparation, delivery, and application of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-603-5.1	Emulsified Asphalt Tack Coat - per gallon
----------------	---

### **REFERENCES**

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM D1250	Standard Guide for Use of the Petroleum Measurement Tables
ASTM D2995	Standard Practice for Estimating Application Rate and Residual Application Rate of Bituminous Distributors
ASTM D3628	Standard Practice for Selection and Use of Emulsified Asphalts

### **END ITEM P-603**

**Page Intentionally Blank**

## Item P-604 Compression Joint Seals for Concrete Pavements

### DESCRIPTION

**604-1.1** This item shall consist of preformed polychloroprene compression seals used for sealing joints of rigid pavements.

### MATERIALS

**604-2.1 Compression seals.** Compression joint seal materials shall be a vulcanized elastomeric compound using polychloroprene as the only base polymer. The material and the manufactured seal shall conform to ASTM D2628.

The joint seal shall be a labyrinth type seal. The uncompressed depth of the face of the compression seal (that is to be bonded to the joint wall) shall be greater than the uncompressed width of the seal, except that for seals one inch (25 mm) or greater in width, the depth need be only one inch (25 mm) or greater. The actual width of the uncompressed seal shall be as recommended by the joint seal manufacturer for the type and width of joints as shown on the plans. The tolerance on the seal shall be +1/8 inch or -1/16 inch (+3 mm or -2 mm), below the top of the pavement surface or bottom of groove for grooved pavement.

The Contractor shall provide a copy of the manufacturer's Certificate of Analysis (COA) for the joint seal material delivered to the project. The COA shall be provided to and approved by the RPR before the material is installed. The furnishing of the vendor's certified test report shall not be interpreted as a basis for final acceptance. The manufacturer's COA may be subject to verification by testing the material delivered for use on the project.

Materials delivered to the job site shall be inspected for defects, unloaded, and stored with a minimum of handling to avoid damage. Storage facilities shall be provided at the job site to protect materials from weather and maintain materials at temperatures recommended by the manufacturer.

Representative sample of joint seal material will be sampled and retained by the RPR for possible testing.

**604-2.2 Lubricant/adhesive.** Lubricant/adhesive used for the compression elastomeric joint seal shall be a one-component compound conforming to ASTM D2835.

### CONSTRUCTION METHODS

**604-3.1 Equipment.** Machines, tools, and equipment used in the performance of the work required by this section shall be approved by the RPR before the work starts and shall be maintained by the Contractor in satisfactory condition at all times.

#### a. Joint cleaning equipment.

(1) **Concrete saw.** A self-propelled power saw with water-cooled diamond saw blades shall be provided for cutting joints to the depths and widths specified and for removing filler, existing old joint seal or other material embedded in the joints or adhered to the joint faces.

(2) **Waterblasting equipment.** Waterblasting equipment shall include a trailer-mounted water tank, pumps, high-pressure hose, a wand with safety release cutoff controls, nozzle, and auxiliary water resupply equipment. The water tank and auxiliary water resupply equipment shall be of sufficient

capacity to permit continuous operations. The pumps, hoses, wand, and nozzle shall be of sufficient capacity to permit the cleaning of both walls of the joint and the pavement surface for a width of at least 1/2 inch (12 mm) on either side of the joint. The pump shall be capable of supplying a pressure of at least 3,000 psi (20.7 MPa). A pressure gauge mounted at the pump shall show at all times the pressure in pounds per square inch (psi) (kPa) at which the equipment is operating.

**(3) Sandblasting equipment.** Sandblasting is not allowed.

**b. Sealing equipment.** Equipment used to install the compression seal shall place the compression seal to the prescribed depths within the specified tolerances without cutting, nicking, twisting, or otherwise damaging the seal. The equipment shall not stretch or compress the seal more than 2.0% longitudinally during installation. The machine shall be an automatic self-propelled joint seal application equipment and shall be engine powered. The machine shall include a reservoir for the lubricant/adhesive, a device for conveying the lubricant/adhesive in the proper quantities to the sides the preformed seal or the sidewalls of the joint, a reel capable of holding one full spool of compression seal, and a power-driven apparatus for feeding the joint seal through a compression device and inserting the seal into the joint. The equipment shall also include a guide to maintain the proper course along the joint being sealed. The machine shall at all times be operated by an experienced operator.

Hand operated joint seal application equipment may be used for localized areas and for projects less than 500 square yards (450 square meters). The equipment shall be a two-axle, four-wheel machine that includes means for compressing and inserting the compression seal into the joint and a reel capable of holding one full spool of compression seal material.

## CONSTRUCTION METHODS

**604-4.1 Environmental conditions.** The ambient temperature and the pavement temperature within the joint wall shall be at least 35°F (2°C) and rising at the time of installation of the materials. Sealant application will not be permitted if moisture or any foreign material is observed in the joint.

**604-4.2 Trial joint seal and lubricant/adhesive installation.** Prior to the cleaning and sealing of the joints for the entire project, a control strip at least 200 feet (69 meters) long shall be prepared at a location designated by the RPR using the specified materials and the approved equipment, to demonstrate the materials and construction processes for joint preparation and sealing of all types of joints included in the project. No other joints shall be sealed until the test installation has been approved by the RPR.

If materials or installation do not meet requirements, the materials shall be removed, and the joints shall be cleaned and a new trial joint seal installation shall be performed at the Contractor's expense. The RPR approved trial section will be incorporated into the permanent work.

**604-4.3 Preparation of joints.** Immediately before installation of the compression joint seal, the joints shall be thoroughly cleaned to remove all laitance, filler, existing sealer, foreign material and protrusions of hardened concrete from the sides and upper edges of the joint space to be sealed. Cleaning shall extend along pavement surfaces at least 1/2 inch (12 mm) on either side of the joint. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left free of debris and water. Any irregularity in the joint face that would prevent uniform contact between the joint seal and the joint face shall be corrected prior to the installation of the joint seal.

**a. Sawing.** Joints shall be sawed to clean and to open them to the full specified width and depth. Immediately following the sawing operation, the joint faces and opening shall be thoroughly cleaned using a water jet to remove all saw cuttings or debris remaining on the faces or in the joint opening. Compression seal shall be installed within three (3) calendar days of the time the joint cavity is sawed. Depth of the joint cavity shall be in accordance with manufacturer's instructions. Submit printed copies of manufacturers' instructions 60 days prior to use on the project. The saw cut for the joint seal cavity

shall at all locations be centered over the joint line. The nominal width of the sawed joint seal cavity shall be as follows; the actual width shall be within a tolerance of  $\pm 1/16$  inch (2 mm):

(1) ~~If a nominal 13/16 inch (21 mm) wide compression seal is furnished, the nominal width of the saw cut shall be [ ] inches ([ ] mm) when the pavement temperature at the time of sawing is between [ ] and [ ]°F ([ ] and [ ]°C). If the pavement temperature at the time of sawing is above this range, the nominal width of the saw cut shall be decreased 1/16 inch (2 mm). If the pavement temperature at the time of sawing is below this range, the nominal width of the saw cut shall be increased 1/16 inch (2 mm).~~

(2) If a nominal one inch (25 mm) wide compression seal is furnished, the nominal width of the saw cut shall be **as indicated in the plans** when the pavement temperature at the time of sawing is between 25 and 140°F. If the pavement temperature at the time of sawing is above this range, the nominal width of the saw cut shall be decreased 1/16 inch (2 mm). If the pavement temperature at the time of sawing is below this range, the nominal width of the saw cut shall be increased 1/16 inch (2 mm).

(3) The pavement temperature shall be measured and recorded in the presence of the RPR. Measurement shall be made each day before commencing sawing and at any other time during the day when the temperature appears to be moving out of the allowable sawing range.

**b. Waterblast cleaning.** The concrete joint faces and pavement surfaces extending at least 1/2 inch (12 mm) from the joint edges shall be waterblasted clean. A multiple pass technique shall be used until the surfaces are free of dust, dirt, curing compound, or any residue that might prevent ready insertion or uniform contact of the seal and bonding of the lubricant/adhesive to the concrete. After final cleaning and immediately prior to sealing, the joints shall be blown out with compressed air and left completely free of debris and water.

**c. Sandblast cleaning.** Sandblast cleaning is not allowed.

**d. Rate of progress.** Cleaning of the joint faces shall be limited to the linear footage of joint that can be sealed during the same workday.

#### 604-4.4 Installation of the compression seal.

**a. Time of installation.** Joints shall be sealed within 3 calendar days of sawing the joint seal cavity and the final cleaning of the joint walls, or a temporary seal shall be installed to prevent infiltration of foreign material. If rain interrupts the sealing operations, the joints shall be washed, cleaned with air and be dry before proceeding with installing of the lubricant/adhesive and compression seal.

**b. Installation Sequence.** Longitudinal joints shall be sealed first, then seal the transverse joints. Transverse joint seals will be continuous from edge to edge of the pavement. Intersections shall be made monolithic by use of joint seal adhesive and care in fitting the intersection parts together. Seals which do not reach an intersection shall be removed and replaced with new seal as directed by the RPR at the Contractor's Expense. Seal extender pieces shall not be used at intersections.

**c. Sealing joints.** The sides of the joint seal or the sides of the joint shall be covered with a coating of lubricant/adhesive and the seal installed as specified. Butt joints and seal intersections shall be coated with liberal applications of lubricant/adhesive. Lubricant/adhesive spilled on the pavement shall be removed immediately to prevent setting on the pavement.

The joint seal shall be placed at a uniform depth within the tolerances specified. The compression joint seal shall be placed to a depth of 3/16 inch (5 mm),  $\pm 1/8$  inch (3 mm), below the pavement surface or below the depth of the groove unless otherwise directed by the RPR.

The seal shall be installed in the longest practicable lengths in longitudinal joints and shall be cut at the joint intersections to provide continuous installation of the seal in the transverse joints. The joint seal shall be installed in an upright position, free from twisting, distortion, and cuts. If stretch of installed joint seal

exceeds 1%, adjustments shall be made to the installation equipment and procedure. Stretch of installed joint seals exceeding 2% stretch shall be removed and replaced.

After installation of the longitudinal joint seals, it shall set for a minimum of one (1) hour prior to cutting the seal at the joint intersections. For all transverse joints, the minimum length of the preformed joint seal shall be the pavement width from edge to edge.

**604-4.5 Clean-up.** Upon completion of the project, all unused materials shall be removed from the site, all lubricant/adhesive on the pavement surface shall be removed, and the pavement shall be left in clean condition.

#### **604-4.6 Quality Control and Quality Assurance.**

**a. Quality Control** The application equipment shall be inspected to assure uniform application of lubricant/adhesive to the sides of the compression joint seal or the walls of the joint. Equipment causing cutting, twisting, nicking, excessive stretching or compressing of the compression seal, or improper application of the lubricant/adhesive, shall not be used until causes of the deficiencies are determined and corrected by the Contractor.

The seal shall be inspected by the Contractor a minimum of once per 400 feet (120 m) of seal for compliance to the shrinkage or compression requirements. Measurements shall be made at the same interval to determine conformance with depth and width installation requirements.

**b. Quality Assurance.** Cleaned joints shall be approved by the RPR prior to installation of the lubricant/adhesive and compression joint seal.

Conformance to stretching and compression limitations shall be determined by the RPR using the following procedures:

(1) Mark the top surface of the compression seal at one foot (30 cm) intervals in a manner clear and durable to enable length determinations of the seal.

(2) After installation, the distance between the marks on the seal shall be measured by the Contractor.

(3) If the stretching or compression exceeds the specified limit, the seal shall be removed and replaced with new joint seal at the Contractor's Expense. The seal shall be removed up to the last correct measurement.

**604-4.7 Acceptance.** The joint sealing system (compression seal and lubricant/adhesive) shall be inspected by the RPR for proper rate of cure and bonding to the concrete, cuts, twists, nicks, and other deficiencies. Seals exhibiting any defects prior to final acceptance of the project, shall be removed from the joint, wasted, and replaced with new material in a satisfactory manner, at the Contractor's expense, as determined by the RPR.

### **METHOD OF MEASUREMENT**

**604-5.1 Measurement.** The quantity of compression joint seals installed and accepted, will be determined by the linear feet (meter).

### **BASIS OF PAYMENT**

**604-6.1 Payment.** Payment will be made at the contract unit bid prices per linear foot (meter) for the compression joint seals. The unit bid prices shall include the cost of all labor, materials, the use of all equipment, and tools required to complete the work.

Item 604-6.1

Compression Joint Seals for Concrete Pavements – per linear feet

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### ASTM International (ASTM)

- |            |  |
|------------|--|
| ASTM D2628 | Standard Specification for Preformed Polychloroprene Elastomeric Joint Seals for Concrete Pavements        |
| ASTM D2835 | Standard Specification for Lubricant for Installation of Preformed Compression Seals in Concrete Pavements |

### Corps of Engineers

- |          |  |
|----------|--|
| CRD C548 | Standard Specification for Jet-Fuel and Heat Resistant Preformed Polychloroprene Elastomeric Joint Seals for Rigid Pavements |
|----------|--|

### Unified Facilities Criteria (UFC)

- |                |   |
|----------------|---|
| UFC 3-250-08FA | Standard Practice for Sealing Joints and Cracks in Rigid and Flexible Pavements |
|----------------|---|

**END ITEM P-604**



Page Intentionally Blank

## Item P-605 Joint Sealants for Pavements

### DESCRIPTION

**605-1.1** This item shall consist of providing and installing a resilient and adhesive joint sealing material capable of effectively sealing joints in pavement; joints between different types of pavements; and cracks in existing pavement.

### MATERIALS

**605-2.1 Joint sealants.** Joint sealant materials shall meet the requirements of ASTM D7116 or ASTM D5893.

Each lot or batch of sealant shall be delivered to the jobsite in the manufacturer's original sealed container. Each container shall be marked with the manufacturer's name, batch or lot number, the safe heating temperature, and shall be accompanied by the manufacturer's certification stating that the sealant meets the requirements of this specification.

**605-2.2 Backer rod.** The material furnished shall be a compressible, non-shrinking, non-staining, non-absorbing material that is non-reactive with the joint sealant in accordance with ASTM D5249. The backer-rod material shall be  $25\% \pm 5\%$  larger in diameter than the nominal width of the joint.

**605-2.3 Bond breaking tapes.** ~~Not used. Provide a bond breaking tape or separating material that is a flexible, non-shrinkable, non-absorbing, non-staining, and non-reacting adhesive backed tape. The material shall have a melting point at least 5°F (3°C) greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D789. The bond breaker tape shall be approximately 1/8 inch (3 mm) wider than the nominal width of the joint and shall not bond to the joint sealant.~~

### CONSTRUCTION METHODS

**605-3.1 Time of application.** Joints shall be sealed as soon after completion of the curing period as feasible and before the pavement is opened to traffic, including construction equipment. The pavement temperature shall be 50°F (10°C) and rising at the time of application of the poured joint sealing material. Do not apply sealant if moisture is observed in the joint.

**605-3.2 Equipment.** Machines, tools, and equipment used in the performance of the work required by this section shall be approved before the work is started and maintained in satisfactory condition at all times. Submit a list of proposed equipment to be used in performance of construction work including descriptive data, 30 days prior to use on the project.

**a. Concrete saw.** Provide a self-propelled power saw, with water-cooled diamond or abrasive saw blades, for cutting joints to the depths and widths specified.

**b. Sandblasting equipment.** Sandblasting is not allowed.

**c. Waterblasting equipment.** The Contractor must demonstrate waterblasting equipment including the pumps, hose, guide and nozzle size, under job conditions, before approval in accordance with

paragraph 605-3.3. The Contractor shall demonstrate, in the presence of the RPR, that the method cleans the joint and does not damage the joint.

**d. Hand tools.** Hand tools may be used, when approved, for removing defective sealant from a crack and repairing or cleaning the crack faces. Hand tools should be carefully evaluated for potential spalling effects prior to approval for use.

**e. Hot-poured sealing equipment.** The unit applicators used for heating and installing ASTM D6690 joint sealant materials shall be mobile and shall be equipped with a double-boiler, agitator-type kettle with an oil medium in the outer space for heat transfer; a direct-connected pressure-type extruding device with a nozzle shaped for inserting in the joint to be filled; positive temperature devices for controlling the temperature of the transfer oil and sealant; and a recording type thermometer for indicating the temperature of the sealant. The applicator unit shall be designed so that the sealant will circulate through the delivery hose and return to the inner kettle when not in use.

**f. Cold-applied, single-component sealing equipment.** The equipment for installing ASTM D5893 single component joint sealants shall consist of an extrusion pump, air compressor, following plate, hoses, and nozzle for transferring the sealant from the storage container into the joint opening. The dimension of the nozzle shall be such that the tip of the nozzle will extend into the joint to allow sealing from the bottom of the joint to the top. Maintain the initially approved equipment in good working condition, serviced in accordance with the supplier's instructions, and unaltered in any way without obtaining prior approval. Small hand-held air-powered equipment (i.e., caulking guns) may be used for small applications.

**605-3.3 Preparation of joints.** Pavement joints for application of material in this specification must be dry, clean of all scale, dirt, dust, curing compound, and other foreign matter. The Contractor shall demonstrate, in the presence of the RPR, that the method cleans the joint and does not damage the joint.

**a. Sawing.** All joints shall be sawed in accordance with specifications and plan details. Immediately after sawing the joint, the resulting slurry shall be completely removed from joint and adjacent area by flushing with a jet of water, and by use of other tools as necessary.

**b. Sealing.** Immediately before sealing, the joints shall be thoroughly cleaned of all remaining laitance, curing compound, filler, protrusions of hardened concrete, old sealant and other foreign material from the sides and upper edges of the joint space to be sealed. Cleaning shall be accomplished by waterblaster as specified in paragraph 605-3.2. The newly exposed concrete joint faces and the pavement surface extending a minimum of 1/2 inch (12 mm) from the joint edge shall be sandblasted clean. Sandblasting shall be accomplished in a minimum of two passes. One pass per joint face with the nozzle held at an angle directly toward the joint face and not more than 3 inches (75 mm) from it. After final cleaning and immediately prior to sealing, blow out the joints with compressed air and leave them completely free of debris and water. The joint faces shall be surface dry when the seal is applied.

**c. Backer Rod.** When the joint opening is of a greater depth than indicated for the sealant depth, plug or seal off the lower portion of the joint opening using a backer rod in accordance with paragraph 605-2.2 to prevent the entrance of the sealant below the specified depth. Take care to ensure that the backer rod is placed at the specified depth and is not stretched or twisted during installation.

**d. Bond-breaking tape.** ~~Not used. Where inserts or filler materials contain bitumen, or the depth of the joint opening does not allow for the use of a backup material, insert a bond separating tape breaker in accordance with paragraph 605-2.3 to prevent incompatibility with the filler materials and three-sided adhesion of the sealant. Securely bond the tape to the bottom of the joint opening so it will not float up into the new sealant.~~

**605-3.4 Installation of sealants.** Joints shall be inspected for proper width, depth, alignment, and preparation, and shall be approved by the RPR before sealing is allowed. Sealants shall be installed in accordance with the following requirements:

Immediately preceding, but not more than 50 feet (15 m) ahead of the joint sealing operations, perform a final cleaning with compressed air. Fill the joints from the bottom up to 1/4 inch  $\pm$  1/16 inch below the top of pavement surface; or bottom of groove for grooved pavement. Remove and discard excess or spilled sealant from the pavement by approved methods. Install the sealant in such a manner as to prevent the formation of voids and entrapped air. In no case shall gravity methods or pouring pots be used to install the sealant material. Traffic shall not be permitted over newly sealed pavement until authorized by the RPR. When a primer is recommended by the manufacturer, apply it evenly to the joint faces in accordance with the manufacturer's instructions. Check the joints frequently to ensure that the newly installed sealant is cured to a tack-free condition within the time specified.

**605-3.5 Inspection.** The Contractor shall inspect the joint sealant for proper rate of cure and set, bonding to the joint walls, cohesive separation within the sealant, reversion to liquid, entrapped air and voids. Sealants exhibiting any of these deficiencies at any time prior to the final acceptance of the project shall be removed from the joint, wasted, and replaced as specified at no additional cost to the airport.

**605-3.6 Clean-up.** Upon completion of the project, remove all unused materials from the site and leave the pavement in a clean condition.

## METHOD OF MEASUREMENT

**605-4.1** Joint sealing material shall be measured by the linear foot of sealant in place, completed, and accepted.

## BASIS OF PAYMENT

**605-5.1** Payment for joint sealing material shall be made at the contract unit price per linear foot. The price shall be full compensation for furnishing all materials, for all preparation, delivering, and placing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-605-5.1	Joint Sealing Filler – per linear foot
----------------	--

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM D789	Standard Test Method for Determination of Relative Viscosity of Polyamide (PA)
ASTM D5249	Standard Specification for Backer Material for Use with Cold- and Hot-Applied Joint Sealants in Portland-Cement Concrete and Asphalt Joints
ASTM D5893	Standard Specification for Cold Applied, Single Component, Chemically Curing Silicone Joint Sealant for Portland Cement Concrete Pavements
ASTM D7116	Standard Specification for Joint Sealants, Hot Applied, Jet Fuel Resistant Types for Portland Cement Concrete Pavements

Advisory Circulars (AC)

AC 150/5340-30

Design and Installation Details for Airport Visual Aids

**END ITEM P-605**

## Item P-610 Concrete for Miscellaneous Structures

### DESCRIPTION

**610-1.1** This item shall consist of concrete and reinforcement, as shown on the plans, prepared and constructed in accordance with these specifications. This specification shall be used for all concrete other than airfield pavement which are cast-in-place.

### MATERIALS

**610-2.1 General.** Only approved materials, conforming to the requirements of these specifications, shall be used in the work. Materials may be subject to inspection and tests at any time during their preparation or use. The source of all materials shall be approved by the Resident Project Representative (RPR) before delivery or use in the work. Representative preliminary samples of the materials shall be submitted by the Contractor, when required, for examination and test. Materials shall be stored and handled to ensure preservation of their quality and fitness for use and shall be located to facilitate prompt inspection. All equipment for handling and transporting materials and concrete must be clean before any material or concrete is placed in them.

The use of pit-run aggregates shall not be permitted unless the pit-run aggregate has been screened and washed, and all fine and coarse aggregates stored separately and kept clean. The mixing of different aggregates from different sources in one storage stockpile or alternating batches of different aggregates shall not be permitted.

**a. Reactivity.** Fine aggregate and coarse aggregates to be used in all concrete shall have been tested separately within six months of the project in accordance with ASTM C1260. Test results shall be submitted to the RPR. The aggregate shall be considered innocuous if the expansion of test specimens, tested in accordance with ASTM C1260, does not exceed 0.08% at 14 days (16 days from casting). If the expansion either or both test specimen is greater than 0.08% at 14 days, but less than 0.20%, a minimum of 25% of Type F fly ash, or between 40% and 55% of slag cement shall be used in the concrete mix.

If the expansion is greater than 0.20%, the aggregates shall not be used, and test results for other aggregates must be submitted for evaluation; or aggregates that meet P-501 reactivity test requirements may be utilized.

**610-2.2 Coarse aggregate.** The coarse aggregate for concrete shall meet the requirements of ASTM C33 and the requirements of Table 4, Class Designation 5S; and the grading requirements shown below, as required for the project.

### Coarse Aggregate Grading Requirements

Maximum Aggregate Size	ASTM C33, Table 3 Grading Requirements (Size No.)
1 inch (25 mm)	57
$\frac{3}{4}$ inch (19 mm)	67
$\frac{1}{2}$ inch (12.5 mm)	7

**610-2.2.1 Coarse Aggregate susceptibility to durability (D) cracking.** Coarse aggregate may only be accepted from sources that have a 20-year service history for the same gradation to be supplied with no history of D-Cracking. Aggregates that do not have a 20-year record of service free from major repairs (less than 5% of slabs replaced) in similar conditions without D-cracking shall not be used unless the material currently being produced has a durability factor greater than or equal to 95 per ASTM C666. The Contractor shall submit a current certification and test results to verify the aggregate acceptability. Test results will only be accepted from a State Department of Transportation (DOT) materials laboratory or an accredited laboratory. Certification and test results which are not dated or which are over one (1) year old or which are for different gradations will not be accepted.

Crushed granite, calcite cemented sandstone, quartzite, basalt, diabase, rhyolite or trap rock are considered to meet the D-cracking test requirements but must meet all other quality tests specified in Item P-501.

**610-2.3 Fine aggregate.** The fine aggregate for concrete shall meet all fine aggregate requirements of ASTM C33.

**610-2.4 Cement.** Cement shall conform to the requirements of ASTM C150 Type I or II. [Fast setting cement to make grouts and concretes shall be non-shrink, conforming to the requirements of ASTM C1600. The minimum compressive strength at 1.5 hours shall be no less than 4,000 psi in accordance to C109. ASTM C150 Type III shall not be used.](#)

#### 610-2.5 Cementitious materials.

**a. Fly ash.** Fly ash shall meet the requirements of ASTM C618, with the exception of loss of ignition, where the maximum shall be less than 6%. Fly ash shall have a Calcium Oxide (CaO) content of less than 15% and a total available alkali content less than 3% per ASTM C311. Fly ash produced in furnace operations using liming materials or soda ash (sodium carbonate) as an additive shall not be acceptable. The Contractor shall furnish the previous three most recent, consecutive ASTM C618 reports for each source of fly ash proposed in the concrete mix, and shall furnish each additional report as they become available during the project. The reports can be used for acceptance or the material may be tested independently by the RPR.

**b. Slag cement (ground granulated blast furnace (GGBF)).** Slag cement shall conform to ASTM C989, Grade 100 or Grade 120. Slag cement shall be used only at a rate between 25% and 55% of the total cementitious material by mass.

**610-2.6 Water.** Water used in mixing or curing shall be from potable water sources. Other sources shall be tested in accordance with ASTM C1602 prior to use.

**610-2.7 Admixtures.** The Contractor shall submit certificates indicating that the material to be furnished meets all of the requirements indicated below. In addition, the RPR may require the Contractor to submit complete test data from an approved laboratory showing that the material to be furnished meets all of the requirements of the cited specifications. Subsequent tests may be made of samples taken by the RPR from the supply of the material being furnished or proposed for use on the work to determine whether the admixture is uniform in quality with that approved.

**a. Air-entraining admixtures.** Air-entraining admixtures shall meet the requirements of ASTM C260 and shall consistently entrain the air content in the specified ranges under field conditions. The air-entrainment agent and any water reducer admixture shall be compatible.

**b. Water-reducing admixtures.** Water-reducing admixture shall meet the requirements of ASTM C494, Type A, B, or D. ASTM C494, Type F and G high range water reducing admixtures and ASTM C1017 flowable admixtures shall not be used.

**c. Other chemical admixtures.** The use of set retarding, and set-accelerating admixtures shall be approved by the RPR. Retarding shall meet the requirements of ASTM C494, Type A, B, or D and set-accelerating shall meet the requirements of ASTM C494, Type C. Calcium chloride and admixtures containing calcium chloride shall not be used.

**610-2.8 Premolded joint material.** Premolded joint material for expansion joints shall meet the requirements of ASTM D1751 or ASTM D1752.

**610-2.9 Joint filler.** The filler for joints shall meet the requirements of Item P-605, unless otherwise specified.

**610-2.10 Steel reinforcement.** Reinforcing shall consist of reinforcing steel conforming to the requirements of ASTM A615, ASTM A706, ASTM A775, or ASTM A934; or welded steel wire fabric conforming to the requirements of ASTM A1064 or ASTM A884.

**610-2.11 Materials for curing concrete.** Curing materials shall conform to ASTM C309.

## CONSTRUCTION METHODS

**610-3.1 General.** The Contractor shall furnish all labor, materials, and services necessary for, and incidental to, the completion of all work as shown on the drawings and specified here. All machinery and equipment used by the Contractor on the work, shall be of sufficient size to meet the requirements of the work. All work shall be subject to the inspection and approval of the RPR.

**610-3.2 Concrete Mixture.** The concrete shall develop a compressive strength [as indicated below](#) in 28 days as determined by test cylinders made in accordance with ASTM C31 and tested in accordance with ASTM C39. The concrete shall contain not less than 470 pounds of cementitious material per cubic yard (280 kg per cubic meter). The water cementitious ratio shall not exceed 0.45 by weight. The air content of the concrete shall be 5% +/- 1.2% as determined by ASTM C231 and shall have a slump of not more than 4 inches (100 mm) as determined by ASTM C143.

### Concrete Mixtures

Structure	Referred Item	Minimum Compressive Strength, psi	Coarse Aggregate Size Group
Drainage	D-751	4,000	57

[Fast setting grout and concrete for electrical lights shall be pre-bagged material composed of fast setting hydraulic cement. The grout or concrete shall have at one hour a minimum compressive strength of 3,000 psi in accordance with ASTM C109 or ASTM C39, respectively.](#)

**610-3.3 Mixing.** Concrete may be mixed at the construction site, at a central point, or wholly or in part in truck mixers. The concrete shall be mixed and delivered in accordance with the requirements of ASTM C94 or ASTM C685.



The concrete shall be mixed only in quantities required for immediate use. Concrete shall not be mixed while the air temperature is below 40°F (4°C) without the RPRs approval. If approval is granted for mixing under such conditions, aggregates or water, or both, shall be heated and the concrete shall be placed at a temperature not less than 50°F (10°C) nor more than 100°F (38°C). The Contractor shall be held responsible for any defective work, resulting from freezing or injury in any manner during placing and curing, and shall replace such work at his expense.

Retempering of concrete by adding water or any other material is not permitted.

The rate of delivery of concrete to the job shall be sufficient to allow uninterrupted placement of the concrete.

**610-3.4 Forms.** Concrete shall not be placed until all the forms and reinforcements have been inspected and approved by the RPR. Forms shall be of suitable material and shall be of the type, size, shape, quality, and strength to build the structure as shown on the plans. The forms shall be true to line and grade and shall be mortar-tight and sufficiently rigid to prevent displacement and sagging between supports. The surfaces of forms shall be smooth and free from irregularities, dents, sags, and holes. The Contractor shall be responsible for their adequacy.

The internal form ties shall be arranged so no metal will show in the concrete surface or discolor the surface when exposed to weathering when the forms are removed. All forms shall be wetted with water or with a non-staining mineral oil, which shall be applied immediately before the concrete is placed. Forms shall be constructed so they can be removed without injuring the concrete or concrete surface.

**610-3.5 Placing reinforcement.** All reinforcement shall be accurately placed, as shown on the plans, and shall be firmly held in position during concrete placement. Bars shall be fastened together at intersections. The reinforcement shall be supported by approved metal chairs. Shop drawings, lists, and bending details shall be supplied by the Contractor when required.

**610-3.6 Embedded items.** Before placing concrete, all embedded items shall be firmly and securely fastened in place as indicated. All embedded items shall be clean and free from coating, rust, scale, oil, or any foreign matter. The concrete shall be spaded and consolidated around and against embedded items. The embedding of wood shall not be allowed.

**610-3.7 Concrete Consistency.** The Contractor shall monitor the consistency of the concrete delivered to the project site; collect each batch ticket; check temperature; and perform slump tests on each truck at the project site in accordance with ASTM C143.

**610-3.8 Placing concrete.** All concrete shall be placed during daylight hours, unless otherwise approved. The concrete shall not be placed until the depth and condition of foundations, the adequacy of forms and falsework, and the placing of the steel reinforcing have been approved by the RPR. Concrete shall be placed as soon as practical after mixing, but in no case later than one (1) hour after water has been added to the mix. The method and manner of placing shall avoid segregation and displacement of the reinforcement. Troughs, pipes, and chutes shall be used as an aid in placing concrete when necessary. The concrete shall not be dropped from a height of more than 5 feet (1.5 m). Concrete shall be deposited as nearly as practical in its final position to avoid segregation due to rehandling or flowing. Do not subject concrete to procedures which cause segregation. Concrete shall be placed on clean, damp surfaces, free from running water, or on a properly consolidated soil foundation.

**610-3.9 Vibration.** Vibration shall follow the guidelines in American Concrete Institute (ACI) Committee 309R, Guide for Consolidation of Concrete.

**610-3.10 Joints.** Joints shall be constructed as indicated on the plans.

**610-3.11 Finishing.** All exposed concrete surfaces shall be true, smooth, and free from open or rough areas, depressions, or projections. All concrete horizontal plane surfaces shall be brought flush to the proper elevation with the finished top surface struck-off with a straightedge and floated.

**610-3.12 Curing and protection.** All concrete shall be properly cured in accordance with the recommendations in American Concrete Institute (ACI) 308R, Guide to External Curing of Concrete. The concrete shall be protected from damage until project acceptance.

**610-3.13 Cold weather placing.** When concrete is placed at temperatures below 40°F (4°C), follow the cold weather concreting recommendations found in ACI 306R, Cold Weather Concreting.

**610-3.14 Hot weather placing.** When concrete is placed in hot weather greater than 85°F (30 °C), follow the hot weather concreting recommendations found in ACI 305R, Hot Weather Concreting.

## QUALITY ASSURANCE (QA)

**610-4.1 Quality Assurance sampling and testing.** Concrete for each day's placement will be accepted on the basis of the compressive strength specified in paragraph 610-3.2. The RPR will sample the concrete in accordance with ASTM C172; test the slump in accordance with ASTM C143; test air content in accordance with ASTM C231; make and cure compressive strength specimens in accordance with ASTM C31; and test in accordance with ASTM C39. The QA testing agency will meet the requirements of ASTM C1077.

The Contractor shall provide adequate facilities for the initial curing of cylinders.

**610-4.2 Defective work.** Any defective work that cannot be satisfactorily repaired as determined by the RPR, shall be removed and replaced at the Contractor's expense. Defective work includes, but is not limited to, uneven dimensions, honeycombing and other voids on the surface or edges of the concrete.

## METHOD OF MEASUREMENT

**610-5.1** Concrete shall be considered incidental and no separate measurement shall be made.

## BASIS OF PAYMENT

**610-6.1** No separate payment shall be made for structural concrete. It shall be considered incidental to the item requiring the concrete and furnishing all materials including reinforcement and embedded items and for all preparation, delivery, installation, and curing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item. ~~Payment shall be made at the contract price. This price shall be full compensation for furnishing all materials including reinforcement and embedded items and for all preparation, delivery, installation, and curing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.~~

~~Payment will be made under:~~

~~Item P 610-6.1 — Concrete, incidental to other work items~~

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM A184	Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
-----------	--

ASTM A615	Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A704	Standard Specification for Welded Steel Plain Bar or Rod Mats for Concrete Reinforcement
ASTM A706	Standard Specification for Low-Alloy Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM A775	Standard Specification for Epoxy-Coated Steel Reinforcing Bars
ASTM A884	Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement
ASTM A934	Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars
ASTM A1064	Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM C31	Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33	Standard Specification for Concrete Aggregates
ASTM C39	Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C94	Standard Specification for Ready-Mixed Concrete
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C114	Standard Test Methods for Chemical Analysis of Hydraulic Cement
ASTM C136	Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C143	Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150	Standard Specification for Portland Cement
ASTM C171	Standard Specification for Sheet Materials for Curing Concrete
ASTM C172	Standard Practice for Sampling Freshly Mixed Concrete
ASTM C231	Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260	Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C309	Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C311	Standard Test Methods for Sampling and Testing Fly Ash or Natural Pozzolans for Use in Portland-Cement Concrete
ASTM C494	Standard Specification for Chemical Admixtures for Concrete
ASTM C618	Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C666	Standard Test Method for Resistance of Concrete to Rapid Freezing and Thawing

ASTM C685	Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing
ASTM C989	Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1017	Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C1077	Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1157	Standard Performance Specification for Hydraulic Cement
ASTM C1260	Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C1365	Standard Test Method for Determination of the Proportion of Phases in Portland Cement and Portland-Cement Clinker Using X-Ray Powder Diffraction Analysis
ASTM C1602	Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete
ASTM D1751	Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Asphalt Types)
ASTM D1752	Standard Specification for Preformed Sponge Rubber Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction

## American Concrete Institute (ACI)

ACI 305R	Hot Weather Concreting
ACI 306R	Cold Weather Concreting
ACI 308R	Guide to External Curing of Concrete
ACI 309R	Guide for Consolidation of Concrete

**END OF ITEM P-610**

Page Intentionally Blank

## Item P-620 Runway and Taxiway Marking

### DESCRIPTION

**620-1.1** This item shall consist of the preparation and painting of numbers, markings, and stripes on the surface of runways, taxiways, and aprons, in accordance with these specifications and at the locations shown on the plans, or as directed by the Resident Project Representative (RPR). The terms “paint” and “marking material” as well as “painting” and “application of markings” are interchangeable throughout this specification.

### MATERIALS

**620-2.1 Materials acceptance.** The Contractor shall furnish manufacturer’s certified test reports, for materials shipped to the project. The certified test reports shall include a statement that the materials meet the specification requirements. This certification along with a copy of the paint manufacturer’s surface preparation; marking materials, including adhesion, flow promoting and/or floatation additive; and application requirements must be submitted and approved by the Resident Project Representative (RPR) prior to the initial application of markings. The reports can be used for material acceptance or the RPR may perform verification testing. The reports shall not be interpreted as a basis for payment. The Contractor shall notify the RPR upon arrival of a shipment of materials to the site. All material shall arrive in sealed containers that are easily quantifiable for inspection by the RPR.

**620-2.2 Marking materials.**

**Table 1. Marking Materials**

Paint <sup>1</sup>				Glass Beads <sup>2</sup>	
Type	Color	Fed Std. 595 Number	Application Rate Maximum	Type	Application Rate Minimum
Type III	Yellow	33538 or 33655	90 ft <sup>2</sup> /gal	Type III	8 lb/gal
Type III	White	37925	90 ft <sup>2</sup> /gal	Type III	8 lb/gal
Type III	Red	31136	90 ft <sup>2</sup> /gal	Type I Gradation A	7 lb/gal
Type III	Black	37038	90 ft <sup>2</sup> /gal	N/A	N/A
Temporary Marking Waterborne Type I			230 ft <sup>2</sup> /gal	N/A	N/A

<sup>1</sup> See paragraph 620-2.2a

<sup>2</sup> See paragraph 620-2.2b

**a. Paint.** Paint shall be waterborne in accordance with the requirements of this paragraph. Paint colors shall comply with Federal Standard No. 595.

**Waterborne.** Paint shall meet the requirements of Federal Specification TT-P-1952F, Type III. The non-volatile portion of the vehicle for all paint types shall be composed of a 100% acrylic polymer as determined by infrared spectral analysis. The acrylic resin used for Type III shall be 100% cross linking acrylic as evidenced by infrared peaks at wavelengths 1568, 1624, and 1672 cm-l with intensities equal to those produced by an acrylic resin known to be 100% cross linking.

**b. Reflective media.** Glass beads for white and yellow paint shall meet the requirements for Federal Specification TT-B-1325D Type III.

Glass beads for red and pink paint shall meet the requirements for Type I, Gradation A.

Glass beads shall be treated with all compatible coupling agents recommended by the manufacturers of the paint and reflective media to ensure adhesion and embedment.

Glass beads shall not be used in black and green paint.

Type III glass beads shall not be used in red and pink paint.

## CONSTRUCTION METHODS

**620-3.1 Weather limitations.** Painting shall only be performed when the surface is dry, and the ambient temperature and the pavement surface temperature meet the manufacturer's recommendations in accordance with paragraph 620-2.1. Painting operations shall be discontinued when the ambient or surface temperatures does not meet the manufacturer's recommendations. Markings shall not be applied when the wind speed exceeds 10 mph unless windscreens are used to shroud the material guns. Markings shall not be applied when weather conditions are forecasts to not be within the manufacturers' recommendations for application and dry time.

**620-3.2 Equipment.** Equipment shall include the apparatus necessary to properly clean the existing surface, a mechanical marking machine, a bead dispensing machine, and such auxiliary hand-painting equipment as may be necessary to satisfactorily complete the job.

The mechanical marker shall be an atomizing spray-type or airless type marking machine with automatic glass bead dispensers suitable for application of traffic paint. It shall produce an even and uniform film thickness and appearance of both paint and glass beads at the required coverage and shall apply markings of uniform cross-sections and clear-cut edges without running or spattering and without over spray. The marking equipment for both paint and beads shall be calibrated daily.

**620-3.3 Preparation of surfaces.** Immediately before application of the paint, the surface shall be dry and free from dirt, grease, oil, laitance, or other contaminants that would reduce the bond between the paint and the pavement. Use of any chemicals or impact abrasives during surface preparation shall be approved in advance by the RPR. After the cleaning operations, sweeping, blowing, or rinsing with pressurized water shall be performed to ensure the surface is clean and free of grit or other debris left from the cleaning process.

**a. Preparation of new pavement surfaces.** The area to be painted shall be cleaned by broom, blower, water blasting, or by other methods approved by the RPR to remove all contaminants, including PCC curing compounds, minimizing damage to the pavement surface.

**b. Preparation of pavement to remove existing markings.** Existing pavement markings shall be removed by rotary grinding, water blasting, or by other methods approved by the RPR minimizing damage to the pavement surface. The removal area may need to be larger than the area of the markings to eliminate ghost markings. After removal of markings on asphalt pavements, apply a fog seal or seal coat to 'block out' the removal area to eliminate 'ghost' markings.

**c. Preparation of pavement markings prior to remarking.** Prior to remarking existing markings, loose existing markings must be removed minimizing damage to the pavement surface, with a method approved by the RPR. After removal, the surface shall be cleaned of all residue or debris.

Prior to the application of markings, the Contractor shall certify in writing that the surface is dry and free from dirt, grease, oil, laitance, or other foreign material that would prevent the bond of the paint to the pavement or existing markings. This certification along with a copy of the paint manufacturers application and surface preparation requirements must be submitted to the RPR prior to the initial application of markings.

**620-3.4 Layout of markings.** The proposed markings shall be laid out in advance of the paint application. The locations of markings to receive glass beads shall be shown on the plans.

**620-3.5 Application.** A period of 30 days shall elapse between placement of surface course or seal coat and application of the permanent paint markings. Paint shall be applied at the locations and to the dimensions and spacing shown on the plans. Paint shall not be applied until the layout and condition of the surface has been approved by the RPR.

The edges of the markings shall not vary from a straight line more than 1/2 inch (12 mm) in 50 feet (15 m), and marking dimensions and spacing shall be within the following tolerances:

**Marking Dimensions and Spacing Tolerance**

<b>Dimension and Spacing</b>	<b>Tolerance</b>
36 inch (910 mm) or less	±1/2 inch (12 mm)
greater than 36 inch to 6 feet (910 mm to 1.85 m)	±1 inch (25 mm)
greater than 6 feet to 60 feet (1.85 m to 18.3 m)	±2 inch (50 mm)
greater than 60 feet (18.3 m)	±3 inch (76 mm)

The paint shall be mixed in accordance with the manufacturer's instructions and applied to the pavement with a marking machine at the rate shown in Table 1. The addition of thinner will not be permitted.

Glass beads shall be distributed upon the marked areas at the locations shown on the plans to receive glass beads immediately after application of the paint. A dispenser shall be furnished that is properly designed for attachment to the marking machine and suitable for dispensing glass beads. Glass beads shall be applied at the rate shown in Table 1. Glass beads shall not be applied to black paint or green paint. Glass beads shall adhere to the cured paint or all marking operations shall cease until corrections are made. Different bead types shall not be mixed. Regular monitoring of glass bead embedment and distribution should be performed.

**620-3.6 Application--preformed thermoplastic airport pavement markings.** Preformed thermoplastic pavement markings not used.

**620-3.7 Control strip.** Prior to the full application of airfield markings, the Contractor shall prepare a control strip in the presence of the RPR. The Contractor shall demonstrate the surface preparation method and all striping equipment to be used on the project. The marking equipment must achieve the prescribed application rate of paint and population of glass beads (per Table 1) that are properly embedded and evenly distributed across the full width of the marking. Prior to acceptance of the control strip, markings must be evaluated during darkness to ensure a uniform appearance.

**620-3.8 Retro-reflectance.** Reflectance shall be measured with a portable retro-reflectometer meeting ASTM E1710 (or equivalent). A total of 6 reading shall be taken over a 6 square foot area with 3



readings taken from each direction. The average shall be equal to or above the minimum levels of all readings which are within 30% of each other.

#### Minimum Retro-Reflectance Values

Material	Retro-reflectance mcd/m <sup>2</sup> /lux		
	White	Yellow	Red
Initial Type I	300	175	35
Initial Type III	600	300	35
Initial Thermoplastic	225	100	35
All materials, remark when less than <sup>1</sup>	100	75	10

<sup>1</sup> Prior to remarking determine if removal of contaminants on markings will restore retro-reflectance

**620-3.9 Protection and cleanup.** After application of the markings, all markings shall be protected from damage until dry. All surfaces shall be protected from excess moisture and/or rain and from disfiguration by spatter, splashes, spillage, or drippings. The Contractor shall remove from the work area all debris, waste, loose reflective media, and by-products generated by the surface preparation and application operations to the satisfaction of the RPR. The Contractor shall dispose of these wastes in strict compliance with all applicable state, local, and federal environmental statutes and regulations.

#### METHOD OF MEASUREMENT

**620-4.1a** The quantity of marking removal to be paid for shall be measured by the number of square feet of removal.

**620-4.1b** The quantity of final markings shall be paid for shall be measured by the number of square feet of painting.

**620-4.1c** The quantity of reflective media shall be incidental to the quantity of markings.

**620-4.1d** The quantity of temporary markings to be paid for shall be the number of square feet of painting performed in accordance with the specifications and accepted by the RPR. Temporary marking includes surface preparation, application and complete removal of the temporary marking.

#### BASIS OF PAYMENT

**620-5.1** This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item complete in place and accepted by the RPR in accordance with these specifications.

**620-5.1a** Payment for marking removal shall be made at the contract price for the number of square feet of removal. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item.

**620-5.2b** Payment for final marking shall be made at the contract price for the number of square feet of painting. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item.

**620-5.4c** Payment for temporary markings shall be made at the contract price for the number of square feet of painting. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item. Unit price also includes removal of any temporary markings.

Payment will be made under:

Item P-620-5.1	Pavement Marking Removal – per square foot
Item P-620-5.2	Final Marking – per square foot
Item P-620-5.3	Temporary Marking – per square foot

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### ASTM International (ASTM)

ASTM D476	Standard Classification for Dry Pigmentary Titanium Dioxide Products
ASTM D968	Standard Test Methods for Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM D1652	Standard Test Method for Epoxy Content of Epoxy Resins
ASTM D2074	Standard Test Method for Total, Primary, Secondary, and Tertiary Amine Values of Fatty Amines by Alternative Indicator Method
ASTM D2240	Standard Test Method for Rubber Property - Durometer Hardness
ASTM D7585	Standard Practice for Evaluating Retroreflective Pavement Markings Using Portable Hand-Operated Instruments
ASTM E303	Standard Test Method for Measuring Surface Frictional Properties Using the British Pendulum Tester
ASTM E1710	Standard Test Method for Measurement of Retroreflective Pavement Marking Materials with CEN-Prescribed Geometry Using a Portable Retroreflectometer
ASTM E2302	Standard Test Method for Measurement of the Luminance Coefficient Under Diffuse Illumination of Pavement Marking Materials Using a Portable Reflectometer
ASTM G154	Standard Practice for Operating Fluorescent Ultraviolet (UV) Lamp Apparatus for Exposure of Nonmetallic Materials

### Code of Federal Regulations (CFR)

40 CFR Part 60, Appendix A-7, Method 24	Determination of volatile matter content, water content, density, volume solids, and weight solids of surface coatings
29 CFR Part 1910.1200 Hazard Communication	

Federal Specifications (FED SPEC)

FED SPEC TT-B-1325D	Beads (Glass Spheres) Retro-Reflective
FED SPEC TT-P-1952F	Paint, Traffic and Airfield Marking, Waterborne
FED STD 595	Colors used in Government Procurement

Commercial Item Description

A-A-2886B	Paint, Traffic, Solvent Based
-----------	-------------------------------

Advisory Circulars (AC)

AC 150/5340-1	Standards for Airport Markings
AC 150/5320-12	Measurement, Construction, and Maintenance of Skid Resistant Airport Pavement Surfaces

**END OF ITEM P-620**

## Item D-701 Pipe for Storm Drains and Culverts

### DESCRIPTION

**701-1.1** This item shall consist of the construction of pipe culverts and storm drains in accordance with these specifications and in reasonably close conformity with the lines and grades shown on the plans.

### MATERIALS

**701-2.1** Materials shall meet the requirements shown on the plans and specified below. Underground piping and components used in drainage systems for terminal and aircraft fueling ramp drainage shall be noncombustible and inert to fuel in accordance with National Fire Protection Association (NFPA) 415.

**701-2.2 Pipe.** The pipe shall be of the type called for on the plans or in the proposal and shall be in accordance with the following appropriate requirements:

AASHTO R73	Standard Practice for Evaluation of Precast Concrete Drainage Productions
ASTM C76	Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
ASTM C506	Standard Specification for Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe
ASTM C507	Standard Specification for Reinforced Concrete Elliptical Culvert, Storm Drain, and Sewer Pipe
ASTM C655	Standard Specification for Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe
ASTM C1433	Standard Specification for Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains, and Sewers
ASTM C1479	Standard Practice for Installation of Precast Concrete Sewer, Storm Drain, and Culvert Pipe Using Standard Installations
ASTM C1577	Standard Specification for Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains, and Sewers Designed According to AASHTO LRFD

**701-2.3 Concrete.** Concrete for pipe cradles shall have a minimum compressive strength of 2000 psi (13.8 MPa) at 28 days and conform to the requirements of ASTM C94.

**701-2.4 Rubber gaskets.** Rubber gaskets for rigid pipe shall conform to the requirements of ASTM C443.

**701-2.5 Joint mortar.** Pipe joint mortar shall consist of one part Portland cement and two parts sand. The Portland cement shall conform to the requirements of ASTM C150, Type I. The sand shall conform to the requirements of ASTM C144.

**701-2.6 Joint fillers.** Poured filler for joints shall conform to the requirements of ASTM D6690.

**701-2.7 Plastic gaskets.** Not used.

**701-2.8. Controlled low-strength material (CLSM).** Not used.

**701-2.9 Precast box culverts.** Manufactured in accordance with and conforming to ASTM C1433.

**701-2.10 Precast concrete pipe.** Precast concrete structures shall be furnished by a plant meeting National Precast Concrete Association Plant Certification Program or American Concrete Pipe Association QCast Plant Certification program.

## CONSTRUCTION METHODS

**701-3.1 Excavation.** The width of the pipe trench shall be sufficient to permit satisfactory jointing of the pipe and thorough tamping of the bedding material under and around the pipe, but it shall not be less than the external diameter of the pipe plus 12 inches (300 mm) on each side. The trench walls shall be approximately vertical.

The Contractor shall comply with all current federal, state and local rules and regulations governing the safety of men and materials during the excavation, installation and backfilling operations. Specifically, the Contractor shall observe that all requirements of the Occupational Safety and Health Administration (OSHA) relating to excavations, trenching and shoring are strictly adhered to. The width of the trench shall be sufficient to permit satisfactorily jointing of the pipe and thorough compaction of the bedding material under the pipe and backfill material around the pipe, but it shall not be greater than the widths shown on the plans trench detail.

Where rock, hardpan, or other unyielding material is encountered, the Contractor shall remove it from below the foundation grade for a depth of at least 8 inch (200 mm) or 1/2 inch (12 mm) for each foot of fill over the top of the pipe (whichever is greater) but for no more than three-quarters of the nominal diameter of the pipe. The excavation below grade should be filled with granular material to form a uniform foundation.

Where a firm foundation is not encountered at the grade established, due to soft, spongy, or other unstable soil, the unstable soil shall be removed and replaced with approved granular material for the full trench width. The RPR shall determine the depth of removal necessary. The granular material shall be compacted to provide adequate support for the pipe.

The excavation for pipes placed in embankment fill shall not be made until the embankment has been completed to a height above the top of the pipe as shown on the plans.

**701-3.2 Bedding.** The bedding surface for the pipe shall provide a foundation of uniform density to support the pipe throughout its entire length.

**a. Rigid pipe.** The pipe bedding shall be constructed uniformly for the full length of the pipe barrel, as required on the plans. The maximum aggregate size shall be 1 in when the bedding thickness is less than 6 inches, and 1-1/2 in when the bedding thickness is greater than 6 inches. Bedding shall be loosely placed uncompacted material under the middle third of the pipe prior to placement of the pipe.

**b. Flexible pipe.** ~~Not Used. For flexible pipe, the bed shall be roughly shaped to fit the pipe, and a bedding blanket of sand or fine granular material shall be provided as follows:~~

### Flexible Pipe Bedding

Pipe Corrugation Depth		Minimum Bedding Depth	
inch	mm	inch	mm
1/2	12	1	25
1	25	2	50
2	50	3	75
2-1/2	60	3-1/2	90

**c. Other pipe materials.** ~~Not Used.~~ For PVC, polyethylene, polypropylene, or fiberglass pipe, the bedding material shall consist of coarse sands and gravels with a maximum particle size of 3/4 inches (19 mm). For pipes installed under paved areas, no more than 12% of the material shall pass the No. 200 (0.075 mm) sieve. For all other areas, no more than 50% of the material shall pass the No. 200 (0.075 mm) sieve. The bedding shall have a thickness of at least 6 inches (150 mm) below the bottom of the pipe and extend up around the pipe for a depth of not less than 50% of the pipe's vertical outside diameter.

**701-3.3 Laying pipe.** The pipe laying shall begin at the lowest point of the trench and proceed upgrade. The lower segment of the pipe shall be in contact with the bedding throughout its full length. Bell or groove ends of rigid pipes and outside circumferential laps of flexible pipes shall be placed facing upgrade.

Paved or partially lined pipe shall be placed so that the longitudinal center line of the paved segment coincides with the flow line.

Elliptical and elliptically reinforced concrete pipes shall be placed with the manufacturer's reference lines designating the top of the pipe within five degrees of a vertical plane through the longitudinal axis of the pipe.

**701-3.4 Joining pipe.** Joints shall be made with (1) cement mortar, (2) cement grout, or (3) preformed flexible joint sealant. (3) rubber gaskets, (4) plastic gaskets, or (5) coupling bands.

Mortar joints shall be made with an excess of mortar to form a continuous bead around the outside of the pipe and shall be finished smooth on the inside. Molds or runners shall be used for grouted joints to retain the poured grout. Rubber ring gaskets shall be installed to form a flexible watertight seal.

**a. Concrete pipe.** Concrete pipe may be either bell and spigot or tongue and groove. Pipe sections at joints shall be fully seated and the inner surfaces flush and even. Concrete pipe joints shall be sealed with ~~butyl mastic~~ preformed flexible joint sealant meeting ASTM C990 or mortar when soil tight joints are required. Joints shall be thoroughly wetted before applying mortar or grout.

**b. Metal pipe.** ~~Not Used.~~ Metal pipe shall be firmly joined by form fitting bands conforming to the requirements of ASTM A760 for steel pipe and AASHTO M196 for aluminum pipe.

**c. PVC, Polyethylene, or Polypropylene pipe.** ~~Not Used.~~ Joints for PVC, Polyethylene, or Polypropylene pipe shall conform to the requirements of ASTM D3212 when leak resistant joints are required. Joints for PVC and Polyethylene pipe shall conform to the requirements of AASHTO M304 when soil tight joints are required. Fittings for polyethylene pipe shall conform to the requirements of AASHTO M252 or ASTM M294. Fittings for polypropylene pipe shall conform to ASTM F2881, ASTM F2736, or ASTM F2764.

**d. Fiberglass pipe.** ~~Not Used.~~ Joints and fittings shall be as detailed on the plans and in accordance with the manufacturers recommendations.

**701-3.5 Embedment and Overfill.** Pipes shall be inspected before any fill material is placed; any pipes found to be out of alignment, unduly settled, or damaged shall be removed and re-laid or replaced at the Contractor's expense.

#### **701-3.5-1 Embedment Material Requirements**

**a. Concrete Pipe.** Embedment material and compaction requirements shall be in accordance with the applicable Type of Standard Installation (Types 1, 2, 3, or 4) per ASTM C1479. ~~If a concrete cradle or CLSM embedment material is used, it shall conform to the plan details.~~

**b. Plastic and fiberglass Pipe.** ~~Not Used. Embedment material shall meet the requirements of ASTM D3282, A 1, A 2-4, A 2-5, or A 3. Embedment material shall be free of organic material, stones larger than 1.5 inches in the greatest dimension, or frozen lumps. Embedment material shall extend to 12 inches above the top of the pipe.~~

**c. Metal Pipe.** ~~Not Used. Embedment material shall be granular as specified in the contract document and specifications, and shall be free of organic material, rock fragments larger than 1.5 inches in the greatest dimension and frozen lumps. As a minimum, backfill materials shall meet the requirements of ASTM D3282, A 1, A 2, or A 3. Embedment material shall extend to 12 inches above the top of the pipe.~~

#### **701-3.5-2 Placement of Embedment Material**

The embedment material shall be compacted in layers not exceeding 6 inches (150 mm) on each side of the pipe and shall be brought up one foot (30 cm) above the top of the pipe or to natural ground level, whichever is greater. Thoroughly compact the embedment material under the haunches of the pipe without displacing the pipe. Material shall be brought up evenly on each side of the pipe for the full length of the pipe.

When the top of the pipe is above the top of the trench, the embedment material shall be compacted in layers not exceeding 6 inches (150 mm) and shall be brought up evenly on each side of the pipe to one foot (30 cm) above the top of the pipe. All embedment material shall be compacted to a density required under Item P-152.

Concrete cradles and flowable fills, such as controlled low strength material (CLSM) or controlled density fill (CDF), may be used for embedment provided adequate flotation resistance can be achieved by restraints, weighing, or placement technique.

It shall be the Contractor's responsibility to protect installed pipes and culverts from damage due to construction equipment operations. The Contractor shall be responsible for installation of any extra strutting or backfill required to protect pipes from the construction equipment.

#### **701-3.6 Overfill**

Pipes shall be inspected before any overfill is in place. Any pipes found to be out of alignment, unduly settled, or damaged shall be removed and relaid or replaced at the Contractor's expense. Evaluation of any damage to RCP shall be evaluated based on AASHTO R73.

Overfill material shall be placed and compacted in layers as required to achieve compaction to at least 95 percent standard proctor per ASTM D1557. The soil shall contain no debris, organic matter, frozen material, or stones with a diameter greater than one half the thickness of the compacted layers being placed.

#### **701-3.7 Inspection Requirements**

An initial post installation inspection shall be performed by the RPR no sooner than 30 days after completion of installation and final backfill. Clean or flush all lines prior to inspection.

Use a camera with lighting suitable to allow a clear picture of the entire periphery of the pipe interior. Center the camera in the pipe both vertically and horizontally and be able to pan and tilt to a 90 degree angle with the axis of the pipe rotating 360 degrees. Use equipment to move the camera through the pipe that will not obstruct the camera's view or interfere with proper documentation of the pipe's condition. The video image shall be clear, focused, and relatively free from roll, static, or other image distortion qualities that would prevent the reviewer from evaluating the condition of the pipe.

Incorporate specific inspection requirements for the various types of pipes beneath the general inspection requirements.

Reinforced concrete pipe shall be inspected, evaluated, and reported on in accordance with ASTM C1840, "Standard Practice for Inspection and Acceptance of Installed Reinforced Concrete Culvert, Storm Drain, and Storm Sewer Pipe." Any issues reported shall include still photo and video documentation. The zoom ratio shall be provided for all still or video images that document any issues of concern by the inspection firm.

### METHOD OF MEASUREMENT

**701-4.1** The length of pipe shall be measured in linear feet (m) of pipe in place, completed, and accepted. It shall be measured along the centerline of the pipe from end or inside face of structure to the end or inside face of structure, whichever is applicable. [The pipes shall be measured by the linear foot of the pay items identified in 701-5.1 and shall be measured separately.](#) All fittings shall be included in the footage as typical pipe sections in the pipe being measured.

**701-4.2** Bedding material shall be incidental to the linear foot of pipe installed and shall not be measured separately for payment.

**701-4.3** Joint material shall be incidental to the linear foot of pipe installed and shall not be measured separately for payment.

**701-4.4** The volume of rock, foundation soft or yielding, or otherwise unsuitable material shall be [incidental to the removal of pipe, see Item 152-5.4 in P-152 Excavation, Subgrade, and Embankment specification.](#)

### BASIS OF PAYMENT

**701-5.0** These prices shall fully compensate the Contractor for furnishing all materials and for all preparation, excavation, and installation of these materials; and for all labor, equipment, tools, and incidentals necessary to complete the item.

**701-5.1** Payment will be made at the contract unit price per linear foot for the pay items listed below.

Payment will be made under:

Item 701-5.1	18-inch Class V RCP – per linear foot
Item 701-5.2	24-inch Class V RCP – per linear foot
Item 701-5.3	Aircraft Rated Pipe Collar, 18-inch – per each
Item 701-5.4	Aircraft Rated Pipe Collar, 24-inch – per each



## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

### American Association of State Highway and Transportation Officials (AASHTO)

AASHTO M167	Standard Specification for Corrugated Steel Structural Plate, Zinc-Coated, for Field-Bolted Pipe, Pipe-Arches, and Arches
AASHTO M190	Standard Specification for Bituminous-Coated Corrugated Metal Culvert Pipe and Pipe Arches
AASHTO M196	Standard Specification for Corrugated Aluminum Pipe for Sewers and Drains
AASHTO M219	Standard Specification for Corrugated Aluminum Alloy Structural Plate for Field-Bolted Pipe, Pipe-Arches, and Arches
AASHTO M243	Standard Specification for Field Applied Coating of Corrugated Metal Structural Plate for Pipe, Pipe-Arches, and Arches
AASHTO M252	Standard Specification for Corrugated Polyethylene Drainage Pipe
AASHTO M294	Standard Specification for Corrugated Polyethylene Pipe, 300- to 1500-mm (12- to 60-in.) Diameter
AASHTO M304	Standard Specification for Poly (Vinyl Chloride) (PVC) Profile Wall Drain Pipe and Fittings Based on Controlled Inside Diameter
AASHTO MP20	Standard Specification for Steel Reinforced Polyethylene (PE) Ribbed Pipe, 300- to 900-mm (12- to 36-in.) Diameter

### ASTM International (ASTM)

ASTM A760	Standard Specification for Corrugated Steel Pipe, Metallic Coated for Sewers and Drains
ASTM A761	Standard Specification for Corrugated Steel Structural Plate, Zinc Coated, for Field-Bolted Pipe, Pipe-Arches, and Arches
ASTM A762	Standard Specification for Corrugated Steel Pipe, Polymer Precoated for Sewers and Drains
ASTM A849	Standard Specification for Post-Applied Coatings, Pavings, and Linings for Corrugated Steel Sewer and Drainage Pipe
ASTM B745	Standard Specification for Corrugated Aluminum Pipe for Sewers and Drains
ASTM C14	Standard Specification for Nonreinforced Concrete Sewer, Storm Drain, and Culvert Pipe
ASTM C76	Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
ASTM C94	Standard Specification for Ready Mixed Concrete
ASTM C144	Standard Specification for Aggregate for Masonry Mortar
ASTM C150	Standard Specification for Portland Cement

ASTM C443	Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
ASTM C506	Standard Specification for Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe
ASTM C507	Standard Specification for Reinforced Concrete Elliptical Culvert, Storm Drain and Sewer Pipe
ASTM C655	Standard Specification for Reinforced Concrete D-Load Culvert, Storm Drain and Sewer Pipe
ASTM C990	Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants
ASTM C1433	Standard Specification for Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains, and Sewers
ASTM D1056	Standard Specification for Flexible Cellular Materials Sponge or Expanded Rubber
ASTM D3034	Standard Specification for Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings
ASTM D3212	Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D3262	Standard Specification for "Fiberglass" (Glass-Fiber Reinforced Thermosetting Resin) Sewer Pipe
ASTM D3282	Standard Practice for Classification of Soils and Soil-Aggregate Mixtures for Highway Construction Purposes
ASTM D4161	Standard Specification for "Fiberglass" (Glass-Fiber Reinforced Thermosetting Resin) Pipe Joints Using Flexible Elastomeric Seals
ASTM D6690	Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements
ASTM F477	Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F667	Standard Specification for 3 through 24 in. Corrugated Polyethylene Pipe and Fittings
ASTM F714	Standard Specification for Polyethylene (PE) Plastic Pipe (DR PR) Based on Outside Diameter
ASTM F794	Standard Specification for Poly (Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe & Fittings Based on Controlled Inside Diameter
ASTM F894	Standard Specification for Polyethylene (PE) Large Diameter Profile Wall Sewer and Drain Pipe
ASTM F949	Standard Specification for Poly (Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings
ASTM F2435	Standard Specification for Steel Reinforced Polyethylene (PE) Corrugated Pipe

ASTM F2562	Specification for Steel Reinforced Thermoplastic Ribbed Pipe and Fittings for Non-Pressure Drainage and Sewerage
ASTM F2736	Standard Specification for 6 to 30 in. (152 to 762 mm) Polypropylene (PP) Corrugated Single Wall Pipe and Double Wall Pipe
ASTM F2764	Standard Specification for 30 to 60 in. (750 to 1500 mm) Polypropylene (PP) Triple Wall Pipe and Fittings for Non-Pressure Sanitary Sewer Applications
ASTM F2881	Standard Specification for 12 to 60 in. (300 to 1500 mm) Polypropylene (PP) Dual Wall Pipe and Fittings for Non-Pressure Storm Sewer Applications

National Fire Protection Association (NFPA)

NFPA 415	Standard on Airport Terminal Buildings, Fueling Ramp Drainage, and Loading Walkways
----------	---

**END ITEM D-701**

## Item D-751 Manholes, Catch Basins, Inlets and Inspection Holes

### DESCRIPTION

**751-1.1** This item shall consist of construction of manholes, catch basins, inlets, and inspection holes, in accordance with these specifications, at the specified locations and conforming to the lines, grades, and dimensions shown on the plans or required by the RPR.

### MATERIALS

**751-2.1 Brick.** Not Used. ~~The brick shall conform to the requirements of ASTM C32, Grade MS.~~

**751-2.2 Mortar.** Mortar shall consist of one part Portland cement and two parts sand. The cement shall conform to the requirements of ASTM C150, Type I. The sand shall conform to the requirements of ASTM C144.

**751-2.3 Concrete.** Plain and reinforced concrete used in structures, connections of pipes with structures, and the support of structures or frames shall conform to the requirements of Item P-610.

**751-2.4 Precast concrete pipe manhole rings.** Precast concrete pipe manhole rings shall conform to the requirements of ASTM C478. Unless otherwise specified, the risers and offset cone sections shall have an inside diameter of not less than 36 inches (90 cm) nor more than 48 inches (120 cm). There shall be a gasket between individual sections and sections cemented together with mortar on the inside of the manhole. Gaskets shall conform to the requirements of ASTM C443.

**751-2.5 Corrugated metal.** Corrugated metal shall conform to the requirements of American Association of State Highway and Transportation Officials (AASHTO) M36.

**751-2.6 Frames, covers, and grates.** The castings shall conform to one of the following requirements:

- a. ASTM A48, Class 35B: Gray iron castings
- b. ASTM A47: Malleable iron castings
- c. ASTM A27: Steel castings
- d. ASTM A283, Grade D: Structural steel for grates and frames
- e. ASTM A536, Grade 65-45-12: Ductile iron castings
- f. ASTM A897: Austempered ductile iron castings

All castings or structural steel units shall conform to the dimensions shown on the plans and shall be designed to support the loadings, aircraft gear configuration and/or direct loading, specified.

Each frame and cover or grate unit shall be provided with fastening members to prevent it from being dislodged by traffic but which will allow easy removal for access to the structure.

All castings shall be thoroughly cleaned. After fabrication, structural steel units shall be galvanized to meet the requirements of ASTM A123.

**751-2.7 Steps.** The steps or ladder bars shall be gray or malleable cast iron or galvanized steel. The steps shall be the size, length, and shape shown on the plans and those steps that are not galvanized shall be given a coat of asphalt paint, when directed.

**751-2.8 Precast inlet structures.** Manufactured in accordance with and conforming to ASTM C913.

## CONSTRUCTION METHODS

### 751-3.1 Unclassified excavation.

**a.** The Contractor shall excavate for structures and footings to the lines and grades or elevations, shown on the plans, or as staked by the RPR. The excavation shall be of sufficient size to permit the placing of the full width and length of the structure or structure footings shown. The elevations of the bottoms of footings, as shown on the plans, shall be considered as approximately only; and the RPR may direct, in writing, changes in dimensions or elevations of footings necessary for a satisfactory foundation.

**b.** Boulders, logs, or any other objectionable material encountered in excavation shall be removed. All rock or other hard foundation material shall be cleaned of all loose material and cut to a firm surface either level, stepped, or serrated, as directed by the RPR. All seams or crevices shall be cleaned out and grouted. All loose and disintegrated rock and thin strata shall be removed. Where concrete will rest on a surface other than rock, the bottom of the excavation shall not be disturbed and excavation to final grade shall not be made until immediately before the concrete or reinforcing is placed.

**c.** The Contractor shall do all bracing, sheathing, or shoring necessary to implement and protect the excavation and the structure as required for safety or conformance to governing laws. The cost of bracing, sheathing, or shoring shall be included in the unit price bid for the structure.

**d.** All bracing, sheathing, or shoring involved in the construction of this item shall be removed by the Contractor after the completion of the structure. Removal shall not disturb or damage finished masonry. The cost of removal shall be included in the unit price bid for the structure.

**e.** After excavation is completed for each structure, the Contractor shall notify the RPR. No concrete or reinforcing steel shall be placed until the RPR has approved the depth of the excavation and the character of the foundation material.

### 751-3.2 Brick structures. ~~Not Used.~~

**a. Foundations.** ~~A prepared foundation shall be placed for all brick structures after the foundation excavation is completed and accepted. Unless otherwise specified, the base shall consist of reinforced concrete mixed, prepared, and placed in accordance with the requirements of Item P-610.~~

**b. Laying brick.** ~~All brick shall be clean and thoroughly wet before laying so that they will not absorb any appreciable amount of additional water at the time they are laid. All brick shall be laid in freshly made mortar. Mortar not used within 45 minutes after water has been added shall be discarded. Retempering of mortar shall not be permitted. An ample layer of mortar shall be spread on the beds and a shallow furrow shall be made in it that can be readily closed by the laying of the brick. All bed and head joints shall be filled solid with mortar. End joints of stretchers and side or cross joints of headers shall be fully buttered with mortar and a shoved joint made to squeeze out mortar at the top of the joint. Any bricks that may be loosened after the mortar has taken its set, shall be removed, cleaned, and re-laid with fresh mortar. No broken or chipped brick shall be used in the face, and no spalls or bats shall be used except where necessary to shape around irregular openings or edges; in which case, full bricks shall be placed at ends or corners where possible, and the bats shall be used in the interior of the course. In making closures, no piece of brick shorter than the width of a whole brick shall be used; and wherever practicable, whole brick shall be used and laid as headers.~~

**c. Joints.** ~~All joints shall be filled with mortar at every course. Exterior faces shall be laid up in advance of backing. Exterior faces shall be plastered or parged with a coat of mortar not less than 3/8 inch (9 mm) thick before the backing is laid up. Prior to parging, all joints on the back of face courses shall be~~

cut flush. Unless otherwise noted, joints shall be not less than 1/4 inch (6 mm) nor more than 1/2 inch (12 mm) wide and the selected joint width shall be maintained uniform throughout the work.

**d. Pointing.** Face joints shall be neatly struck, using the weather struck joint. All joints shall be finished properly as the laying of the brick progresses. When nails or line pins are used, the holes shall be immediately plugged with mortar and pointed when the nail or pin is removed.

**e. Cleaning.** Upon completion of the work all exterior surfaces shall be thoroughly cleaned by scrubbing and washing with water. If necessary to produce satisfactory results, cleaning shall be done with a 5% solution of muriatic acid which shall then be rinsed off with liberal quantities of water.

**f. Curing and cold weather protection.** The brick masonry shall be protected and kept moist for at least 48 hours after laying the brick. Brick masonry work or pointing shall not be done when there is frost on the brick or when the air temperature is below 50°F (10°C) unless the Contractor has, on the project ready to use, suitable covering and artificial heating devices necessary to keep the atmosphere surrounding the masonry at a temperature of not less than 60°F (16°C) for the duration of the curing period.

**751-3.3 Concrete structures.** Concrete structures which are to be cast-in-place within the project boundaries shall be built on prepared foundations, conforming to the dimensions and shape indicated on the plans. The construction shall conform to the requirements specified in Item P-610. Any reinforcement required shall be placed as indicated on the plans and shall be approved by the RPR before the concrete is placed.

All invert channels shall be constructed and shaped accurately to be smooth, uniform, and cause minimum resistance to flowing water. The interior bottom shall be sloped to the outlet.

**751-3.4 Precast concrete structures.** Precast concrete structures shall be furnished by a plant meeting National Precast Concrete Association Plant Certification Program or another RPR approved third party certification program.

Precast concrete structures shall conform to ASTM C478. Precast concrete structures shall be constructed on prepared or previously placed slab foundations conforming to the dimensions and locations shown on the plans. All precast concrete sections necessary to build a completed structure shall be furnished. The different sections shall fit together readily. Joints between precast concrete risers and tops shall be full-bedded in cement mortar and shall: (1) be smoothed to a uniform surface on both interior and exterior of the structure or (2) utilize a rubber gasket per ASTM C443. The top of the upper precast concrete section shall be suitably formed and dimensioned to receive the metal frame and cover or grate, or other cap, as required. Provision shall be made for any connections for lateral pipe, including drops and leads that may be installed in the structure. The flow lines shall be smooth, uniform, and cause minimum resistance to flow. The metal or metal encapsulated steps that are embedded or built into the side walls shall be aligned and placed in accordance to ASTM C478. When a metal ladder replaces the steps, it shall be securely fastened into position.

**751-3.5 Corrugated metal structures.** ~~Not Used.~~ Corrugated metal structures shall be prefabricated. All standard or special fittings shall be furnished to provide pipe connections or branches with the correct dimensions and of sufficient length to accommodate connecting bands. The fittings shall be welded in place to the metal structures. The top of the metal structure shall be designed so that either a concrete slab or metal collar may be attached to allow the fastening of a standard metal frame and grate or cover. Steps or ladders shall be furnished as shown on the plans. Corrugated metal structures shall be constructed on prepared foundations, conforming to the dimensions and locations as shown on the plans. When indicated, the structures shall be placed on a reinforced concrete base.

**751-3.6 Inlet and outlet pipes.** Inlet and outlet pipes shall extend through the walls of the structures a sufficient distance beyond the outside surface to allow for connections. They shall be cut off flush with

the wall on the inside surface of the structure, unless otherwise directed. For concrete or brick structures, mortar shall be placed around these pipes to form a tight, neat connection.

**751-3.7 Placement and treatment of castings, frames, and fittings.** All castings, frames, and fittings shall be placed in the positions indicated on the plans or as directed by the RPR, and shall be set true to line and elevation. If frames or fittings are to be set in concrete or cement mortar, all anchors or bolts shall be in place before the concrete or mortar is placed. The unit shall not be disturbed until the mortar or concrete has set.

When frames or fittings are placed on previously constructed masonry, the bearing surface of the masonry shall be brought true to line and grade and shall present an even bearing surface so the entire face or back of the unit will come in contact with the masonry. The unit shall be set in mortar beds and anchored to the masonry as indicated on the plans or as directed by the RPR. All units shall set firm and secure.

After the frames or fittings have been set in final position, the concrete or mortar shall be allowed to harden for seven (7) days before the grates or covers are placed and fastened down.

**751-3.8 Installation of steps.** The steps shall be installed as indicated on the plans or as directed by the RPR. When the steps are to be set in concrete, they shall be placed and secured in position before the concrete is placed. When the steps are installed in brick masonry, they shall be placed as the masonry is being built. The steps shall not be disturbed or used until the concrete or mortar has hardened for at least seven (7) days. After seven (7) days, the steps shall be cleaned and painted, unless they have been galvanized.

When steps are required with precast concrete structures they shall meet the requirements of ASTM C478. The steps shall be cast into the side of the sections at the time the sections are manufactured or set in place after the structure is erected by drilling holes in the concrete and cementing the steps in place.

When steps are required with corrugated metal structures, they shall be welded into aligned position at a vertical spacing of 12 inches (300 mm).

Instead of steps, prefabricated ladders may be installed. For brick or concrete structures, the ladder shall be held in place by grouting the supports in drilled holes. For metal structures, the ladder shall be secured by welding the top support to the structure and grouting the bottom support into drilled holes in the foundation or as directed by the RPR.

### **751-3.9 Backfilling.**

**a.** After a structure has been completed, the area around it shall be backfilled with approved material, in horizontal layers not to exceed 8 inches (200 mm) in loose depth, and compacted to the density required in Item P-152. Each layer shall be deposited evenly around the structure to approximately the same elevation. The top of the fill shall meet the elevation shown on the plans or as directed by the RPR.

**b.** Backfill shall not be placed against any structure until approved by the RPR. For concrete structures, approval shall not be given until the concrete has been in place seven (7) days, or until tests establish that the concrete has attained sufficient strength to withstand any pressure created by the backfill and placing methods.

**c.** Backfill shall not be measured for direct payment. Performance of this work shall be considered an obligation of the Contractor covered under the contract unit price for the structure involved.

**751-3.10 Cleaning and restoration of site.** After the backfill is completed, the Contractor shall dispose of all surplus material, dirt, and rubbish from the site. Surplus dirt may be deposited in embankments, shoulders, or as approved by the RPR. The Contractor shall restore all disturbed areas to their original condition. The Contractor shall remove all tools and equipment, leaving the entire site free, clear, and in good condition.

## METHOD OF MEASUREMENT

**751-4.1** Manholes, catch basins, inlets, and inspection holes shall be measured by the unit.

## BASIS OF PAYMENT

**751-5.1** The accepted quantities of manholes, catch basins, inlets, and inspection holes will be paid for at the contract unit price per each in place when completed. This price shall be full compensation for furnishing all materials and for all preparation, excavation, backfilling and placing of the materials; furnishing and installation of such specials and connections to pipes and other structures as may be required to complete the item as shown on the plans; and for all labor equipment, tools and incidentals necessary to complete the structure.

Payment will be made under:

Item D-751-5.1	Aircraft Rated Inlet – per each
----------------	---------------------------------

## REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM A27	Standard Specification for Steel Castings, Carbon, for General Application
ASTM A47	Standard Specification for Ferritic Malleable Iron Castings
ASTM A48	Standard Specification for Gray Iron Castings
ASTM A123	Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A283	Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates
ASTM A536	Standard Specification for Ductile Iron Castings
ASTM A897	Standard Specification for Austempered Ductile Iron Castings
ASTM C32	Standard Specification for Sewer and Manhole Brick (Made from Clay or Shale)
ASTM C144	Standard Specification for Aggregate for Masonry Mortar
ASTM C150	Standard Specification for Portland Cement
ASTM C443	Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets.
ASTM C478	Standard Specification for Precast Reinforced Concrete Manhole Sections
ASTM C913	Standard Specification for Precast Concrete Water and Wastewater Structures.



American Association of State Highway and Transportation Officials (AASHTO)

AASHTO M36

Standard Specification for Corrugated Steel Pipe, Metallic-Coated, for  
Sewers and Drains

**END OF ITEM D-751**